# AMAZON BASE BUILDING COMPLIANCE STANDARD

| | |
|---|---|
| **Task Title** | Staircase pressurisation |
| **APM Object** | CT.FIRE.STAIRCASE |
| **APM Description** | Staircase pressurisation system. |
| **General tasks always required** | Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc.<br>Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required<br>Add notes for each observation and create a FWO if necessary to eliminate defects<br>Use appropriate tools, chemicals and industry standard practices (RME policy permitting)<br>Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure. CT evidence must be additionally uploaded to the DMS (WorkDocs in DE)<br>To suggest improvements please raise a SIM or contact document authors<br>Leonardo Vitale (LEOVITAL) Rob Gisby (EWARTGXR) or APM, Benito Sanchez Sanchez de Puerta (BPPUERTA)<br>SIM - Link to SIM template |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| **Last Update: (Version)** | abr-24 | **Last Update Change Detail:** | PM evidence changed from 3M to 12M. | **Activities may be covered by No-Go restrictions:** | Yes | **Special Certification Required:** | **Delivered By:** |
| **Evidenced part or full by PM:** | Not Specified | **Related BBM PM:** | FIRE.SUP.SMOKEHEATVENT | **Related CT Areas:** | CT.FIRE.SMOKEVENTS | | |

## Scope

Any site where fire dampers are used to prevent fire (when occurring) from escaping the room where it originated through ducting vents.

## Using this document

This document is intended as a guide and may not be exhaustive. Whilst this document is based extensively on professional guidance and subject to periodic review, individual sites must be diligent to ensure they are aware of, and comply to, local and changing regulations.
The format of these standards is intended to improve navigation between maintenance and compliance standards and to allow frequent, minor updates to a single living resource. Please avoid offline or printed versions and check version dates and change log.
In the event of becoming aware of errors or omissions in this document, sites must provide detail, including references to relevant source information to their local planner for escalation - SIM Link above.
This document is considered released as draft.
For Information contact Authors: R Gisby (ewartgxr), Leonardo Vitale (leovital) and Benito Sanchez Sanchez de Puerta (bppuerta)

## Maintenance and Compliance Relationship

Where relevant, associated Base Building PM's are listed on the header . In many cases maintenance contributes to, or fulfils compliance requirement. This may not be exhaustive and is intended to assist users to identify relevant maintenance.
If a BBM Maintenance activity fully meets the compliance requirements below, periodic upload of PM evidence will be required to APM and DMS / Workdays depending on region.

## Key to Abbreviations

The key to the below document is as follows:
**CT** - Amazon compliance / statutory task - not otherwise covered by a BBM Standard PM. Evidence to be provided into APM and DMS upon task closure.
**CT*** - This is a conditional task based or based on findings from previous inspections. If a frequency is not used, a further appropriate frequency needs to be in either the region, or 'ALL'. Local teams must ensure appropriate frequency.
**(CT)** - Compliance task which is likely met or exceeded by a CT task in [ALL] and therefore achieved by proxy BUT local site must satisfy themselves that requirements are fully met.
**PM** - Requirement can demonstrated through appropriate maintenance - Refer to relevant PM Standard
**(PM)** - Maintenance task which is met or exceeded by a PM task in [ALL] and therefore achieved by proxy BUT local site must satisfy themselves that requirements are fully met including regional / manufacturer requirements.
**EVID** - Periodic upload of evidence to DMS, for non-CT task lines. For example, evidence of PM completion, certification, licence etc.
**EVID*** - Conditional requirement to upload evidence at the interval provided
**N A R** - No Additional Requirement

## Required Tasks

| Region | Task Index | Task Frequency | Task Requirements | Qualification of Inspector | Records Required | PM | Weekly | Monthly | 3 Monthly | 6 Monthly | 12 Monthly | 24 Monthly | Additional |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| All | 1 | In accordance with manufacturer's instructions and recommendations, but at least every 12 months. | Regular inspection and servicing of staircase pressurisation system. | Competent person (e.g. fire safety engineer) | Inspection records, report or certificate | PM | | | | | EVID | | |
| ES | 3 | Every 3 months. | Visual checks for obstructions or changes that might affects its effectiveness. | No additional requirements | Inspection records | | | | CT | | | | |
| IT | 2 | Every 6 months. | Visual inspection of ventilation systems for obstructions and cleaning (regular maintenance) | No additional requirements | CE Declaration of Conformity. | | | | | CT | | | |
| SK | 4 | Every 6 months in administrative buildings<br>Every 3 months in companies. | Visual inspection of ventilation systems for obstructions and cleaning (regular maintenance) | No additional requirements | Inspection records | | | | CT | | | | |

## Related Regional Legislation

| Region | Relevant legislation | Vendor Certification | Statutory requirement |
|---|---|---|---|

| | | | |
|---|---|---|---|
| CZ | Decree no. 246/2001 Coll.,<br>Act. No. 133/1985 Coll. | Accredited company - manufacturer-trained worker | Inspection and service every 12 months unless the manufacturer sets a shorter time limit. |
| DE | Federal State building laws and building permit;<br>(Muster-) Verwaltungsvorschrift Technische Baubestimmung MVV TB<br>DIN EN 12101-6:2005-09 Smoke and heat control systems - Part 6: Specification for pressure differential systems | Expert (Sachverständiger) for inspections;<br>Competent person for maintenance | Expert inspection before the first commencement of use of the building facilities, without undue delay after a technical modification of the building facilities, as well as immediately after a significant change to the technical installations, and within a period of three years (periodic inspections).<br>Regular maintenance by competent persons according to manufacturer specifications, at least every 12 months. |
| ES | RD 513/2017, which approves the Regulation of fire protection installations.<br><br>RD 2267/2004, which approves the Regulation of fire safety in industrial establishments.<br><br>RD 314/2006, which approves the Technical Building Code:<br>- Fire Safety Basic Document (DB SI)<br>- Use and Accessibility Basic Document (DB SUA).<br><br>UNE-EN- 12101-6: 2006. Smoke and heat control systems - Part 6: Specification for pressure differential systems – Kits. | Quarterly servicing by competent person<br>Annual maintenance by authorised company.<br>10 years inspections by accredited company (OCA). | Regular visual checks for obstructions or changes that might affect the effectiveness every 3 months.<br><br>Functional inspection (manual activation) and cleaning of the system every 6 months.<br><br>Every year: Functional inspection of system positions, including manual and automatic signals.<br><br>Inspection every 10 years. |
| FR | Labor Code Article R4227-28 to 33: Firefighting and prevention means<br>https://www.legifrance.gouv.fr/codes/section_lc/LEGITEXT000006072050/LEGISCTA000018489127/#LEGISCTA000018532085<br>Site Authorization Permit can require additional periodic exams | N/A | N/A |
| IT | Legislative Decree 09/04/2008 n.81<br>DPR 151/2011<br>DM 10/03/1998 (Currently being replaced)<br>UNI EN 12101-6:2005 (Pressure differential systems)<br>UNI 9494-3:2014 (Maintenance) | Competent, qualified person. | Inspection every 6 months. |
| PL | Act of July 7, 1994 - Construction Law (Journal of Laws of 1994, No. 89, item 414)<br>Regulation of the Minister of Infrastructure of 12 April 2002 on technical conditions corresponding to the buildings and their location. (Jornal of Laws 2019, item 1065)<br>Regulation of Minister of Interior and Administration of 7 June 2010 on fire protection of buildings, other structures and areas (Journal of Laws 2010, number 109, item 719)<br>Regulation of Minister of Labor and Social Policy of 26 September 1997 on general provisions on health and safety at work (Journal of Laws 2003, number 169, item 1650)<br>Act of 24 August 1991 on fire protection (Journal of Laws 2021, item 869)<br>Regulation of the Minister of Internal Affairs and Administration of 24 July 2009 on firefighting water supply and fire roads (Journal of Laws of 2009, No. 124, item 1030) | Qualified or competent person, usually a fire safety specialist | According to manufacturer's instruction but at least once per year. |
| ROI | Safety, Health and Welfare at Work Act 2005 (irishstatutebook.ie)<br>S.I. No. 299/2007 - Safety, Health and Welfare at Work (General Application) Regulations 2007 (irishstatutebook.ie)<br>BS EN 12101-6:2005 - Smoke and heat control systems. Specification for pressure differential systems | Weekly test by competent person, often the manager.<br>Inspection by competent engineer | Test functionality weekly if interfaced with the FAS.<br>Inspected and serviced yearly. |
| SK | Ordinance No. 94/2004 Coll. on technical requirements for fire safety during construction and use of buildings<br>Ordinance No. 121/2002 Coll. on fire prevention | Qualified and certified person | Every 12 months in households, every 6 months in administrative buildings and every 3 months in companies. |
| UK | The Regulatory Reform (Fire Safety) Order 2005 (legislation.gov.uk)<br>The Fire Safety (Scotland) Regulations 2006 (legislation.gov.uk)<br>The Fire Safety Regulations (Northern Ireland) 2010 (legislation.gov.uk)<br>Emergency procedures (hse.gov.uk)<br>BS 9999: 2017 - Fire safety in the design, management and use of buildings. Code of practice<br>BS EN 12101-6:2005 - Smoke and heat control systems. Specification for pressure differential systems | Weekly test by competent person, often the manager.<br>Inspection by competent engineer | Test functionality weekly if interfaced with the FAS.<br>Inspected and serviced yearly. |