AMAZON BASE BUILDING COMPLIANCE STANDARD

Task Title	Vacuum
APM Object	CT.LIFT.VACUUM
APM Description	Vacuum lifting equipment.
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure. CT evidence must be additionally uploaded to the DMS (WorkDocs in DE) To suggest improvements please raise a SIM or contact document authors Leonardo Vitale (LEOVITAL) Rob Gisby (EWARTGXR) or APM, Benito Sanchez Sanchez de Puerta (BPPUERTA) SIM - Link to SIM template

Last Update: (Version)	ago-23	**Last Update Change Detail:**	Transfer to new template. Rationalisation of EU RME Minimum standards. Alignment with dependant PM. Released as Draft.	**Activities may be covered by No-Go restrictions:**	Not Specified	**Special Certification Required:**	**Delivered By:**
Evidenced part or full by PM:	Not Specified	**Related BBM PM:**	Not Specified	**Related CT Areas:**	Not Specified		

Scope

Any site that uses vacuum lifting equipment to transport heavy loads. If they vacuum lifting machine is permanently attached to a crane or other lifting equipment it should be thoroughly examined as an integral part of such equipment. In any other instance, it is considered to be a lifting accessory.

Using this document

This document is intended as a guide and may not be exhaustive. Whilst this document is based extensively on professional guidance and subject to periodic review, individual sites must be diligent to ensure they are aware of, and comply to, local and changing regulations.
The format of these standards is intended to improve navigation between maintenance and compliance standards and to allow frequent, minor updates to a single living resource. Please avoid offline or printed versions and check version dates and change log.
In the event of becoming aware of errors or omissions in this document, sites must provide detail, including references to relevant source information to their local planner for escalation - SIM Link above.
This document is considered released as draft.
For Information contact Authors: R Gisby (ewartgxr), Leonardo Vitale (leovital) and Benito Sanchez Sanchez de Puerta (bppuerta)

Maintenance and Compliance Relationship

Where relevant, associated Base Building PM's are listed on the header . In many cases maintenance contributes to, or fulfils compliance requirement. This may not be exhaustive and is intended to assist users to identify relevant maintenance.
If a BBM Maintenance activity fully meets the compliance requirements below, periodic upload of PM evidence will be required to APM and DMS / Workdays depending on region.

Key to Abbreviations

The key to the below document is as follows:
CT - Amazon compliance / statutory task - not otherwise covered by a BBM Standard PM. Evidence to be provided into APM and DMS upon task closure.
CT* - This is a conditional task based or based on findings from previous inspections. If a frequency is not used, a further appropriate frequency needs to be in either the region, or 'ALL'. Local teams must ensure appropriate frequency.
(CT) - Compliance task which is likely met or exceeded by a CT task in [ALL] and therefore achieved by proxy BUT local site must satisfy themselves that requirements are fully met.
PM - Requirement can demonstrated through appropriate maintenance - Refer to relevant PM Standard
(PM) - Maintenance task which is met or exceeded by a PM task in [ALL] and therefore achieved by proxy BUT local site must satisfy themselves that requirements are fully met including regional / manufacturer requirements.
EVID - Periodic upload of evidence to DMS, for non-CT task lines. For example, evidence of PM completion, certification, licence etc.
EVID* - Conditional requirement to upload evidence at the interval provided
N A R - No Additional Requirement

Required Tasks

Region	Task Index	Task Frequency	Task Requirements	Qualification of Inspector	Records Required	PM	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	Additional
All	1	Regular maintenance	Based on risk assessment and/or manufacturer's instructions.	Competent, trained specialist.	Inspection records, reports or certificates. Risk assessment						CT		
All	2	Installation inspection - upon first assembly, or when has been moved and reconstructed	Once assembled, before it is first used	Competent, trained specialist.	Inspection records, reports or certificates. Risk assessment								As Needed EVID
All	3	Regular thorough inspection of safety-critical parts to ensure safe use, including the structure, connections, damage, pipes/hoses, motor and pump, controls, lights, etc. If defects are identified, prevent subsequent use through	At least every 12 months IF the vacuum machine is permanently attached to a crane/lifting equipment. More frequent inspections might be conducted based on use, environmental conditions and site-specific risk assessment. At least every 6 months if the vacuum machine is not permanently attached to a crane/lifting equipment, and therefore considered a lifting accessory	Competent, trained specialist.	Inspection records, reports or certificates. Risk assessment						CT		
IT	4	Every 3 months if the vacuum machine is considered a lifting accessory, every 12 months if attached to a crane/lifting equipment.	No additional requirements.	No additional requirements	CE Declaration of Conformity.			CT*			CT*		

Related Regional Legislation

Region	Relevant legislation	Vendor Certification	Statutory requirement

CZ	ČSN EN 13155	Competent person, according to the relevant instructions for the device	Inspection before first use and at least every 12 months.
DE	DIN EN 13155:2009-08 BetrSichV, §3 DGUV Regel 100-500 Betreiben von Arbeitsmitteln, Section 2.8 DGUV Regel 109-017 - Betreiben von Lastaufnahmemitteln und Anschlagmitteln im Hebezeugbetrieb	Expert (zur Prüfung befähigte Person) according to DGUV Regel 109-017	Inspection before first use and recommissioning, and at least every 12 months.
ES	RD 1644/2008, which establishes the rules for marketing and commissioning of the machines. RD 1215/97 establishing minimum security provisions and Health for the use by workers of work equipment.	Competent person.	Maintenance according to manufacturer's instructions. Inspection frequency depends on operating conditions.
FR	N/A	N/A	N/A
IT	If used individually: D.Lgs 81/08 Directive 2006/42/EU on machinery UNI EN 13155:2021 (Removable load carrying equipment) UNI EN ISO 9712:2012 (Non-destructive testing) UNI ISO 23815:2011 (Maintenance) UNI EN 14238:2009 (Manually controlled load handling devices) If permanently attached to a lifting equipment: D.Lgs 81/08 Directive 2006/42/EU on machinery	Competent person	Inspection every 12 months. Inspection of lifting components every 3 months.
PL	Regulation of the Minister of Economy of October 21 2008 on essential requirements for machines (Journal of Laws 2008, number 199, item 1228)	N/A	N/A
ROI	N/A	N/A	N/A
SK	Act No. 124/2006 Coll. on safety and health at work and on the amendment of certain acts Ordinance No. 508/2009 Coll., laying down details to ensure safety and health protection when working with technical equipment - pressure, lifting, electrical and gas and which lays down technical equipment that is considered to be reserved technical equipment	Competent person, outsource to specialist company.	Inspections in accordance with manufacturer's instructions.
UK	The Lifting Operations and Lifting Equipment Regulations 1998 The Provision and Use of Work Equipment Regulations 1998 Provision and Use of Work Equipment Regulations (Northern Ireland) 1999 Lifting Operations and Lifting Equipment Regulations (Northern Ireland) 1999	Competent person, best practice to outsource. Independent and UKAS accredited company (BS EN ISO/IEC 17020:2004)	Inspection before first use and at least every 12 months. Planned maintenance programme in place.