amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUILDING MANAGEMENT SYSTEM BMS - 1
APM Object	BLDG.BMS
APM EC	AMZ.BLDG.BMS
BBM Handbook Title	Building Management System (BMS)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	1	**Related CT Areas:**	CT.AIR.INDOOR			**Assets included in this PM:**	BMS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

BMS connects the base building assets and systems across the building to allow them to be monitored and controlled. For example a BMS can: Maintain the temperature and humidity of HVAC system as well as received notifications in case of alarm status of a unit, etc.
Note: This standard maintenance is applicable for all sites with an AMZ BMS system (Niagara / Jace controller installed)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This standard maintenance is applicable for all sites with an AMZ BMS system (Niagara / Jace controller installed)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	BMS online & BBA	Check if the site is online in the BMS		SC		SC		PM				
2	BMS online & BBA	Check the system throught the User Interface, examine plant for proper control, review active alarms		SC		SC		PM				
3	BMS online & BBA	Identify issue cause through further testing, examine trend logs etc		SC		SC		PM				
4	BMS online & BBA	If defect cannot be iliminated, create APM WO for plant related defects or SIM to BMS support as appropriate		SC		SC		PM				
5	Control & device check	Check the sensor values, drives, fans, actuator etc through the BMS User Interface and compare it with expected values in the field.				SC		PM				
6	Control & device check	If values are detected to be out of expected range, confirm this in the field using suitable test eqipment such as Environental HVAC tester to detmine cause				SC		PM				
7	Control & device check	If defect cannot be eliminated, create APM WO for plant and field device related defects or SIM to BMS support as appropriate				SC		PM				
8	Control & device check	Review BMS schedules to ensure that the most approrate schedule is in use for the plant, the building use, occupancy level etc. Optimise for frugal energy use.				SC		PM				
9	Control & device check	Review temprature setpoints and historic performance against RME Energy HVAC Standard Setpoints and ensure compliance				SC		PM				
10	Control & device check	Check the sensors and devices for visual damage						PM				
11	Control & device check	Meters - Read all meter values at the meter and compare it to the value displayed in the BMS.						PM				
12	Control & device check	Change setpoints and check correct operation of controlled devices						PM				
13	Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM				
14	Control cabinet	Check if the circuit diagram is complete & no handwritten changes have been done						PM				
15	Control cabinet	Are all cables properly routed						PM				
16	Control cabinet	Are all cables, terminal blocks & devices properly labeled and no obvious changes have been carried out (e.g. rewiring, hanging cables)						PM				
17	Control cabinet	Visual check for the protection against direct contact with live part						PM				
18	Control cabinet	Tight cable connections in the control cabinets						PM				
19	Control cabinet	Are all metal parts connected to the protection earth (ground)						PM				
20	Control cabinet	Replace the air filters of the panel & check operation of cooling fan						PM				
21	Final check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removing requirement for firmware check according to BMS team.