amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, CRANES - 14
APM Object	BLDG.CRANES
APM EC	AMZ.BLDG.CRANES
BBM Handbook Title	Cranes and Hoists (Lifting equipment)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	14	**Related CT Areas:**	CT.LIFT.HOIST			**Assets included in this PM:**	CRANES AND HOISTS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Cranes and Hoists (Lifting equipment)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Foundations	Visual inspection of the anchorage attachment for visible damage						PM				
3	Beam elements	Visual inspection of supports, beams, bars, bolts, thread lockers, joints, butt joints, welds, floor attachment and wall attachment for visible damage						PM				
4	Ascents and catwalks	Visual inspection of steps, rungs and stiles for damage. Check the fixed installations and condition of the covering of e.g. catwalks, platforms for defects. Check the protection against falling (handrails, back protection) for missing parts						PM				
5	Crane & trolley drive ban	Visually inspect the tracks, track supports, fasteners, warping, gauge attachments & welded joints for deformations, damage, corrosion and cracks. Perform visual and functional inspections of wind protection, track suspension,						PM				
6	Motor	Visual inspection of the impellers, bearings, axles, shafts, couplings, compensating rollers with pins and gears, drums, rollers, hydraulic and pneumatic components for visible damage. Lubrication of the impellers, drums and rollers. Noise						PM				
7	Brakes and slipping clutch	Visual inspection of brake discs, brake linkages, auxiliary brake, suspensions and attachments for damage. Lubricate the brake linkages. Functional check of the brakes and auxiliary brake: Check braking distance and readjust brake stroke or						PM				
8	Pipes	Visual inspection of fixed/movable pipes for damage						PM				
9	Hoist	Check the ropes, roller chains, load hooks and round steel chains for damage and adjust them if necessary. In addition, measure the length and compare it with the EU/DIN standard.						PM				
10	Electrical components	Are all cables properly routed and attached						PM				
11	Electrical components	Are all electrical terminations secure						PM				
12	Marking and signage	Signs, notices, and identification of hazardous locations are visibly attached and in place. These are complete and legible. The inspection book is present, complete and legible.						PM				
13	Test label	The test labels are attached and present in the correct places.						PM				
14	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.