amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DISABLED CALL POINT - 10
APM Object	BLDG.DISABL.CLLPNT
APM EC	AMZ.BLDG.DISABL.CLLPNT
BBM Handbook Title	Disabled Call Point - (toilet alarm)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	Not Identified	**Assets included in this PM:**	DISABLED CALL POINT	**Schedule With:**	BLDG.TOIL				

Description of System / Technology (According to BBM Handbook)

Disabled Call Point - (toilet alarm) - They provide two way communication

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: Combine the maintenance with the toilet check.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Function	Carry out a functional test of the disabled toilet alarm		SC								
2	Function	Is there any damage to the emergency switch (cord), indication light or other components		SC								
3	Final Check	Check the O&M manual & local requirements and carry out additionally required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.