amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DOORS, AUTOMATIC DOORS - 2 and 4
APM Object	BLDG.DOOR.AUTODOOR
APM EC	AMZ.BLDG.AUTODOOR
BBM Handbook Title	Automatic Doors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2 and 4	**Related CT Areas:**	CT.WORK.AUTOGATE-PEDESTRIAN			**Assets included in this PM:**	AUTOMATIC DOORS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Doors open only when activated and automatically close so to eliminate the doors being left open. They also prevent air conditioning from escaping and outside air and dust from entering. This slide represent interior & exterior assets.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
2	Safety	Does the panic door opening work correctly (in the case of an emergency escape door)						PM				
3	Safety	Check pinch protection for damage and correct function						PM				
4	Safety	Check for correct function of safety switches and sensors						PM				
5	Door	Is the door leaf free from damage and corrosion						PM				
6	Door	Are the door hinges free from damage and corrosion						PM				
7	Door	Clean and lubricate relevant mechanical components						PM				
8	Door	Is the door frame free from damage and corrosion						PM				
9	Door	Is the door operating smoothly without resistance, free from dragging on the floor, making contact with the door frame, or getting stuck at any point						PM				
10	Door	Are door sealings ok						PM				
11	Door	Does the door close properly and stay close						PM				
12	Door	Does the door close smoothly and fully without obstruction						PM				
13	Door	Are the mechanisms, including handles and locks, functioning correctly						PM				
14	Door	Door handle does not hit the wall when opening						PM				
15	Door	Doorstop is properly fixed						PM				
16	Door	It is possible to lock the door properly						PM				
17	Door	Inspect the motor, gears, and drive belts for wear and tear						PM				
18	Electrical components	Ensure that the door's speed is within the manufacturer's recommended range						PM				
19	Electrical components	Check for correct operation of drive mechanism Lubricate and adjust as necessary						PM				
20	Electrical components	Check motor overload for correct function						PM				
21	Electrical components	Check condition and correct function of limit switches Adjust if necessary						PM				
22	Electrical components	Check the control elements for damage and correct function						PM				
23	Electrical components	Check if cables are properly routed and free from damage						PM				
24	Electrical components	Ensure all cable terminations are secure						PM				
25	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Added tasks and changed wording