amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DOORS - 2 and 4
APM Object	BLDG.DOOR
APM EC	AMZ.BLDG.DOOR
BBM Handbook Title	Doors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	2 and 4	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	DOORS	**Schedule With:**	BLDG.WINDOWS BLDG.SHADING		

Description of System / Technology (According to BBM Handbook)

The function of normal/manual doors are just the closure of a room or area within the building without any additional requirement (no fire protection or any automatic functionality). This slide represent interior & exterior assets.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
2	Door	Is the door leaf free from damage and corrosion						PM				
3	Door	Are the door hinges free from damage and corrosion						PM				
4	Door	Clean and lubricate hinges if required						PM				
5	Door	Is the door frame free from damage and corrosion						PM				
6	Door	Does the door move smoothly without resistance and doesn`t drag on the floor or door frame						PM				
7	Door	Are all door sealing ok						PM				
8	Door	Does the door close properly and stay close						PM				
9	Door	If an automatic closer installed, does the door close smoothly & completely						PM				
10	Door	Are the door mechanisms functioning correctly (handles & lock)						PM				
11	Door	Door handle does not hit the wall when opening						PM				
12	Door	Doorstop is properly fixed						PM				
13	Door	It is possible to lock the door properly						PM				
14	Door	Check pinch protection for damage and correct function						PM				
15	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.