amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DRAINAGE SYSTEM - 5
APM Object	BLDG.DRAIN
APM EC	AMZ.BLDG.DRAIN
BBM Handbook Title	Drainage System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	5	**Related CT Areas:**	CT.FAC.DRAIN			**Assets included in this PM:**	DRAINAGE SYSTEM	**Schedule With:**	BLDG.TOIL		

Description of System / Technology (According to BBM Handbook)

Water drainage system from mains water internally. This does not include rain water drainage.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Clogging	If there are signs of clogging, schedule a CCTV inspection asap					SC	SC		SC		
2	General	Is the documentation of installed BBA available & complete						SC		SC		
3	Drainage inlets	Check of basin, shower, etc. drainage for damage, dirt and free drainage - clean if clogged					SC	SC		SC		
4	Drainage inlets	Check of basin drains for leaks (visual parts, e.g. siphon)					SC	SC		SC		
5	Drainage inlets	Check of the floor drains & drain grids for damage, dirt and free drainage - clean if clogged					SC	SC		SC		
6	Drainage inlets	Check water level and top up if necessary to prevent outgassing (siphon)					SC	SC		SC		
7	Drainage pipe system	Check for damage & corrosion of the drain pipes, insulation, suspension						SC		SC		
8	Drainage pipe system	Check the pipe system for impermissible & unwanted pipe openings - close immediately						SC		SC		
9	Drainage pipe system	Open maintenance flaps & check drain pipe inside for deposits and clogging						SC		SC		
10	Manual valves	Check manual valve for correct function, corrosion, dirt deposits and leaks					SC	SC		SC		
11	Automatic valves	Functional test of automatic valves of the drainage system (primarily pollution control valves)						SC		SC		
12	Pipe ventilation valves	Check if the ventilation valves are accessible, functioning correctly and free from leaks						SC		SC		
13	Pipe ventilation	Check that the pipe ventilation outlet is free from dirt and protected from rainwater						SC		SC		
14	Shaft & pit inside the building	Check if the shaft or pit is freely accessible, is free from deposit & damage (inside the building)						SC		SC		
15	Shaft & pit inside the building	Check the climbing aids in the shaft or pit for damage, corrosion and proper installation (inside t b)						SC		SC		
16	Drainage pipe system	Carry out a camera inspection of the drainage system (inside the drain pipes)								SC		
17	Final Check	Check the O&M manual & local requirements (e.g.Environmental requirements & building permit) and carry out additional required tasks								SC		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.