amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, EARTHING SYSTEM - 11
APM Object	BLDG.EARTHING
APM EC	AMZ.BLDG.EARTHING
BBM Handbook Title	Earthing System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.DISCHARGE			**Assets included in this PM:**	EARTHING SYSTEM	**Schedule With:**	ELEC.LV.CABS ELEC.MET ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD		

Description of System / Technology (According to BBM Handbook)

An earthing system connects specific parts of an electric power system with the ground, typically the Earth's conductive surface, for safety and functional purposes. The choice of earthing system can affect the safety and electromagnetic compatibility of the installation.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note: Measurements of the resistance needs to be aligned with compliance tasks

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
2	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
3	General check	Are all cables labeled correctly						PM				
4	Earthing system	Are all earthing connections to the building ground correct, tight, free from damage & corrosion						PM				
5	Earthing system	Carry out resistance measurement on main lines, compare to design and local requirements						PM				
6	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.