amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, EMERGENCY EXIT DOORS - 4
APM Object	BLDG.EMERDOOR
APM EC	AMZ.BLDG.EMERDOOR.GRP
BBM Handbook Title	Emergency Exit Doors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jan-25	**Geo Applied:**	Not Listed	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	4	**Related CT Areas:**	CT.FIRE.DOORS			**Assets included in this PM:**	EMERGENCY EXIT DOOR	**Schedule With:**	FIRE.FLS.FIREDOOR FIRE.FLS.HOLDDOOR		

Description of System / Technology (According to BBM Handbook)

Emergency exit doors are structural elements designed to allow for a quick and secure exit from a building during an emergency.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Visual check	Inspect all mechanical parts, like hinges, and tracks for physical damage, corrosion, or wear						PM				
2	Visual check	Check for obstructions or debris that might impede door operation						PM				
3	Visual check	Ensure proper alignment of doors with manual and automatic openers						PM				
4	Automatic Opener	Simulate fire alarm activation to verify the automatic door opener's response - Combine with yearly test of the fire matrix						PM				
5	Automatic Opener	Test integration with the fire alarm system, ensuring all signals are properly received and executed - Combine with yearly test of the fire matrix						PM				
6	Automatic Opener	Confirm smooth and timely door opening without mechanical resistance or delays						PM				
7	Manual Opener	Verify that the manual safety opener operates as intended, overriding the automatic system, if necessary						PM				
8	Manual Opener	Test the noise alert mechanism to ensure activation during manual operation						PM				
9	Manual Opener	Inspect the manual override mechanism for wear, corrosion, or misalignment						PM				
10	Mechanical Component	Lubricate hinges, tracks, and other moving components to reduce friction and ensure smooth operation						PM				
11	Mechanical Component	Tighten screws, bolts, and other fasteners						PM				
12	Mechanical Component	Remove any obstacles near the doors that could block their operation						PM				
13	Electrical Components	Inspect all wiring and electrical components for signs of damage and ensure there are no exposed live parts						PM				
14	Electrical Components	Test the backup power system (e.g., batteries or generators) for functionality during power outages						PM				
15	Electrical Components	Confirm the integrity of all electrical components and connections						PM				
16	Calibration	Test and calibrate sensors to ensure tcorrect detection						PM				
17	Calibration	Verify the noise alert system activates appropriately during manual override						PM				
18	Functional Cleaning	Clean all components, including doors, sensors, and tracks, to prevent buildup of dirt or debris that could cause an reliability issue						PM				
19	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

JAN 2025 - New PM after OCB update in 2024