amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUILDING EXTERIOR - 2
APM Object	BLDG.EXT
APM EC	AMZ.BLDG.EXT
BBM Handbook Title	Building Exterior
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2	**Related CT Areas:**	Not Identified	**Assets included in this PM:**	BARRIERS - GATEHOUSE - YARD - PERIMITTER FENCING	**Schedule With:**	BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.GATEBARRIER LIGHT.EXT				

Description of System / Technology (According to BBM Handbook)

Green areas around the warehouse (yard and parking area).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Perform a walk at the exterior areas of the site & perform the tasks below					SC					
2	Protection Barriers	Are protection barriers fixed properly and free from damage					SC					
3	Gates	Are gates fixed properly, free from damage and operating correctly					SC					
4	Illuminated signage Inclusive totem signs	Check all illuminated signages around the building and parking areas for correct function and damage					SC					
5	Gatehouse	Is the entrance freely accessible & free of obstacles					SC					
6	Gatehouse	Visually check for damage or excessive vegetation at the building or around					SC					
7	Gatehouse	Check for damage or corrosion at easily accessible cable trays and other installation					SC					
8	Gatehouse	Is it possible to lock the door properly - protection against unauthorized entry					SC					
9	Gatehouse	Does the light work properly					SC					
10	Gatehouse	Are there any water leaks visible at the walls or ceiling inside the gatehouse					SC					
11	Gatehouse	Visiually check for damage to the floor, walls or ceiling inside the gatehouse					SC					
12	Gatehouse	Are technical installations damaged or loose - inside the gatehouse (e.g. cable trays, MCP, fire extinguisher)					SC					
13	Gatehouse	Are flammable or unnecessary goods stored in the room					SC					
15	Yard	Check the yard floor for damage, for obstacles blocking emergency escape ways, emergency stairwells & emergency assembly points					SC					
16	Perimeter Fencing	Check the perimeter fencing for damage					SC					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Moving the task exterior walls/cladding to BLDG.STRUCTURE PM and changing the frequency of this task from 6M to 12M.