amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, GATE BARRIERS - 2
APM Object	BLDG.GATEBARRIER
APM EC	AMZ.BLDG.GATEBARRIER
BBM Handbook Title	Automatic Gate Barrier
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	AUTOMATIC GATE BARRIER	**Schedule With:**	BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.EXT LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

Automatic barriers ideal for
managing the access and control of vehicles in communal areas, car parks, industries, etc.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
3	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
4	Safety	Check for correct function of safety switches						PM				
5	Barrier	Is the barrier functioning correctly						PM				
6	Barrier	Are there any unusual noises or vibration?						PM				
7	Barrier	Are manual operating devices functioning properly						PM				
8	Intercom	Does the intercom work correctly						PM				
9	Electromechanical components	Check for correct operation of motor and mechanism Lubricate and adjust as necessary						PM				
10	Electromechanical components	Check motor overload for correct function						PM				
11	Electromechanical components	Check condition and correct function of limit switches Adjust if necessary						PM				
12	Electromechanical components	Check the control elements for damage, correct function & alarms						PM				
13	Electromechanical components	-> eliminate the root cause if an alarm is indicated						PM				
14	Electromechanical components	Check if cables are properly routed and free from damage						PM				
15	Electromechanical components	Ensure all cable terminations are secure						PM				
16	Functional cleaning	Carry out a functional cleaning and lubricate necessary moving parts						PM				
17	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.Removed task regarding CE certification.