amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, MEZZANINES - 4
APM Object	BLDG.MEZZANINE
APM EC	AMZ.BLDG.MEZZANINE.GRP
BBM Handbook Title	Mezzanines
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.FAC.BUILDING			**Assets included in this PM:**	MEZZANINES	**Schedule With:**	BLDG.STRUCTURE BLDG.INT		

Description of System / Technology (According to BBM Handbook)

Mezzanines - Raised access floors/metal mezzanines

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						SC				
2	Steelworks	Are there visible deformations, cracked welds, broken or missing bolts/nuts/rivets in the joints						SC				
3	Steelworks	Check for corrosion or other damage						SC				
4	Safety	Are there missing plates which could cause an injury						SC				
5	Safety	Are handrails and other protective equipment fixed properly, free from damage & corrosion						SC				
6	Safety	Is the walkway free from blocking obstacles						SC				
7	Safety	Are emergency letter, etc. freely accessible, functioning properly & free from damage						SC				
8	Lighting	Is the lighting in the accessible area sufficient						SC				
9	Steelworks	Check if suspended and attached equipment is loose, missing or defect						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Updated task plan, adding task 7 and 8.