amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, SUN PROTECTION / SHADING SYSTEM - 11
APM Object	BLDG.SHADING
APM EC	AMZ.BLDG.SHADING
BBM Handbook Title	Sun Protection / Shading System (Automatic Blinds)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	SUN PROTECTION / SHADING SYSTEM	**Schedule With:**	BLDG.WINDOWS		

Description of System / Technology (According to BBM Handbook)

Sun Protection / Shading System (Automatic Blinds)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of installed BBA available & complete						PM				
2	Shading system	Carry out a functional test & visual check for damage (from inside & outside the building)					SC	PM				
3	Shading system	Check condition of armor/slats						PM				
4	Shading system	Check the condition of the suspension & tighten any loose components						PM				
5	Electrical components	Check the condition of the electrical wiring for correct installation and loose components						PM				
6	Electrical components	Check if electrical components are protected against direct contact with life parts						PM				
7	Electrical components	Check the motor & shutter for unusual noise & vibration during operation					SC	PM				
8	Electrical components	Check panel for alarms, available and correct drawings & torque check all connections						PM				
9	Shading system	Check the condition of the guide rails						PM				
10	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.