amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, STRUCTURE/ WALLS AND PILLARS - 4
APM Object	BLDG.STRUCTURE
APM EC	AMZ.BLDG.STRCTR
BBM Handbook Title	Structure/ Walls and Pillars
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Feb-25	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.FAC.BUILDING			**Assets included in this PM:**	CEILINGS - FLOORS - STRUCTURE/WALLS AND PILLARS	**Schedule With:**	BLDG.INT BLDG.MEZZANINE		

Description of System / Technology (According to BBM Handbook)

Structure/ Walls and Pillars - External walls and cladding and interior walls and pillars

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Training	Confirm that the knet training "Structural Inspection Handbook for Concrete Buildings" was undertaken (link attached in Instructions tab).						SC				
2	Documentation	Follow the "Structural Inspection Handbook" attached in documents to carry out the inspection.						SC				
3	Interior walls and pillars	Check the interior walls and pillars according to the SOP. (Steel and concrete). Warehouse, technical rooms, car park building, robotics floors, stairs, offices.						SC				
4	Ceilings	Check the beams and ceilings according to the SOP.(Steel and concrete).Warehouse, technical rooms, car park building, robotics floors, stairs, offices.						SC				
5	Floors	Check the floors according to the SOP.(Steel and concrete).Warehouse, technical rooms, car park building, robotics floors, stairs, offices.						SC				
6	Attachments	Check suspended and attached equipment for signs of movement due to structural issues (e.g. shifted connections/displacement on sprinkler lines, drainage lines, ventilation ducts, etc.)						SC				
7	Exterior walls/cladding	Check the external walls and cladding according to the SOP. Warehouse, car park building, technical rooms.						SC				
8	Report	Once the report is validated, attach the completed "Inspection Report Template" to the WO Documents tab.						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the object where is applied the PM from BLDG (STEELWORK) to BLDG.STRUCTURE. Removed steelworks in the component cell, adding steelworks in the task cell. Added in component cell: Interior walls and pillars. Moved tasks from BLDG.INT, BLDG.EXT PM to BLDG.STRUCTURE PM.
February 2025 - Aligning PM according to D&C Inspection.