amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, ENTRANCE TURNSTILES - 4
APM Object	BLDG.TURNST
APM EC	AMZ.BLDG.TRNSTIL
BBM Handbook Title	Entrance Turnstiles
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.WORK.AUTOGATE-PEDESTRIAN			**Assets included in this PM:**	ENTRANCE TURNSTILES	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Entrance Turnstiles - A mechanical gate consisting of revolving horizontal arms fixed to a vertical post, allowing only one person at a time to pass through. Turnstiles can be found internally and externally. All images below represent entrance turnstiles.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Safety	Check the safety devices for correct function						PM				
4	Operating device	Visual inspection of the buttons, card reader, motion detector and opto-sensor for damage						PM				
5	Functional cleaning	Carry out a functional cleaning to maintain a reliable operation						PM				
6	Rotating column	Check the free movement of the linkage in the unlocked state & correct function of the electromagnetic clutch						PM				
7	Rotating column	Backstop is functioning correctly						PM				
8	Motor/gearbox	Check if the motor is fixed properly & doesn`t make any unusual noise						PM				
9	Motor/gearbox	Check for oil leakages and lubricate bearings if required						PM				
10	Electrical components	The lighting is working properly						PM				
11	Electrical components	The intercom is working properly						PM				
12	Electrical components	The cables are routed and fixed properly						PM				
13	Electrical components	Electrical terminations are secure						PM				
14	Electrical components	Check connections to fire system and verify the opening when the signal is activated.						PM				
15	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removing SPEEDGATES from APM Description Cell.Removed task regarding CE certification.