amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	AIR.COMPRESSORS - 13
APM Object	COMPR
APM EC	AMZ.COMPRESSORS
BBM Handbook Title	Air Compressors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	13	**Related CT Areas:**	CT.PRESSURE.SYS			**Assets included in this PM:**	AIR COMPRESSOR - COMPRESSOR AIR DRYER - COMPRESSED AIR TANK - LIQUID SEPARATOR - COMPRESSOR WATER PUMP	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

An air compressor is a pneumatic device that takes ambient air from the surroundings and discharges it at a higher pressure.

Important

The time intervals correspond to the operating hours given below. Make sure that the threshold that is reached first triggers the appropriate maintenance.

12 monthly or 3000 operational hrs

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Important

The time intervals correspond to the operating hours given below. Make sure that the threshold that is reached first triggers the appropriate maintenance.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed BBA available & complete						PM	PM	PM	PM	
2	Safety	Are all safety switches & other safety components functioning correctly	SC					PM	PM	PM	PM	
3	Visual check	Is the unit accessible	SC									
4	Visual check	Is there any visual damage, missing / loose components or corrosion	SC									
5	Controller & Control Panel	Is there an alarm at the main controller or at one of the compressors	SC									
6	Controller & Control Panel	Is the main air manager and the single compressors in an automatic mode	SC									
7	Controller & Control Panel	Is the system air pressure on the required level	SC									
8	Controller & Control Panel	Is the compressor oil temperature ok (check the IOM/O&M)			PM		PM					
9	Controller & Control Panel	Add the compressor oil temperature into the notes			PM		PM					
10	Controller & Control Panel	Do any of the counters indicate a PM due in < 800 hrs - if yes schedule PM			PM							
11	Controller & Control Panel	Add the operational hours of the compressor into the notes			PM		PM	PM	PM	PM	PM	
12	Controller & Control Panel	Switch running compressors off & check automatic start of next compressor					PM	PM	PM	PM	PM	
13	Controller & Control Panel	Did the next compressor start automatically					PM	PM	PM	PM	PM	
14	Controller & Control Panel	Are all settings according to design of the system						PM	PM	PM	PM	
15	Controller & Control Panel	Were any obvious changes made in the panel (e.g. rewiring, hanging cables)						PM	PM	PM	PM	
16	Controller & Control Panel	Is the documentation and the circuit diagram complete						PM	PM	PM	PM	
17	Controller & Control Panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM	PM	PM	PM	
18	Controller & Control Panel	Change the filter of the electrical control cabinet						PM	PM	PM	PM	
19	Air compressor	Test the condensate drain unit			PM		PM	PM	PM	PM	PM	
20	Air compressor	Are there any leakages at the connections of the pipe system (air & drainage)			PM		PM	PM	PM	PM	PM	
21	Air compressor	Is the oil level on the oil separator ok			PM		PM	PM	PM	PM	PM	
22	Air compressor	Is the oil level of the unit ok			PM		PM	PM	PM	PM	PM	
23	Air compressor	Change the oil of the unit						PM	PM	PM	PM	
24	Air compressor	Change air intake filter						PM	PM	PM	PM	
25	Air compressor	Change the oil filter							PM		PM	
26	Air compressor	Change filter cartridge of oil separator							PM		PM	
27	Air compressor	Lubricate bearings of compressor & fan							PM		PM	
28	Air compressor	Carry out a valve service using service kit (change of O-rings, etc.)									PM	
29	Air compressor	Lubricate bearings of the compressor									PM	
30	Air compressor	Change bearings of the fan									PM	
31	Oil - water separator	Is the quality of the drain water behind the oil water separator ok			PM		PM	PM	PM	PM	PM	
32	Oil - water separator	Is the drainage of the oil water separator unblocked			PM		PM	PM	PM	PM	PM	
33	Oil - water separator	Is the quality of the drain water behind the oil water separator ok						PM	PM	PM	PM	
34	Oil - water separator	Change filter of oil water separator unit						PM	PM	PM	PM	
35	Water pump	Is the water pump functioning properly					PM	PM	PM	PM	PM	

36	Compressed air tank	Vent the water sump at the bottom of the air tank			PM		PM	PM	PM	PM	PM	
37	Compressed air tank	Is the over pressure valve of the air tank functioning properly					PM	PM	PM	PM	PM	
38	Compressed air dryer	Is the air dryer functioning correctly						PM	PM	PM	PM	
39	Compressed air dryer	Is the refrigerant circuit of the air dryer free from leakages (refrigerant)						PM	PM	PM	PM	
40	Functional cleaning	Organize a cleaning of the mezzanine floor if it`s dusty			PM		PM	PM	PM	PM	PM	
41	Functional cleaning	Clean the filter of the electrical control cabinet (vacuum from outside)			PM		PM	PM	PM	PM	PM	
42	Functional cleaning	Clean the in- & outlet fins of the unit			PM		PM	PM	PM	PM	PM	
43	Functional cleaning	Damp clean all outside surfaces of the main compressed air equipment					PM	PM	PM	PM	PM	
44	Final Check	Check the O&M manual and carry out additional required tasks						PM	PM	PM	PM	

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.