amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, LOW VOLTAGE, BUSBAR - 11
APM Object	ELEC.LV.BSBR
APM EC	AMZ.ELEC.LV.BSBR
BBM Handbook Title	Low Voltage Busbar
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST CT.ELEC.THERMAL			**Assets included in this PM:**	LV BUSBAR	**Schedule With:**	ELEC.MET ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD BLDG.EARTHING		

Description of System / Technology (According to BBM Handbook)

A busbar is a metallic strip or bar, typically housed inside switchgear, panel boards, and busway enclosures for local high current power distribution. They are also used to connect high voltage equipment at electrical switchyards, and low voltage equipment in battery banks. They are generally uninsulated, and have sufficient stiffness to be supported in air by insulated pillars. These features allow sufficient cooling of the conductors, and the ability to tap in at various points without creating a new joint.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note: This standard PM package is specific to all Busbars which are installed in the FC to distribute electrical power to consumers. Busbars which are installed in any electrical panel/cabinets are always captured in the PM of those equipment.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Are the circuit diagrams and relevant technical documentation available and complete						SC				
2	General check	Are there any visual damage or loose components at the busbar system throughout the building check also for proper suspension						SC				
3	Thermographic scan	Perform thermographic scans at connection point & create a WO for over-temperature to determine the root cause						SC				
4	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature-> Upload the thermographic scan						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.