amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, DUCT DETECTION - 10
APM Object	FIRE.DET.DUCT
APM EC	AMZ.FIRE.DUCT.GRP
BBM Handbook Title	Duct Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT			**Assets included in this PM:**	DUCT DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.SMOKEHEAT FIRE.DET.BEAM FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD		

Description of System / Technology (According to BBM Handbook)

Duct smoke detectors provide early detection of smoke and products of combustion present in air moving through HVAC ducts. These devices are designed for prevention of smoke recirculation in areas by the air handling systems.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all smoke detectors detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
3	Detection	Check for change in sensor position. Are the detectors maps updated?						PM	PM			
4	Detection	Clean the air sampling tube						PM	PM			
5	Detection	Is the device free for damage						PM	PM			
6	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
7	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM.
Aug 2024 - Added task to check for battery after learnings from LATAM field RME