amazon rme

# AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

| | |
|---|---|
| **Task Title** | FIRE DETECTION SYSTEM, LINEAR HEAT - 10 |
| **APM Object** | FIRE.DET.LINEAR |
| **APM EC** | AMZ.FIRE.LNHT.GRP |
| **BBM Handbook Title** | Linear Heat Detector |
| **General tasks always required** | Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc.<br>Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required<br>Add notes for each observation and create a FWO if necessary to eliminate defects<br>Use appropriate tools, chemicals and industry standard practices (RME policy permitting)<br>Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure<br>These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed.<br>To suggest improvements please raise a SIM<br><br>SIM - Link to SIM template |

| | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Last Update: (Version)** | Jun-24 | **Geo Applied:** | Intl APM Instance | **F-Gas** | Not Identified | **Activies may be covered by No-Go restrictions:** | TBC | **Special Certificaion Required:** | TBC | **Delivered By:** | Carried out by trained on site technician with relevant certificates | **OCB:** | BBM |
| **Evidence for CT:** | YES | **Pricing template Position:** | 10 | **Related CT Areas:** | CT.FIRE.FAS<br>CT.FIRE.SMOKEDETECT | **Assets included in this PM:** | LINEAR HEAT DETECTOR | **Schedule With:** | FIRE.DET.SMOKE<br>FIRE.DET.HEAT<br>FIRE.DET.SMOKEHEATCO<br>FIRE.DET.SMOKEHEAT<br>FIRE.DET.BEAM<br>FIRE.DET.DUCT<br>FIRE.DET.FLAME<br>FIRE.DET.ASD | | | | |

## Description of System / Technology (According to BBM Handbook)

Linear Heat Detection (LHD) is a continuous heat detector designed to detect heat along the length of a sensor cable. This sensor cable is made up of two conductors, both insulated by heat sensitive polymers. The heat sensitive polymer is protected by an outer jacket.

## Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

| Task Index | Component | Tasks | Tasks Nested for frequencies > weekly | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Daily | Weekly | Monthly | 3 Monthly | 6 Monthly | 12 Monthly | 24 Monthly | 36 Monthly | 48 Monthly | 60 Monthly |
| 1 | Detection | Test different positions along the cable, including the associated display of the origin of the message | | | | | | PM | | | | |
| 2 | Detection | Check all accustic and illumintaed signals for correct function | | | | | | PM | | | | |
| 3 | Detection | Check for change in room or use of room. Are the detectors maps updated? | | | | | | PM | | | | |
| 4 | Detection | Is there any reasonable damage to the cable | | | | | | PM | | | | |
| 5 | Final Check | Consult the O&M manual and perform any additional tasks as specified | | | | | | PM | | | | |

## Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.