amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, DAMPERS - 10
APM Object	FIRE.FLS.DMP
APM EC	AMZ.FIRE.DMP
BBM Handbook Title	Dampers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DAMPERS			**Assets included in this PM:**	AUTOMATIC CONTROL DAMPER - FIRE DAMPER - FIRE/SMOKE COMBO DAMPER	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Dampers as part of the life safety system open or close during an emergency event. Automatic control dampers are typically found on the exterior of the building and open to provide make-up air for smoke exhaust fans. Fire dampers are installed in an air-distribution system, that is designed to close automatically upon detection of heat to interrupt migratory airflow and to restrict the passage of flame. Combination Fire/Smoke Damper, is a motorized damper located within HVAC ducting that closes both detection of fire, and is also interfaced with the fire alarm control unit to close upon the detection of smoke.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed equipment available & complete						PM				
2	Functional test	Trigger all fire dampers in the duct system & check for correct operation						PM				
3	Functional test	Closed Position: Ensure the damper fully closes to block airflow Open Position: Ensure the damper fully opens for unobstructed airflow						PM				
4	Functional test	Motor driven damper - check drive for damage and obvious noises or vibration while operating						PM				
5	Installation	Are the fire dampers installed according to local regulation & O&M (e.g. correctly cemented)						PM				
6	AHU control	Are the alarms indicated properly & units control process is working as designed (e.g. unit shut down)						PM				
7	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM object from FIRE.SUP.DMP to FIRE.FLS.DMP according to the last updates in the OCB.