amazon rme

# AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

| | |
|---|---|
| **Task Title** | FIRE LIFE SAFETY SYSTEM, FIRE DOORS - 10 |
| **APM Object** | FIRE.FLS.FIREDOOR |
| **APM EC** | AMZ.FIRE.FIREDOOR.GRP |
| **BBM Handbook Title** | Fire Door |
| **General tasks always required** | Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc.<br>Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required<br>Add notes for each observation and create a FWO if necessary to eliminate defects<br>Use appropriate tools, chemicals and industry standard practices (RME policy permitting)<br>Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure<br>These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed.<br>To suggest improvements please raise a SIM<br><br>SIM - Link to SIM template |

| | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Last Update: (Version)** | Jun-24 | **Geo Applied:** | Intl APM Instance | **F-Gas** | Not Identified | **Activies may be covered by No-Go restrictions:** | TBC | **Special Certificaion Required:** | TBC | **Delivered By:** | Carried out by trained on site technician with relevant certification | **OCB:** | BBM |
| **Evidence for CT:** | YES | **Pricing template Position:** | 10 | **Related CT Areas:** | CT.FIRE.DOORS | | | **Assets included in this PM:** | FIRE DOOR | **Schedule With:** | FIRE.FLS.HOLDDOOR<br>BLDG.EMERDOOR | | |

## Description of System / Technology (According to BBM Handbook)

A combination of a fire door, a frame, hardware, and other accessories that together provide a specific degree of fire protection to the opening. Used as part of a passive fire protection system to reduce the spread of fire and smoke between separate compartments of a structure and to enable safe egress from a building.

## Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

| Task Index | Component | Tasks | Tasks Nested for frequencies > weekly | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Daily | Weekly | Monthly | 3 Monthly | 6 Monthly | 12 Monthly | 24 Monthly | 36 Monthly | 48 Monthly | 60 Monthly |
| 1 | Documentation | Is the documentation of installed equipment available & complete | | | | | | PM | | | | |
| 2 | Documentation | Compare the installed equipment to design (e.g. correct fire class) | | | | | | PM | | | | |
| 3 | Safety | Is the door safely accessible and free from obstacles | | | | | | PM | | | | |
| 4 | Safety | Does the panic door opening work correctly (in the case of an emergency escape door) | | | | | | PM | | | | |
| 5 | Door | Is the door leaf & door frame free from damage and corrosion | | | | | | PM | | | | |
| 6 | Door | Is there anything incorrectly fixed to the door leaf (e.g. screw mounted plates) | | | | | | PM | | | | |
| 7 | Door | Are the door hinges free from damage and corrosion<br>Clean and lubcricate if it's necessary | | | | | | PM | | | | |
| 8 | Door | Does the door move smoothly without resistance and doesn`t drag on the floor, bang against door frame, or stick at the rail in case of sliding doors | | | | | | PM | | | | |
| 9 | Door | Are all door & frame sealings ok | | | | | | PM | | | | |
| 10 | Door | Does the door close properly and stay closed | | | | | | PM | | | | |
| 11 | Door | Are the mechanism functioning correctly (handles & lock) | | | | | | PM | | | | |
| 12 | Door | Door handle does not hit the wall when opening | | | | | | PM | | | | |
| 13 | Door | It is possible to lock the door properly | | | | | | PM | | | | |
| 14 | Door | Doorstop is properly fixed | | | | | | PM | | | | |
| 15 | Door | Check pinch protection for damage and correct function | | | | | | PM | | | | |
| 16 | Door | Are there any unusual noises when the door is moving | | | | | | PM | | | | |
| 17 | Electronic Locks | Verify the functionality of the electronic lock, ensuring proper locking, unlocking, and secure operation as per system requirements | | | | | | PM | | | | |
| 18 | Overhead closer | Is the overhead closer connected & functioning correctly | | | | | | PM | | | | |
| 19 | Functional cleaning | Carry out a functional cleaning of all relevant components | | | | | | PM | | | | |
| 20 | Final Check | Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks | | | | | | PM | | | | |

## Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM OBJECT from FIRE.DOOR to FIRE.FLS.FIREDOOR according to the OCB updates. From SC to PM.