amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, SMOKE HEAT VENTS - 10
APM Object	FIRE.FLS.SMOKEHEATVENT
APM EC	AMZ.FIRE.VENT
BBM Handbook Title	Smoke Heat Vent
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SMOKEVENTS			**Assets included in this PM:**	SMOKE HEAT VENT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Smoke heat vents are active fire protection measures. They are openings in the roof which are intended to vent the heat and smoke developed by a fire inside the building.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the system available & complete						PM				
2	General check	Check all components for damage and corrosion						PM				
3	General check	Check air inlets for obstacles blocking the airflow						PM				
4	Functional test	Ensure that all relevant keys to trigger & reset the system are available						PM				
5	Functional test	Verify the functionality of both natural and mechanical smoke extraction systems by activating the smoke extraction button and confirming proper operation						PM				
6	Functional test	Verify the correct operation of all smoke extraction components (incl. fans and the associated automatic dampers if installed)						PM				
7	Functional test	Verify if any unusual noises are present during fan operation, indicating potential mechanical issues						PM				
8	Functional test	Ensure used gas cartridges, covers, etc. are replaced before the unit will be set back in operation						PM				
9	Pipe system	Check if pipe systems are free from damage and properly fixed						PM				
10	Electrical components	Check the control elements for damage, alarms and correct function						PM				
11	Electrical components	Check if cables are properly routed and free from damage						PM				
12	Electrical components	Ensure all cable terminations are secure						PM				
13	Functional cleaning	Carry out a functional cleaning of all relevant components						PM				
14	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.