amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, DRY RISERS - 10
APM Object	FIRE.SUP.DRYRISERS
APM EC	AMZ.FIRE.DRY.RISERS
BBM Handbook Title	Dry Risers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DRYRISERS			**Assets included in this PM:**	DRY RISERS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A dry pipe sprinkler system is one in which pipes are filled with pressurized air or nitrogen, rather than water. This air holds a remote valve, known as a dry pipe valve, in a closed position.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						SC				
2	Equipment check	Check if the dry risers are fixed properly, are free from damage & corrosion						SC				
3	Equipment check	Check if the cabinets & pipe/line ends are closed & freely accessible						SC				
4	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additionally required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.