amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, FOAM SUPPRESSION - 10
APM Object	FIRE.SUP.FOAM
APM EC	AMZ.FIRE.FOAM
BBM Handbook Title	Foam Systems
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION			**Assets included in this PM:**	FOAM SUPPRESSION	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Foam Systems - Used mostly in kitchens where water protection systems could be dangerous

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						sc				
2	General check	Verify that system pressure meets code and design specifications			sc			sc				
3	General check	Check the equipment for any kind of damage (e.g. pressure gauges, pipes)			sc			sc				
4	General check	Verify all suppression system outlet nozzles to ensure they are unblocked and free from obstructions			sc			sc				
5	General check	Confirm that all valves are in the correct position			sc			sc				
6	Electrical components	Are there any alarms indicated			sc			sc				
7	Electrical components	Did any circuit breaker trip			sc			sc				
8	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						sc				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.