amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, PRESSURE WATER VESSELS - 10
APM Object	FIRE.SUP.PRESSWTR.VESSELS
APM EC	AMZ.FIRE.WTR.PRESSVESSELS
BBM Handbook Title	Pressure Water Vessel
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION CT.PRESSURE.SYS	**Assets included in this PM:**	PRESSURE WATER VESSEL	**Schedule With:**	FIRE.SUP.PUMP.AS01 FIRE.SUP.PUMP.JP01				

Description of System / Technology (According to BBM Handbook)

A vessel used in fire protection systems to store water under pressurised conditions.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment is available & complete						SC				
2	Safety	Verify that the safety devices, such as the pressure relief valve, are functioning as specified						SC				
3	Safety	Change pressure relief valve according to local regulation						SC				
4	Equipment check	Are all components are undamaged, securely fastened, and free from visible leaks						SC				
5	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.