amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, FIRE PUMPS, JOCKEY PUMP 01 - 10
APM Object	FIRE.SUP.PUMP.JP01
APM EC	AMZ.FIRE.JPUMP
BBM Handbook Title	Fire Pumps - Jockey Pump
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.PUMP	**Assets included in this PM:**	JOCKEY PUMP - JOCKEY PUMP CNTRL	**Schedule With:**	FIRE.SUP.PUMP.AS01				

Description of System / Technology (According to BBM Handbook)

A jockey pump, also know as a pressure maintenance pump, maintains the pressure in the fire sprinkler system to avoid non emergency starting of the main fire pump.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the technical documentation of the equipment available & complete						PM				
2	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
3	Function	Run jockey pump for 5 minutes (start in auto and verify if the pump started as intended)		PM								
4	Function	Check the pump for correct funtion and abnormal sound or vibration		PM								
5	Function	Did pump shutoff when line pressure was reached		PM								
6	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
7	Safety	Test all safety relevant switches						PM				
8	System Refill	Check the water volume pumped into the system			SC			PM				
9	System Refill	Add the amount in liter into the notes			SC			PM				
10	System Refill	If there is a sign of a leakage, create a WO to identify the root cause			SC			PM				
11	Power consumption	Measure the power consumption & compare to design						PM				
12	Pump	Check pump for unusual noises and lubricate bearings if possible						PM				
13	Jockey Pump Control	Visual check of the electrical panel outside & inside for damage & missing components						PM				
14	Jockey Pump Control	Are there any alarms indicated						PM				
15	Jockey Pump Control	Did any circuit breaker trip						PM				
16	Jockey Pump Control	Visual check of cable connections such as pinched insulation in the contact area						PM				
17	Jockey Pump Control	Visual check for the protection against direct contact with live parts						PM				
18	Jockey Pump Control	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
19	Jockey Pump Control	Are all cables properly routed						PM				
20	Jockey Pump Control	Are all components properly labeled or marked						PM				
21	Jockey Pump Control	Are all components properly attached						PM				
22	Jockey Pump Control	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
23	Jockey Pump Control	Are all metal parts connected to the protection earth (ground)						PM				
24	Functional cleaning	Carry out functional cleaning						PM				
25	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 204 - Moved tasks from Sprinkler System. Changed Component from "Jockey Pumps"