amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, CONVEYOR FIRE SHUTTERS - 10
APM Object	FIRE.SUP.SHUTTER
APM EC	AMZ.FIRE.SHUTTER.GRP
BBM Handbook Title	Conveyor Fire Shutters
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SHUTTERS			**Assets included in this PM:**	CONVEYOR FIRE SHUTTER	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

Conveyor Fire Shutters are allocated in walls where conveyors pass from different building areas. Shutters would close in case of a fire to isolate the areas.

Additional Information

Conveyor Fire Shutters are allocated in walls where conveyors pass from different building areas. Shutters would close in case of a fire to isolate the areas.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed equipment available & complete						PM				
2	Functional test	Trigger all shutters via fire alarm & check for correct operation						PM				
3	Functional test	Simulate the operation of the fusible link to ensure the shutter fully closes the fire compartment as per requirement						PM				
4	Functional test	Simulate the operation of the solenoid to ensure the shutter fully closes the fire compartment as per requirement						PM				
5	Functional test	Motor driven parts - check drive for damage and obvious noises or vibration while operating						PM				
6	Functional test	Check the solenoid battery backup panel for proper function						PM				
7	Functional test	Are all relevant connected systems functioning as intended (e.g., stopping the conveyor, if designed to do so)						PM				
8	Functional test	Verify that Emergency Stop mechanisms are functioning correctly (where installed)						PM				
9	Shutter	Is the shutter free from damage and corrosion						PM				
10	Shutter	Verify that hood & hood brackets are in place and secure						PM				
11	Shutter	Verify that End Lugs are Secure						PM				
12	Shutter	Verify that all limit and safety switches are free from damage and ensure that the system operates correctly according to the signal output						PM				
13	Shutter	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
14	Shutter	Inspect all bearings for any signs of wear or damage						PM				
15	Shutter	Inspect curtain roll alignment & tracking for any signs of wear or damage						PM				
16	Shutter	Check for clutch slippage to ensure proper operation of the conveyor fire shutter						PM				
17	Shutter	Check and adjust drive chain tension to ensure proper operation of the conveyor fire shutter						PM				
18	Shutter	Check and correct drive chain alignment to ensure optimal operation of the conveyor fire shutter						PM				
19	Shutter	Inspect and tighten sprockets, and ensure proper alignment to maintain optimal operation of the conveyor fire shutter						PM				
20	Shutter	Lightly lubricate chains and bearings, ensuring that the safety brake is not lubricated						PM				
21	Shutter	Check and adjust spring/curtain tension on self-coiling doors, to ensure proper operation						PM				
22	Shutter	Confirm that the motor hand chain effectively opens the shutter						PM				
23	Shutter	Ensure that the fusible link is not painted or coated, maintaining its proper function						PM				
24	Panel	Inspect panel and all connected electrical components for damage						PM				
25	Panel	Ensure all relevant electrical connections are securely tightened						PM				
26	Panel	Ensure that all live parts are properly enclosed and not accessible						PM				
27	Panel	Replace the cooling filter, clean the inlets, and verify that the cooling fan is functioning correctly						PM				
28	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

Aug 2024 - New PM based on RME field learnings from HIE