amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, VALVES - 10
APM Object	FIRE.SUP.VALV
APM EC	AMZ.FIRE.VALV
BBM Handbook Title	Fire Suppression Valves
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**		**Delivered By:**		**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION	**Assets included in this PM:**	FIRE VALVES	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.WTRTNK FIRE.SUP.WETRISERS FIRE.SUP.HDRNT				

Description of System / Technology (According to BBM Handbook)

GATE VALVE: Gate valves are used to isolate the specific area of water supply to the network during maintenance, repair works, new installations, as well as to reroute water flow throughout the pipeline.
BUTTERFLY VALVE: Butterfly valves can be used for throttling or regulating flow as well as in the full open and fully closed position. The pressure loss through a butterfly valve is small in comparison with the gate valve.
PRESSURE REDUCING VALVE: A Pressure Reducing Valve (PRV) is an Automatic Control Valve designed to reduce a higher unregulated inlet pressure to a constant, reduced downstream (outlet) pressure regardless of variations in demand and/or upstream (inlet) water pressure.
FIRE BACKFLOW PREVENETER: Backflow preventers provide a critical interface between a building's fire protection system and the water supply that feeds it. A backflow preventer is a device designed to ensure that water inside a building's fire sprinkler system

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Gate valve	Is the valve in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
2	Gate valve	Inspect the valve to ensure it is undamaged, leakage free, functioning properly & moving smoothly		PM								
3	Gate valve	Is the valve properly labeled according to Amazon standards		PM								
4	Gate valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)						PM				
5	Butterfly Valve	Is the valve in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
6	Butterfly Valve	Inspect the valve to ensure it is undamaged, leakage free, functioning properly & moving smoothly		PM								
7	Butterfly Valve	Is the valve in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
8	Pressure Reducing Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
9	Pressure Reducing Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)						PM				
10	Fire Backflow Preventer Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
11	Fire Backflow Preventer Valve	Is the valve properly labeled according to Amazon standards		PM								
12	Fire Backflow Preventer Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)		PM								
13	Fire Backflow Preventer Valve	Open the maintenance cover on the supply site and release the water						PM				
14	Fire Backflow Preventer Valve	Check if there is not water flowing back from the building pipes						PM				
15	Auxiliary Drain Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
16	Auxiliary Drain Valve	Is the valve properly labeled according to Amazon standards		PM								
17	Auxiliary Drain Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)						PM				
18	Auxiliary Drain Valve	Carry out a functional test and ensure dirt deposit is drained out						PM				
19	Check Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
20	Check Valve	Is the valve properly labeled according to Amazon standards		PM								
21	Check Valve	Verify that connected sensors and manometers are fucntioning correctly (if applies)						PM				
22	Check Valve	Check if there is not water flowing back from outlet side						PM				
23	Alarm Valve	Inspect the valve to ensure it is undamaged, leakage free, functioning properly		PM								
24	Alarm Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)		PM								
25	Alarm Valve	Verify tthe correct function of the waterflow alarm						PM				

Change Log

June 2024 - New PM specific for fire valves.