amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, WET RISERS - 10
APM Object	FIRE.SUP.WETRISERS
APM EC	AMZ.FIRE.WET.RISERS
BBM Handbook Title	Wet Risers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**		**Delivered By:**	**OCB:** BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION	**Assets included in this PM:**	WET RISERS	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.WTRTNK FIRE.SUP.VALV FIRE.SUP.HDRNT		

Description of System / Technology (According to BBM Handbook)

A sprinkler system employing automatic sprinklers attached to a piping system containing water and connected to a water supply so that water discharges immediately from sprinklers opened by heat from a fire. Includes a water supply source, a control valve, a waterflow alarm, and a drain Wet pipe sprinkler systems are the most common form of fire sprinkler system.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Wet risers	Verify that all protecting components (e.g., fences & doors) are undamaged		PM								
2	Wet risers	Spring test of all Post Indicating Valves (PIV) and valve supervidory switches				PM		PM				
3	Wet risers	Are additional valves in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
4	Wet risers	Inspect additional valves to ensure it is undamaged, leakage free, functioning properly & moving smoothly		PM								
5	Wet risers	Are additional valves properly labeled according to Amazon standards		PM								
6	Wet risers	Verify that connected sensors & manometers to Are additional valves are fucntioning correctly (if applies)						PM				
7	Wet risers	Turn every sprinkler control valve based on NFPA guidelines Ensure valves are reopened and locked after the test				PM		PM				
8	Wet risers	Verify that the main drain is open and free from obstruction						PM				
9	Wet risers	Conduct a main drain test to assess water supply & system performance						PM				

Change Log

June 2024 - New PM specific for wet risers.