amazon rme

# AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

| | |
|---|---|
| **Task Title** | GAS SYSTEM - 9 |
| **APM Object** | GAS |
| **APM EC** | AMZ.GAS |
| **BBM Handbook Title** | Gas System |
| **General tasks always required** | Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc.<br>Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required<br>Add notes for each observation and create a FWO if necessary to eliminate defects<br>Use appropriate tools, chemicals and industry standard practices (RME policy permitting)<br>Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure<br>These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed.<br>To suggest improvements please raise a SIM<br><br>SIM - Link to SIM template |

| | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Last Update: (Version)** | Jun-24 | **Geo Applied:** | Intl APM Instance | **F-Gas** | Not Identified | **Activies may be covered by No-Go restrictions:** | YES | **Special Certificaion Required:** | TBC | **Delivered By:** | Carried out by trained on site technician | **OCB:** | BBM |
| **Evidence for CT:** | YES | **Pricing template Position:** | 9 | **Related CT Areas:** | CT.HVAC.GASINSTALL | | | **Assets included in this PM:** | GAS SYSTEM | **Schedule With:** | HVAC.BLR<br>HVAC.GH<br>WTR.SUPPLY.HTR.01 | | |

## Description of System / Technology (According to BBM Handbook)

Gas System includes: Gas Valves, Meters, Booster pumps, Reduction valves and Natural gas generators.

## Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

| Task Index | Component | Tasks | Tasks Nested for frequencies > weekly | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | Daily | Weekly | Monthly | 3 Monthly | 6 Monthly | 12 Monthly | 24 Monthly | 36 Monthly | 48 Monthly | 60 Monthly |
| 1 | General | Is the gas system documentation complete & are there drawings on the wall | | | | | | PM | | | | |
| 2 | Gas distribution rooms | Are the gas connection & distribution rooms freely accessible | | | | | | PM | | | | |
| 3 | Gas distribution rooms | Are meters & valves freely accessible | | | | | | PM | | | | |
| 4 | Gas distribution rooms | Are the gas connection & distribution rooms properly ventilated | | | | | | PM | | | | |
| 5 | Gas distribution rooms | Marking of the room incl. warning and prohibition instructions / safety instructions are correct and visible | | | | | | PM | | | | |
| 6 | Measurement devices | Are installed Gas detectors functioning as designed | | | | | | PM | | | | |
| 7 | Gas pipe system | Are all installed devices working properly (e.g. booster pump, pressure reduction) | | | | | | PM | | | | |
| 8 | Gas pipe system | Check gas pipe connections in gas connection & distribution room for leakages | | | | | | PM | | | | |
| 9 | Gas pipe system | Is there any visual damage at the gas pipe system throughout the building check also for proper suspension | | | | | | PM | | | | |
| 10 | Gas pipe system | Are the connections at all gas consumers free from damage, corrosion & free from leakages - Only the visible connections (it`s not required to dismantle the kitchen appliances) | | | | | | PM | | | | |
| 11 | Electrical | Maintain electrical elements components to local regulations (e.g. DIN VDE) | | | | | | PM | | | | |
| 12 | Final Check | Check the O&M manual and carry out additional required tasks | | | | | | PM | | | | |

## Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Added "forecast with".