amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, CONVECTOR RADIATOR UNITS - 9
APM Object	HVAC.CNV
APM EC	AMZ.HVAC.CNV.GRP
BBM Handbook Title	Convector Heater Units
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Certified electrician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.ELEC.PAT	**Assets included in this PM:**	ELECTRICAL HEATER UNIT	**Schedule With:**	-				

Description of System / Technology (According to BBM Handbook)

A convection radiator is a heating terminal unit which uses electricity has its heating source and utilizes convection (ie : fan) heat principles and not radiation. Amazon considers other non water supplied heating systems which are primarily electric driven within this Convector Radiator Unit System. (ie : Air Curtains,heated or non heated).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The yearly PPM should be carried out before the start of the heating season (winter)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the unit free from damage or corrosion						PM				
2	Safety	Are all safety devices functioning correctly						PM				
3	Safety	All electrical components free for damage and live parts not accesible						PM				
4	Function	Is the unit functioning correctly						PM				
5	Function	Is there any unusual noise or vibration						PM				
6	Hygiene & Filter	Clean reusable filter or exchange disposable filter						PM				
7	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM according to the new category created in the OCB.