amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, GAS DARK HEATERS - 9
APM Object	HVAC.GH
APM EC	AMZ.HVAC.GH.GRP
BBM Handbook Title	Gas Heater Unit
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.GASAPPLIANCE			**Assets included in this PM:**	GAS HEATER UNIT	**Schedule With:**	GAS HVAC.BLR WTR.SUPPLY.HTR.01		

Description of System / Technology (According to BBM Handbook)

A gas heater is a space heater used to heat a room or outdoor area by burning natural gas, liquefied petroleum gas, propane, or butane.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This PM yearkly Gas Radiant Tube Heater should be carried out before the winter season starts

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Functional check	Is the heater functioning properly						PM				
2	General	Is the documentation of installed BBA available & complete						PM				
3	Unit check	Are there any damage at the heater (e.g. loose parts)						PM				
4	Burner	Is the burner engine functioning as designed						PM				
5	Burner	Are there any unusual noises (e.g. bearings)						PM				
6	Burner	Is the impeller free from dirt & damage						PM				
7	Burner	Is the flame sensor functioning as designed						PM				
8	Burner	Is the ignition device functioning as designed						PM				
9	Control & safety device	Is the mixing device free from dirt & damage (gas & air)						PM				
10	Control & safety device	Is the air adjustment device functioning as designed						PM				
11	Control & safety device	Is the lack of air protection device functioning as designed						PM				
12	Control & safety device	Are the air seal flaps functioning as designed						PM				
13	Control & safety device	Are the manual control valves functioning properly						PM				
14	Control & safety device	Is the gas pressure regulator functioning as designed						PM				
15	Control & safety device	Are the magnetic valves functioning as designed						PM				
16	Control & safety device	Are the Gas pipes & fittings tight						PM				
17	Control & safety device	Check connection and nozzle pressure						PM				
18	Measurement	Carry out an exhaust analysis						PM				
19	Measurement	Determine exhaust loss						PM				
20	Measurement	Add measurement log into the notes						PM				
21	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.