amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING WATER SUPPLY, DOMESTIC HOT WATER HEATERS - 9
APM Object	WTR.SUPPLY.HTR
APM EC	AMZ.WS.HTR.GRP
BBM Handbook Title	Domestic Water Heaters (Drinking water)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version) Jul-23	**Geo Applied:** Intl APM Instance	**F-Gas** Not Identified	**Activies may be covered by No-Go restrictions:** TBC	**Special Certificaion Required:** TBC	**Delivered By:** Carried out by trained on site technician	**OCB:** BBM	
Evidence for CT: TBC	**Pricing template Position:** 9	**Related CT Areas:** CT.WATER.HOTSERVICE		**Assets included in this PM:** DOMESTIC HOT WATER UNIT	**Schedule With:** NO INFO		

Description of System / Technology (According to BBM Handbook)

Domestic Hot Water (DHW) generators are generally gas direct fired units with the burner integrated in to the bottom of a water cylinder.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note : Theis PM can be used for electrical domestic water heater and for warm trinking water stations supplied by a separate gas boiler

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Are the water treatment rooms accessible						PM				
2	General	Are there any visible water leakages at the system						PM				
3	General	Are technical installations damaged or loose (incl. cables connected to equipment)						PM				
4	General	Are there any damage at pipe or equipment insulation						PM				
5	General	Is the documentation of the hot drinking water treatment system complete & are there drawings on the wall						PM				
6	Controller	Is the unit in operation & no alarms indicated - unit controller or control cabinet						PM				
7	Measurement	Are there any damage at the thermometer or manometer (pressure)						PM				
8	Measurement	Measure the water temperature to verify the thermometer & value on control display						PM				
9	Unit check	Is the buffer tank free from damage & corrosion						PM				
10	Unit check	Is the electrical heater functioning correctly						PM				
11	Unit check	Is the softening system functioning correctly & free from damage						PM				
12	Unit check	Are the motor driven valves functioning correctly						PM				
13	Unit check	Are all manual control valves functioning correctly & are free from damage						PM				
14	Unit check	Check sacrificial anode (if installed)						PM				
15	Safety & hygiene	Are the pressure reducer and non-return valves functioning properly						PM				
16	Safety & hygiene	Is the filter backwash unit functioning correctly						PM				
17	Safety & hygiene	Is the water filter in a good condition						PM				
18	Safety & hygiene	Is the expansion vessel functioning correctly						PM				
19	Safety & hygiene	Do the safety devices work as required (e.g. pressure relief valve, group valve)						PM				
20	Safety & hygiene	Is the legionella program functioning correctly						PM				
21	Safety & hygiene	Is the circulation pump functioning correctly						PM				
22	Electrical	Maintain electrical elements components to local regulations (e.g. DIN VDE)						PM				
23	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

Error - Entry for specified object not found on change log