Base Building Preventative Maintenance Standards

Issued March 2025

To be used with BBM Pricing Template version 7.XX only

Document owned and updated by:
Leonardo Vitale (LEOVITAL)
Rob Gisby (EWARTGXR)
Lara Leal Pino (LALEAL)

GLOBAL CENTRAL RME
STANDARDS & COMPLIANCE

Table of Contents

- New in this release
- Using this document
- Definitions & References
- Acknowledgements
- PM Standards
    - BUILDING, BUILDING MANAGEMENT SYSTEM BMS
    - BUILDING, BUS SHELTER
    - BUILDING, CRANES
    - BUILDING, DISABLED CALL POINT
    - BUILDING, DOORS
    - BUILDING, DOORS, AUTOMATIC DOORS
    - BUILDING, DOORS, ROLLER DOORS
    - BUILDING, DRAINAGE SYSTEM
    - BUILDING, DRINK WATER DISPENSERS
    - BUILDING, EARTHING SYSTEM
    - BUILDING, EMERGENCY EXIT DOORS
    - BUILDING, BUILDING EXTERIOR
    - BUILDING, EXTERIOR SURFACES
    - BUILDING, FUEL STORAGE TANKS
    - BUILDING, GATE BARRIERS
    - BUILDING, GREASE SEPARATOR
    - BUILDING, HEARING LOOP
    - BUILDING, BUILDING INTERIOR
    - BUILDING, LIGHTNING PROTECTION SYSTEM
    - BUILDING, WASTE MACERATOR PUMPS
    - BUILDING, METAL DETECTORS
    - BUILDING, MEZZANINES
    - BUILDING, OIL SEPARATOR
    - BUILDING, RAINWATER COLLECTORS
    - BUILDING, ROOF AND ROOF DRAINAGE
    - BUILDING, SEWAGE SYSTEM, SEWAGE WATER PUMPS
    - BUILDING, SUN PROTECTION / SHADING SYSTEM
    - BUILDING, ENTRANCE SPEED GATES
    - BUILDING, SMART ROOF MONITORING SYSTEM
    - BUILDING, STRUCTURE/ WALLS AND PILLARS
    - BUILDING, TOILETS
    - BUILDING, ENTRANCE TURNSTILES
    - BUILDING, WINDOWS
    - AIR.COMPRESSORS
    - DOCKS
    - ELECTRICAL SYSTEM, DIESEL POWER GENERATORS
    - ELECTRICAL SYSTEM, HIGH VOLTAGE, SWITCHGEAR SYSTEM
    - ELECTRICAL SYSTEM, HIGH VOLTAGE, TRANSFORMERS ELECTRICAL SYSTEM, LOW VOLTAGE, BUSBAR
    - ELECTRICAL SYSTEM, LOW VOLTAGE, ELECTRICAL CABINETS
    - ELECTRICAL SYSTEM, LOW VOLTAGE, POWER FACTOR CORRECTION
    - ELECTRICAL SYSTEM, LOW VOLTAGE, SWITCHBOARD
    - ELECTRICAL SYSTEM, METERS
    - ELECTRICAL SYSTEM, UNINTERRUPTABLE POWER SUPPLY
    - FIRE DETECTION SYSTEM, FIRE ALARM PANELS
    - FIRE DETECTION SYSTEM, ASPIRATING SMOKE
    - FIRE DETECTION SYSTEM, BEAM
    - FIRE DETECTION SYSTEM, PUBLIC ADDRESS SYSTEM
    - FIRE DETECTION SYSTEM, DUCT DETECTION

FIRE DETECTION SYSTEM, FLAME
FIRE DETECTION SYSTEM, HEAT
FIRE DETECTION SYSTEM, LINEAR HEAT
FIRE DETECTION SYSTEM, MANUAL CALL POINTS
FIRE DETECTION SYSTEM, PUBLIC SAFETY RADIO SYSTEM
FIRE DETECTION SYSTEM, SMOKE
FIRE DETECTION SYSTEM, SMOKE AND HEAT COMBINED
FIRE DETECTION SYSTEM, SMOKE HEAT AND CO DETECTORS
FIRE LIFE SAFETY SYSTEM, DAMPERS
FIRE LIFE SAFETY SYSTEM, FIRE DOORS
FIRE LIFE SAFETY SYSTEM, FIRE SLIDING DOORS
FIRE LIFE SAFETY SYSTEM, FIRE DOORS HOLD OPEN SYSTEM
FIRE LIFE SAFETY SYSTEM, WAREHOUSE SMOKE EXTRACTION
FIRE LIFE SAFETY SYSTEM, SMOKE HEAT VENTS
FIRE SPECIAL HAZARDS SYSTEM, HYDROGEN DETECTION
FIRE SPECIAL HAZARDS SYSTEM, KITCHEN HOOD
FIRE SUPPRESSION SYSTEM, DRY RISERS
FIRE SUPPRESSION SYSTEM, EQUIPMENT, EXTINGUISHERS
FIRE SUPPRESSION SYSTEM, FOAM SUPPRESSION
FIRE SUPPRESSION SYSTEM, HYDRANT
FIRE SUPPRESSION SYSTEM, PRESSURE WATER VESSELS FIRE
SUPPRESSION SYSTEM, FIRE PUMPS, FIRE PUMP 01 FIRE
SUPPRESSION SYSTEM, FIRE PUMPS, JOCKEY PUMP 01 FIRE
SUPPRESSION SYSTEM, CONVEYOR FIRE SHUTTERS FIRE
SUPPRESSION SYSTEM, SPRINKLERS
FIRE SUPPRESSION SYSTEM, VALVES
FIRE SUPPRESSION SYSTEM, WET RISERS
FIRE SUPPRESSION SYSTEM, WATER STORAGE TANKS
GAS SYSTEM
HVAC SYSTEMS, AIR CONDITION
HVAC SYSTEMS, AIR HANDLING UNITS
HVAC SYSTEMS, BOILER UNITS
HVAC SYSTEMS, CHILLER UNITS
HVAC SYSTEMS, CONVECTOR RADIATOR UNITS
HVAC SYSTEMS, AIR CONDENSING
HVAC SYSTEMS, KITCHEN EXHAUST DUCT SYSTEM
HVAC SYSTEMS, EXHAUST FAN UNITS
HVAC SYSTEMS, GAS DARK HEATERS
HVAC SYSTEMS, HUMIDIFIERS
HVAC SYSTEMS, AIR ROOFTOP UNITS-OUTDOOR
HVAC SYSTEMS, SUPPLY FAN UNITS
HVAC SYSTEMS, WATER HEATED SYSTEM
LADDERS, FIXED LADDERS
LADDERS, MOBILE LADDERS
LIFTS, GOODS LIFTS
LIFTS, PASSENGER LIFTS
LIFTS, VEHICLE TO GROUND LIFTS
LIGHT, EXTERNAL
LIGHT, INTERNAL
LIGHT, SAFETY LIGHTING AND SIGNAGE
STORAGE, HIGH RACKS
STORAGE, SHELVING
BUILDING WATER SUPPLY
BUILDING WATER SUPPLY, DOMESTIC HOT WATER HEATERS

What is new in this release?

- PM's have been refreshed to align with latest OCB changes as part of global alignment program.
- Some PMs have been split to improve tracking and forecasting in APM
- The following objects are associated with new PM Packages as a result of OCB Updates, Global Alignment or splitting activity to improve data granularity

OBJECT	EC
BLDG.EXTSURFACES	AMZ.BLDG.EXTSURFACES
BLDG.MEZZANINE	AMZ.BLDG.MEZZANINE.GRP
BLDG.SRMS	AMZ.BLDG.SRMS
BLDG.STRUCTURE	AMZ.BLDG.STRCTR
BLDG.WINDOWS	AMZ.BLDG.WINDOW
ELEC.HV.SWGR	AMZ.ELEC.HV.SWGR.GRP
ELEC.HV.TX	AMZ.ELEC.HV.TX.GRP
ELEC.LV.SWBD	AMZ.ELEC.LV.SWBD
FIRE.DET.ASD	AMZ.FIRE.ASP.GRP
FIRE.DET.BEAM	AMZ.FIRE.BEAM.GRP
FIRE.DET.DUCT	AMZ.FIRE.DUCT.GRP
FIRE.DET.FLAME	AMZ.FIRE.FLAME.GRP
FIRE.DET.HEAT	AMZ.FIRE.HEAT.GRP
FIRE.DET.LINEAR	AMZ.FIRE.LNHT.GRP
FIRE.DET.MCP	AMZ.FIRE.MCP.GRP
FIRE.DET.RADIO	AMZ.FIRE.RADIO
FIRE.DET.SMOKE	AMZ.FIRE.SMOKE.GRP
FIRE.DET.SMOKEHEAT	AMZ.FIRE.SMOKEHEAT.GRP
FIRE.DET.SMOKEHEATCO	AMZ.FIRE.SMOKEHEATCO.GRP
FIRE.FLS.FIREDOOR	AMZ.FIRE.FIREDOOR.GRP

OBJECT	EC
FIRE.FLS.FIRESLD	AMZ.FIRE.SLD
FIRE.FLS.HOLDDOOR	AMZ.FIRE.HOLDDOOR.GRP
FIRE.SPHZRD.KITCHEN	AMZ.FIRE.KHOOD
FIRE.SUP.SHUTTER	AMZ.FIRE.SHUTTER.GRP
FIRE.SUP.SPRK	AMZ.FIRE.SPRK
FIRE.SUP.VALV	AMZ.FIRE.VALV
FIRE.SUP.WETRISERS	AMZ.FIRE.WET.RISERS
FIRE.SUP.WTRTNK	AMZ.FIRE.WT
HVAC.CNV	AMZ.HVAC.CNV.GRP
HVAC.HMD	AMZ.HVAC.HMD.GRP
HVAC.WTR	AMZ.HVAC.WTR.GRP
LIFTS.V2G	AMZ.LIFTS.V2G
REFR.BLST	AMZ.REFR.BLST
REFR.DOORS	AMZ.COOL.DOOR
REFR.PLANT.01	AMZ.REFR.PLANT.GRP
REFR.PLANT.CNTRL	AMZ.REFR.CNTRL
REFR.RIC	AMZ.REFR.RCHILL
REFR.ROOM	AMZ.REFR.ROOM
STOR.SHELV	AMZ.SHELV
WTR.SUPPLY.HTR	AMZ.WS.HTR.GRP

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, AIR ROOFTOP UNITS-OUTDOOR - 9
APM Object	HVAC.RTU
APM EC	1 AMZ.HVAC.RTU.GRP
BBM Handbook Title	Air Rooftop Units (RTUs)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

2 **Last Update: (Version)**	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	3 **Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	Hygiene certification required in some countries (e.g. VDI 6022)	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	4 **OCB:**	BBM
5 **Evidence for CT:**	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.INDOOR CT.HVAC.12KW CT.HVAC.FGAS	**Assets included in this PM:**	ROOFTOP UNIT OUTDOOR	6 **Schedule With:**	HVAC.HMD HVAC.BLR (if installed)				

Description of System / Technology (According to BBM Handbook)

7 Roof Top Units (or RTUs) are a packaged unit that is a typical HVAC system type seen across Amazon FC's. RTUs contain all the components needed to provide conditioned air in one concise unit with a single unit being able to provide comfort cooling, heating, supply of an adjustable volume of fresh air, as well as free cooling.

Additional Information

8 All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.
Refrigerant part -> Ensure that leakage and any other requirements according to F Gas Regulation are followed

97	Refrigerant Part Compressor & Safety	Lubricate all moving parts and bearings if reachable						PM		PM			
98	Final Check	Check the O&M manual and carry out additional required tasks						PM		PM			

9 **Change Log**

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Moved "Humidifier tasks" to HVAC.HMD PM.

(See imagine on previous page)

1. **APM EC** has been added to each plan to assist planners to more quickly identify where the PM package is allocated
2. **Geo's applied** has been added to indicate which APM Instance or regions a plan is available and/or deployed.
3. **F-Gas** flag has been added to identify systems which may be linked to F-Gas compliance
4. **Source OCB** has been added as some PM's may be based on technologies outside of the BBM OCB
5. **Pricing Template Position** has been added to each PM to assist vendors to identify quickly which discipline the PM relates to on the BBM Vendor Pricing Template
6. **Schedule With** has been added to indicate Object Codes of equipment which might logically have their maintenance scheduled at the same time due to similar locations or disciplines. These are cross referenced to promote use of efficient maintenance scheduling. This is a guide and intended to support planners.
7. **Description of System** has been included and updated to mirror the BBM Handbook
8. **Additional Information** was previously under a different heading and has been moved and renamed.
9. **Change Control** section has been added to each PM page to show the incremental changes made to each PM over time.

Using this document

This is a living document and whilst updates are minimised, this document (and each PM within it) should be considered living. It is important to avoid taking off-line copies unnecessarily and to actively check the 'Last Update' date field for version control.

To suggest improvements to these standards, please use the appropriate links below:

For issues relating to content of standards:
Raise SIM here

For APM related issues
River Link and Path below
https://river.amazon.com
APM Help Center --> Select Region --> Base Building Maintenance (BBM) --> Standard PM's

Definitions & References

APM – Asset Performance Management, Amazons Computerised Maintenance Management System (CMMS)

APM Instance – APM operates in two 'Instances', one [AMER] covering North America and LATAM, the other [Intl] covering all remaining regions around the world.

CMMS – Computerised Maintenance Management System [See APM]

EC - equipment configuration acts as a profile for equipment, and populates data (Manufacturer, Model, Revision, Class and Category) linked with it to the equipment created. Standard equipment-specific data is linked from the configuration such as Documents, parts associated and PM Schedules.

FWO – Follow-up Work Order (corrective activity)

HIE – High Impact Event

HRO – High Risk Operation as defined by WHS

OCB – Object code builder

Nesting - Nesting is simply an indication that higher frequency tasks are included (nested) in lower frequency tasks. In practice, this would mean, that all tasks that are (example) scheduled monthly, will also be undertaken in the annual maintenance avoiding the need for 2 (or more) work orders to be issued concurrently. APM (The CMMS) will automatically accommodate this releasing only the work order with the higher interval.

No-Go – No-Go Activity as defined by WHS

PM – Preventative Maintenance – (See also SC) Preventative Maintenance may (unlike SC) be intrusive or require specialised training, tooling, certification or perimetry etc
Most appropriate delivery mechanism will be subject to local review and may require SOP, task risk assessment, permits or delivery via sub contracted resource as appropriate. Note:- PM does not automatically indicate that activity cannot be self-delivered. If one or more of the task items within a maintenance activity is determined to be 'PM', the whole maintenance activity will be classified as 'PM'.
Corrective work identified during a PM must be raised as a Follow-up Work Order (FWO)

SC – System Check (See also PM) - a sub-type of PM are 'non-intrusive' checks or activities and will generally be self-delivered by technicians with appropriate information, instruction, training and supervision (which may include SOP) but are usually not intended not to require additional specialist knowledge, certification.
Note - This is guidance only and local implementation should be subject to local review to ensure safety at all times.
Corrective work identified during a SC must be raised as a Follow-up Work Order (FWO)

SME – Subject Matter Expert

SOP – Standard Operating Procedure

VSOP – Visual Standard Operating Procedure

Acknowledgements

This document brings together practices from industry standards, manufacturer recommendations, compliance standards, learnings from HIE/COE and SME input.

Thank you to all who contribute to continue to continue to improve and refine these maintenance activities which play an important part in standardising our approaches across Amazon.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUILDING MANAGEMENT SYSTEM BMS - 1
APM Object	BLDG.BMS
APM EC	AMZ.BLDG.BMS
BBM Handbook Title	Building Management System (BMS)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	1	**Related CT Areas:**	CT.AIR.INDOOR			**Assets included in this PM:**	BMS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

BMS connects the base building assets and systems across the building to allow them to be monitored and controlled. For example a BMS can: Maintain the temperature and humidity of HVAC system as well as received notifications in case of alarm status of a unit, etc.
Note: This standard maintenance is applicable for all sites with an AMZ BMS system (Niagara / Jace controller installed)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This standard maintenance is applicable for all sites with an AMZ BMS system (Niagara / Jace controller installed)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	BMS online & BBA	Check if the site is online in the BMS		SC		SC		PM				
2	BMS online & BBA	Check the system throught the User Interface, examine plant for proper control, review active alarms		SC		SC		PM				
3	BMS online & BBA	Identify issue cause through further testing, examine trend logs etc		SC		SC		PM				
4	BMS online & BBA	If defect cannot be iliminated, create APM WO for plant related defects or SIM to BMS support as appropriate		SC		SC		PM				
5	Control & device check	Check the sensor values, drives, fans, actuator etc through the BMS User Interface and compare it with expected values in the field.				SC		PM				
6	Control & device check	If values are detected to be out of expected range, confirm this in the field using suitable test eqipment such as Environental HVAC tester to detmine cause				SC		PM				
7	Control & device check	If defect cannot be eliminated, create APM WO for plant and field device related defects or SIM to BMS support as appropriate				SC		PM				
8	Control & device check	Review BMS schedules to ensure that the most approrate schedule is in use for the plant, the building use, occupancy level etc. Optimise for frugal energy use.				SC		PM				
9	Control & device check	Review temprature setpoints and historic performance against RME Energy HVAC Standard Setpoints and ensure compliance				SC		PM				
10	Control & device check	Check the sensors and devices for visual damage						PM				
11	Control & device check	Meters - Read all meter values at the meter and compare it to the value displayed in the BMS.						PM				
12	Control & device check	Change setpoints and check correct operation of controlled devices						PM				
13	Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM				
14	Control cabinet	Check if the circuit diagram is complete & no handwritten changes have been done						PM				
15	Control cabinet	Are all cables properly routed						PM				
16	Control cabinet	Are all cables, terminal blocks & devices properly labeled and no obvious changes have been carried out (e.g. rewiring, hanging cables)						PM				
17	Control cabinet	Visual check for the protection against direct contact with live part						PM				
18	Control cabinet	Tight cable connections in the control cabinets						PM				
19	Control cabinet	Are all metal parts connected to the protection earth (ground)						PM				
20	Control cabinet	Replace the air filters of the panel & check operation of cooling fan						PM				
21	Final check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removing requirement for firmware check according to BMS team.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUS SHELTER - 14
APM Object	BLDG.BUSSHELTER
APM EC	AMZ.BLDG.BUSSHELTER
BBM Handbook Title	Bus Shelter
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	BUS SHELTER	**Schedule With:**	BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.EXT BLDG.GATEBARRIER LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

Bus Shelter

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Cladding	Check if the cladding is free from damage & graffiti				SC						
2	Roof	Check if the roof is free from damage & leakage				SC						
3	Drainage	Check if the gutter & drainage pipes are free from damage, blockage & leakage				SC						
4	Lighting	Check if the lighting is working properly				SC						
5	Seats	Check if the seats are free from damage				SC						

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, CRANES - 14
APM Object	BLDG.CRANES
APM EC	AMZ.BLDG.CRANES
BBM Handbook Title	Cranes and Hoists (Lifting equipment)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	14	**Related CT Areas:**	CT.LIFT.HOIST			**Assets included in this PM:**	CRANES AND HOISTS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Cranes and Hoists (Lifting equipment)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Foundations	Visual inspection of the anchorage attachment for visible damage						PM				
3	Beam elements	Visual inspection of supports, beams, bars, bolts, thread lockers, joints, butt joints, welds, floor attachment and wall attachment for visible damage						PM				
4	Ascents and catwalks	Visual inspection of steps, rungs and stiles for damage. Check the fixed installations and condition of the covering of e.g. catwalks, platforms for defects. Check the protection against falling (handrails, back protection) for missing parts						PM				
5	Crane & trolley drive ban	Visually inspect the tracks, track supports, fasteners, warping, gauge attachments & welded joints for deformations, damage, corrosion and cracks. Perform visual and functional inspections of wind protection, track suspension,						PM				
6	Motor	Visual inspection of the impellers, bearings, axles, shafts, couplings, compensating rollers with pins and gears, drums, rollers, hydraulic and pneumatic components for visible damage. Lubrication of the impellers, drums and rollers. Noise						PM				
7	Brakes and slipping clutch	Visual inspection of brake discs, brake linkages, auxiliary brake, suspensions and attachments for damage. Lubricate the brake linkages. Functional check of the brakes and auxiliary brake: Check braking distance and readjust brake stroke or						PM				
8	Pipes	Visual inspection of fixed/movable pipes for damage						PM				
9	Hoist	Check the ropes, roller chains, load hooks and round steel chains for damage and adjust them if necessary. In addition, measure the length and compare it with the EU/DIN standard.						PM				
10	Electrical components	Are all cables properly routed and attached						PM				
11	Electrical components	Are all electrical terminations secure						PM				
12	Marking and signage	Signs, notices, and identification of hazardous locations are visibly attached and in place. These are complete and legible. The inspection book is present, complete and legible.						PM				
13	Test label	The test labels are attached and present in the correct places.						PM				
14	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DISABLED CALL POINT - 10
APM Object	BLDG.DISABL.CLLPNT
APM EC	AMZ.BLDG.DISABL.CLLPNT
BBM Handbook Title	Disabled Call Point - (toilet alarm)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	Not Identified	**Assets included in this PM:**	DISABLED CALL POINT	**Schedule With:**	BLDG.TOIL				

Description of System / Technology (According to BBM Handbook)

Disabled Call Point - (toilet alarm) - They provide two way communication

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: Combine the maintenance with the toilet check.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Function	Carry out a functional test of the disabled toilet alarm		SC								
2	Function	Is there any damage to the emergency switch (cord), indication light or other components		SC								
3	Final Check	Check the O&M manual & local requirements and carry out additionally required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DOORS - 2 and 4
APM Object	BLDG.DOOR
APM EC	AMZ.BLDG.DOOR
BBM Handbook Title	Doors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	2 and 4	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	DOORS	**Schedule With:**	BLDG.WINDOWS BLDG.SHADING		

Description of System / Technology (According to BBM Handbook)

The function of normal/manual doors are just the closure of a room or area within the building without any additional requirement (no fire protection or any automatic functionality). This slide represent interior & exterior assets.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
2	Door	Is the door leaf free from damage and corrosion						PM				
3	Door	Are the door hinges free from damage and corrosion						PM				
4	Door	Clean and lubricate hinges if required						PM				
5	Door	Is the door frame free from damage and corrosion						PM				
6	Door	Does the door move smoothly without resistance and doesn`t drag on the floor or door frame						PM				
7	Door	Are all door sealing ok						PM				
8	Door	Does the door close properly and stay close						PM				
9	Door	If an automatic closer installed, does the door close smoothly & completely						PM				
10	Door	Are the door mechanisms functioning correctly (handles & lock)						PM				
11	Door	Door handle does not hit the wall when opening						PM				
12	Door	Doorstop is properly fixed						PM				
13	Door	It is possible to lock the door properly						PM				
14	Door	Check pinch protection for damage and correct function						PM				
15	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DOORS, AUTOMATIC DOORS - 2 and 4
APM Object	BLDG.DOOR.AUTODOOR
APM EC	AMZ.BLDG.AUTODOOR
BBM Handbook Title	Automatic Doors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2 and 4	**Related CT Areas:**	CT.WORK.AUTOGATE-PEDESTRIAN			**Assets included in this PM:**	AUTOMATIC DOORS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Doors open only when activated and automatically close so to eliminate the doors being left open. They also prevent air conditioning from escaping and outside air and dust from entering. This slide represent interior & exterior assets.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
2	Safety	Does the panic door opening work correctly (in the case of an emergency escape door)						PM				
3	Safety	Check pinch protection for damage and correct function						PM				
4	Safety	Check for correct function of safety switches and sensors						PM				
5	Door	Is the door leaf free from damage and corrosion						PM				
6	Door	Are the door hinges free from damage and corrosion						PM				
7	Door	Clean and lubricate relevant mechanical components						PM				
8	Door	Is the door frame free from damage and corrosion						PM				
9	Door	Is the door operating smoothly without resistance, free from dragging on the floor, making contact with the door frame, or getting stuck at any point						PM				
10	Door	Are door sealings ok						PM				
11	Door	Does the door close properly and stay close						PM				
12	Door	Does the door close smoothly and fully without obstruction						PM				
13	Door	Are the mechanisms, including handles and locks, functioning correctly						PM				
14	Door	Door handle does not hit the wall when opening						PM				
15	Door	Doorstop is properly fixed						PM				
16	Door	It is possible to lock the door properly						PM				
17	Door	Inspect the motor, gears, and drive belts for wear and tear						PM				
18	Electrical components	Ensure that the door's speed is within the manufacturer's recommended range						PM				
19	Electrical components	Check for correct operation of drive mechanism Lubricate and adjust as necessary						PM				
20	Electrical components	Check motor overload for correct function						PM				
21	Electrical components	Check condition and correct function of limit switches Adjust if necessary						PM				
22	Electrical components	Check the control elements for damage and correct function						PM				
23	Electrical components	Check if cables are properly routed and free from damage						PM				
24	Electrical components	Ensure all cable terminations are secure						PM				
25	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Added tasks and changed wording

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DOORS, ROLLER DOORS - 2
APM Object	BLDG.DOOR.RLRDOORS
APM EC	AMZ.BLDG.RLRDOOR
BBM Handbook Title	Roller Door
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	ROLLER DOOR	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A roller shutter door is a door constructed from many individual steel or aluminium horizontal slats and operated by rolling the slats around a barrel directly up or down, with the assistance of either a spring, chain operated gearing, or an electric motor (or both) and guides either side to hold the curtain secure in place.
Note: This is not a Dock Door

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
3	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
4	Safety	Check for correct function of safety switches.						PM				
5	Door	Are the roller door slats free from damage and corrosion						PM				
6	Door	Are the frames free from damage and corrosion						PM				
7	Door	Does the door move smoothly without resistance						PM				
8	Door	Is the door sealing ok						PM				
9	Door	Are manual operating devices functioning properly						PM				
10	Tracks	Are wall tracks fixed properly, free of damage & corrosion						PM				
11	Electromechanical components	Check for correct operation of motor and mechanism Lubricate and adjust as necessary						PM				
12	Electromechanical components	Check motor overload for correct function						PM				
13	Electromechanical components	Check condition and correct function of limit switches Adjust if necessary						PM				
14	Electromechanical components	Check the control elements for damage, correct function & alarms						PM				
15	Electromechanical components	-> eliminate the root cause if an alarm is indicated						PM				
16	Electromechanical components	Check if cables are properly routed and free from damage						PM				
17	Electromechanical components	Ensure all cable terminations are secure						PM				
18	Functional cleaning	Carry out a functional cleaning and lubricate necessary moving parts						PM				
19	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DRAINAGE SYSTEM - 5
APM Object	BLDG.DRAIN
APM EC	AMZ.BLDG.DRAIN
BBM Handbook Title	Drainage System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	5	**Related CT Areas:**	CT.FAC.DRAIN			**Assets included in this PM:**	DRAINAGE SYSTEM	**Schedule With:**	BLDG.TOIL		

Description of System / Technology (According to BBM Handbook)

Water drainage system from mains water internally. This does not include rain water drainage.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Clogging	If there are signs of clogging, schedule a CCTV inspection asap					SC	SC		SC		
2	General	Is the documentation of installed BBA available & complete						SC		SC		
3	Drainage inlets	Check of basin, shower, etc. drainage for damage, dirt and free drainage - clean if clogged					SC	SC		SC		
4	Drainage inlets	Check of basin drains for leaks (visual parts, e.g. siphon)					SC	SC		SC		
5	Drainage inlets	Check of the floor drains & drain grids for damage, dirt and free drainage - clean if clogged					SC	SC		SC		
6	Drainage inlets	Check water level and top up if necessary to prevent outgassing (siphon)					SC	SC		SC		
7	Drainage pipe system	Check for damage & corrosion of the drain pipes, insulation, suspension						SC		SC		
8	Drainage pipe system	Check the pipe system for impermissible & unwanted pipe openings - close immediately						SC		SC		
9	Drainage pipe system	Open maintenance flaps & check drain pipe inside for deposits and clogging						SC		SC		
10	Manual valves	Check manual valve for correct function, corrosion, dirt deposits and leaks					SC	SC		SC		
11	Automatic valves	Functional test of automatic valves of the drainage system (primarily pollution control valves)						SC		SC		
12	Pipe ventilation valves	Check if the ventilation valves are accessible, functioning correctly and free from leaks						SC		SC		
13	Pipe ventilation	Check that the pipe ventilation outlet is free from dirt and protected from rainwater						SC		SC		
14	Shaft & pit inside the building	Check if the shaft or pit is freely accessible, is free from deposit & damage (inside the building)						SC		SC		
15	Shaft & pit inside the building	Check the climbing aids in the shaft or pit for damage, corrosion and proper installation (inside t b)						SC		SC		
16	Drainage pipe system	Carry out a camera inspection of the drainage system (inside the drain pipes)								SC		
17	Final Check	Check the O&M manual & local requirements (e.g.Environmental requirements & building permit) and carry out additional required tasks								SC		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DRINK WATER DISPENSERS - 5
APM Object	BLDG.DWDISP
APM EC	AMZ.BLDG.WTRDISP
BBM Handbook Title	Drinking Water Dispensers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	5	**Related CT Areas:**	CT.WATER.DRINKING CT.WATER.LEGIONELLA			**Assets included in this PM:**	DRINK WATER DISPENSERS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Drinking Water Dispensers.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Ensure spare parts like filter cartridges, aerator, etc. are always on stock to enable a smooth PM process.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete				PM						
2	Cover & functionality	Is the unit/cover free from damage				PM						
3	Cover & functionality	Test water dispenser for correct function				PM						
4	Cover & functionality	Test UV light for correct function (if installed)				PM						
5	Gas	Check the CO2 bottle with regard to pressure level (only for unit with sparkling water)				PM						
6	Gas	Check CO2 components for leaks (only for unit with sparkling water)				PM						
7	Gas	Ensure that the CO2 bottle instructions and warning signs are clearly visible, and verify that the correct bottle is in use. (only for unit with sparkling water)				PM						
8	Water	Check water supply hose/pipe for leaks or wear				PM						
9	Water	Check water pipes inside the unit for leaks or wear				PM						
10	Water	Check pumps and valves for correct function				PM						
11	Water	Change water outlet/aerator if applicable				PM						
12	Functional cleaning	Functional clean and test of the fan, compressor & heat exchanger				PM						
13	Functional cleaning	Carry out a functional test of unit drainage system				PM						
14	Functional cleaning	Cleaning of drip tray and base cabinet				PM						
15	Filter cartridge	Check filter cartridge for proper function and change if necessary (max change interval 6 month) -> Add a note in case of a filter change				PM						
16	Cooling	Renew water of the ice bank				PM						
17	Cooling	Check correct function of the ice bank circulation device (e.g., propeller)				PM						
18	Electrical components	Check all cables for signs of wear and exposed live parts, such as abrasion.				PM						
19	Hygiene	Disinfection of all water-carrying components according to instructions				PM						
20	Hygiene	Check water quality with test strips				PM						
21	Hygiene	Ensure testing for legionella and microbiological contamination are carried out according to local requirements				PM						
22	Final Check	Check the O&M manual & local rwuirements and carry out additional required tasks				PM						

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed "gas" in the component cell. Added tasks regarding cooling and electrical components according to the lesson learned during on-site deep dive. Added task according to the gas components.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, EARTHING SYSTEM - 11
APM Object	BLDG.EARTHING
APM EC	AMZ.BLDG.EARTHING
BBM Handbook Title	Earthing System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.DISCHARGE			**Assets included in this PM:**	EARTHING SYSTEM	**Schedule With:**	ELEC.LV.CABS ELEC.MET ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD		

Description of System / Technology (According to BBM Handbook)

An earthing system connects specific parts of an electric power system with the ground, typically the Earth's conductive surface, for safety and functional purposes. The choice of earthing system can affect the safety and electromagnetic compatibility of the installation.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note: Measurements of the resistance needs to be aligned with compliance tasks

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
2	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
3	General check	Are all cables labeled correctly						PM				
4	Earthing system	Are all earthing connections to the building ground correct, tight, free from damage & corrosion						PM				
5	Earthing system	Carry out resistance measurement on main lines, compare to design and local requirements						PM				
6	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, EMERGENCY EXIT DOORS - 4
APM Object	BLDG.EMERDOOR
APM EC	AMZ.BLDG.EMERDOOR.GRP
BBM Handbook Title	Emergency Exit Doors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jan-25	**Geo Applied:**	Not Listed	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	4	**Related CT Areas:**	CT.FIRE.DOORS			**Assets included in this PM:**	EMERGENCY EXIT DOOR	**Schedule With:**	FIRE.FLS.FIREDOOR FIRE.FLS.HOLDDOOR		

Description of System / Technology (According to BBM Handbook)

Emergency exit doors are structural elements designed to allow for a quick and secure exit from a building during an emergency.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Visual check	Inspect all mechanical parts, like hinges, and tracks for physical damage, corrosion, or wear						PM				
2	Visual check	Check for obstructions or debris that might impede door operation						PM				
3	Visual check	Ensure proper alignment of doors with manual and automatic openers						PM				
4	Automatic Opener	Simulate fire alarm activation to verify the automatic door opener's response - Combine with yearly test of the fire matrix						PM				
5	Automatic Opener	Test integration with the fire alarm system, ensuring all signals are properly received and executed - Combine with yearly test of the fire matrix						PM				
6	Automatic Opener	Confirm smooth and timely door opening without mechanical resistance or delays						PM				
7	Manual Opener	Verify that the manual safety opener operates as intended, overriding the automatic system, if necessary						PM				
8	Manual Opener	Test the noise alert mechanism to ensure activation during manual operation						PM				
9	Manual Opener	Inspect the manual override mechanism for wear, corrosion, or misalignment						PM				
10	Mechanical Component	Lubricate hinges, tracks, and other moving components to reduce friction and ensure smooth operation						PM				
11	Mechanical Component	Tighten screws, bolts, and other fasteners						PM				
12	Mechanical Component	Remove any obstacles near the doors that could block their operation						PM				
13	Electrical Components	Inspect all wiring and electrical components for signs of damage and ensure there are no exposed live parts						PM				
14	Electrical Components	Test the backup power system (e.g., batteries or generators) for functionality during power outages						PM				
15	Electrical Components	Confirm the integrity of all electrical components and connections						PM				
16	Calibration	Test and calibrate sensors to ensure tcorrect detection						PM				
17	Calibration	Verify the noise alert system activates appropriately during manual override						PM				
18	Functional Cleaning	Clean all components, including doors, sensors, and tracks, to prevent buildup of dirt or debris that could cause an reliability issue						PM				
19	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

JAN 2025 - New PM after OCB update in 2024

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUILDING EXTERIOR - 2
APM Object	BLDG.EXT
APM EC	AMZ.BLDG.EXT
BBM Handbook Title	Building Exterior
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	BARRIERS - GATEHOUSE - YARD - PERIMITTER FENCING	**Schedule With:**	BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.GATEBARRIER LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

Green areas around the warehouse (yard and parking area).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Perform a walk at the exterior areas of the site & perform the tasks below					SC					
2	Protection Barriers	Are protection barriers fixed properly and free from damage					SC					
3	Gates	Are gates fixed properly, free from damage and operating correctly					SC					
4	Illuminated signage Inclusive totem signs	Check all illuminated signages around the building and parking areas for correct function and damage					SC					
5	Gatehouse	Is the entrance freely accessible & free of obstacles					SC					
6	Gatehouse	Visually check for damage or excessive vegetation at the building or around					SC					
7	Gatehouse	Check for damage or corrosion at easily accessible cable trays and other installation					SC					
8	Gatehouse	Is it possible to lock the door properly - protection against unauthorized entry					SC					
9	Gatehouse	Does the light work properly					SC					
10	Gatehouse	Are there any water leaks visible at the walls or ceiling inside the gatehouse					SC					
11	Gatehouse	Visiually check for damage to the floor, walls or ceiling inside the gatehouse					SC					
12	Gatehouse	Are technical installations damaged or loose - inside the gatehouse (e.g. cable trays, MCP, fire extinguisher)					SC					
13	Gatehouse	Are flammable or unnecessary goods stored in the room					SC					
15	Yard	Check the yard floor for damage, for obstacles blocking emergency escape ways, emergency stairwells & emergency assembly points					SC					
16	Perimeter Fencing	Check the perimeter fencing for damage					SC					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Moving the task exterior walls/cladding to BLDG.STRUCTURE PM and changing the frequency of this task from 6M to 12M.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, EXTERIOR SURFACES - 3
APM Object	BLDG.EXTSURFACES
APM EC	AMZ.BLDG.EXTSURFACES
BBM Handbook Title	Exterior Surfaces
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	3	**Related CT Areas:**	CT.FAC.BUILDING			**Assets included in this PM:**	ROADS/PAVEMENTS - ROAD SIGNS - SPEED BUMPS - CAR PARK	**Schedule With:**	BLDG.EXT BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.GATEBARRIER LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

All surfaces and installed equipment throughout the parking area

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
This maintenance is specifically for the parking areas and doesn`t include the yard.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	ROADS / PAVEMENTS	Check the ground surfaces for damage and unwanted vegetation						SC				
2	ROADS / PAVEMENTS	Are flammable or unnecessary goods stored						SC				
3	ROADS / PAVEMENTS	Ensure all salt boxes and storage units are fully stocked for winter readiness						SC				
4	Road Signs - line marking, etc.	Check line marking for damage						SC				
5	Road Signs-speed bumps, etc.	Check the speed bumps & tire stops for correct seating (securely fixed) and damage						SC				
6	Road Signs-speed bumps, etc.	Check all road signs for damage & corrosion						SC				
7	Multi storage car park specific	Are there any water leaks visible at the walls or ceiling						SC				
8	Multi storage car park specific	Does the light work properly						SC				
9	Multi storage car park specific	Check walls and ceilings for damage & corrosion						SC				
10	Multi storage car park specific	Are technical installations damaged or loose (e.g. cable trays, MCP, fire extinguisher)						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removing in the asset related cell: Speed bumps / tire stops.
Aug 2024 - Added task to check for salt storage

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, FUEL STORAGE TANKS - 8
APM Object	BLDG.FUELSTOR
APM EC	AMZ.BLDG.FUELSTOR
BBM Handbook Title	Fuel Storeage Tanks
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jan-25	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	8	**Related CT Areas:**	CT.ENVIRO.OIL			**Assets included in this PM:**	FUEL STORAGE TANKS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Fuel Storeage Tanks - Emergency Fuel Systems
Typically a tank which holds diesel for the fire pump system.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This PM is designated to all fuel systems used on site to supply generators and engine driven pumps like sprinkler pumps.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Fuel system	Are all components labeled correctly			PM			PM				
2	Fuel system	Visual inspection of all fuel system components for leakages			PM			PM				
3	Functional cleaning	Carry out a functional cleaning of the fuel system			PM			PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)			PM			PM				
5	Fuel pump - elec. & mech.	Inspect pumps for damage, corrosion and unusual noise (if fuel pump is installed)			PM			PM				
6	Fuel pump - elec. & mech.	Is the device properly fixed -> retighten if required (if fuel pump is installed)			PM			PM				
7	Fuel pump - elec. & mech.	Check if the pump is functioning correctly (if fuel pump is installed)			PM			PM				
8	Fuel filter	Change fuel filter			PM			PM				
9	Valves	Check valves for leakage, corrosion & damage			PM			PM				
10	Valves	Check all valves, incl. automatic & safety valves for correct function			PM			PM				
11	Tank	Check fuel tank for leakage corrosion & damage			PM			PM				
12	Monitoring	Check position/limit value transmitter and limit position switch for correct function			PM			PM				
13	Monitoring	Calibrate all sensors and check correct alarm indication						PM				
14	Final Check	Check the O&M manual and tank permit and carry out additional required tasks			PM			PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed APM Description according to the BBM Handbook.
Removed the Grease bearing task because it is not applicable to this kind of pump. Removed task regarding CE certification.
Jan 2025 - Added tasks to fulfill Compliance Standards requirements and changed WO type from `SC`to `PM`

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, GATE BARRIERS - 2
APM Object	BLDG.GATEBARRIER
APM EC	AMZ.BLDG.GATEBARRIER
BBM Handbook Title	Automatic Gate Barrier
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	AUTOMATIC GATE BARRIER	**Schedule With:**	BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.EXT LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

Automatic barriers ideal for
managing the access and control of vehicles in communal areas, car parks, industries, etc.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
3	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
4	Safety	Check for correct function of safety switches						PM				
5	Barrier	Is the barrier functioning correctly						PM				
6	Barrier	Are there any unusual noises or vibration?						PM				
7	Barrier	Are manual operating devices functioning properly						PM				
8	Intercom	Does the intercom work correctly						PM				
9	Electromechanical components	Check for correct operation of motor and mechanism Lubricate and adjust as necessary						PM				
10	Electromechanical components	Check motor overload for correct function						PM				
11	Electromechanical components	Check condition and correct function of limit switches Adjust if necessary						PM				
12	Electromechanical components	Check the control elements for damage, correct function & alarms						PM				
13	Electromechanical components	-> eliminate the root cause if an alarm is indicated						PM				
14	Electromechanical components	Check if cables are properly routed and free from damage						PM				
15	Electromechanical components	Ensure all cable terminations are secure						PM				
16	Functional cleaning	Carry out a functional cleaning and lubricate necessary moving parts						PM				
17	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, GREASE SEPARATOR - 5
APM Object	BLDG.GREASESEP
APM EC	AMZ.BLDG.GREASESEP
BBM Handbook Title	Grease Separator– Interceptors (Waste water containing grease)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	5	**Related CT Areas:**	CT.ENVIRO.INTERCEPTOR	**Assets included in this PM:**	GREASE SEPARATOR	**Schedule With:**	BLDG.OILSEP				

Description of System / Technology (According to BBM Handbook)

Grease Separator Interceptors (Waste water containing grease)
ACO Grease Capture removes fat, oil and grease from waste water before it enters the drainage system and protects against blockages and the build up of Fatbergs. Mainly used in kitchen environments.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note - The drainage system to be checked within this maintenance is the pressure pipe system.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Guideline	If there are signs of clogging, schedule a CCTV inspection asap			PM			PM				
2	Documentation	Is the documentation of installed BBA available & complete						PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)			PM			PM				
5	Safety	Test all safety relevant switches						PM				
6	Separator unit	Check pumps, pipes, chambers and attachments for damage, corrosion, correct suspension & leakage			PM			PM				
7	Separator unit	Visual inspection of the water level			PM			PM				
8	Separator unit	Empty & clean the unit (inside & outside) –In Spain it is mandatory (compliance) every 6 months						PM				
9	Separator unit	Check for any signs of leakage			PM			PM				
10	Separator unit	Empty unit & carry out a functional celaning the unit (inside & outside)			PM			PM				
11	Separator unit	Clean and check function of backflow prevention						PM				
12	Separator unit	Check correct function and alarms of the system			PM			PM				
13	Pump & panel	If more than 1 pump installed, check if pumps starts one after the other						PM				
14	Pump & panel	Check the pumps for unusual noise & vibration (bearing and impeller)						PM				
15	Pump & panel	Measure power consumption of the pumps and compare to design						PM				
16	Pump & panel	Are all cables properly routed						PM				
17	Pump & panel	Are all cables, terminal blocks & devices properly labeled or marked						PM				
18	Pump & panel	Are all metal parts of the unit connected to the protection earth (ground)						PM				
19	Pump & panel	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
20	Pump & panel	Visual check of cable connections such as pinched insulation in the contact area						PM				
21	Pump & panel	Visual check for the protection against direct contact with live parts						PM				
22	Pump & panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
23	Drainage pipe system	Are the pipes on the pressure site installed correctly, free from damage and are the suspensions ok						PM				
24	Valves	Check correct function of all manual & automatic valves						PM				
25	Valves	Check valves for corrosion, dirt deposits and leakage						PM				
26	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM description as shows the BBM Handbook.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, HEARING LOOP - 10
APM Object	BLDG.HEARING.LOOP
APM EC	AMZ.BLDG.HEARING.LOOP
BBM Handbook Title	Hearing Loop (system to support deaf people)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	HEARING LOOP	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Vibrating device to alert deaf people in case of emergency alarm

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Forecast the functional test together with the 3 monthly PM of the fire detection system

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						SC				
2	Functional test	Carry out a functional test of the equipment				SC		SC				
3	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUILDING INTERIOR - 4
APM Object	BLDG.INT
APM EC	AMZ.BLDG.INT
BBM Handbook Title	Building Interior
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	TECHNICAL ROOMS	**Schedule With:**	BLDG.STRUCTURE BLDG.MEZZANINE		

Description of System / Technology (According to BBM Handbook)

This system has been created only for the allocation of Standard PM's which will cover all: internal structures, ceilings and floors. The Building Interior system has been created to reduce the number of proactive WOs and administrative workload. This system is not to be used for reactive WO's
BLDG.STRUCTURE
BLDG.CEILINGS

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Technical Rooms	Check all technical rooms for alarms, leaks, unnecessarily stored equipment, correct functioning of safety equipment and obvious damage		SC								

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Moved tasks regarding with ceiling, floor and structure/walls to BLDG.STRUCTURE PM.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, LIGHTNING PROTECTION SYSTEM - 11
APM Object	BLDG.LIGHTNING
APM EC	AMZ.BLDG.LIGHTNING
BBM Handbook Title	Lightning Protection System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.LIGHTNING CT.ELEC.DISCHARGE			**Assets included in this PM:**	LIGHTNING PROTECTION SYSTEM	**Schedule With:**	BLDG.ROOF		

Description of System / Technology (According to BBM Handbook)

Lightning Protection System comprises of a metal rod know as a Lightning Rod mounted on a structure which is intended to protect the structure from a lightning strike. If lightning hits the structure, it will preferentially strike the rod and be conducted to ground through a wire, instead of passing through the structure.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note: Measurements of the resistance needs to be aligned with compliance tasks

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
2	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
3	Lightning protection system	Check all lightening protection lines and line connections tight, correctly grounded and free from damage and corrosion						PM				
4	Lightning protection system	Carry out resistance measurement & compare to design						PM				
5	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, WASTE MACERATOR PUMPS - 5
APM Object	BLDG.MCRTRPMP
APM EC	AMZ.BLDG.MCRTR.PMP
BBM Handbook Title	Waste Macerator Pumps
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	5	**Related CT Areas:**	CT.SEWAGE.SEWAGEPUMP			**Assets included in this PM:**	WASTE MACERATOR PUMP	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Waste Macerator Pumps

A Waste Macerator pump converts waste solids and fluids into a fine slurry that is discharged under pressure through small diameter pipe and is expelled into the sewage line or septic tank.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note - The drainage system to be checked within this maintenance is the pressure pipe system.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Guideline	Inspect for signs of clogging				PM		PM				
2	Documentation	Is the documentation of installed equipment available & complete						PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
5	Safety	Test all safety relevant switches						PM				
6	Pump & panel	Measure power consumption of the pumps and compare to design						PM				
7	Pump & panel	Are all cables properly routed						PM				
8	Pump & panel	Are all cables, terminal blocks & devices properly labeled or marked						PM				
9	Pump & panel	Are all metal parts of the unit connected to the protection earth (ground)						PM				
10	Pump & panel	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
11	Pump & panel	Visual check of cable connections such as pinched insulation in the contact area						PM				
12	Pump & panel	Visual check for the protection against direct contact with live parts						PM				
13	Pump & panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
14	Macerator pump unit	Check pumps, pipes, chambers and attachments for damage, corrosion, correct suspension & leakages				PM		PM				
15	Macerator pump unit	Check the pumps for unusual noise & vibration (bearing and impeller)				PM		PM				
16	Macerator pump unit	Check if the unit is functioning correctly				PM		PM				
17	Macerator pump unit	Check condition of filters and schedule an exchange if required (if applicable)				PM		PM				
18	Macerator pump unit	Check if the level switch is functioning correctly and triggers start of the pump						PM				
19	Macerator pump unit	If more than 1 pump installed, check duty and standby arrangement is functional				PM		PM				
20	Macerator pump unit	Clean the container (inside & outside)						PM				
21	Macerator pump unit	Check for damage &corrosion						PM				
22	Macerator pump unit	Remove Pump and Clean inlet / impeller						PM				
23	Macerator pump unit	Check oil level of oil chamber (if oil chamber is installed)						PM				
24	Macerator pump unit	Clean and check function of backflow prevention						PM				
25	Drainage pipe system	Are the pipes on the pressure site installed correctly, free from damage and are the suspensions ok						PM				
26	Valves	Check correct function of all manual & automatic valves						PM				
27	Valves	Check valves for corrosion, dirt deposits and leakages						PM				
28	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 24M because it has the same tasks that 12M.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, METAL DETECTORS - 14
APM Object	BLDG.METALDET
APM EC	AMZ.BLDG.METALDET
BBM Handbook Title	Metal Detectors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	14	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	METAL DETECTORS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Metal Detectors

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						SC				
2	Safety	Check the safety devices for correct function						SC				
3	Metal detector	Check of the metal detector for damage and corrosion						SC				
4	Metal detector	Carry out a functional test using the right type of material Plan a calibration if required						SC				
5	Metal detector	Check for any signs of moisture at the unit and if gaskets are in correct order						SC				
6	Electrical components	Is the area properly illuminated						SC				
7	Electrical components	The cables are routed and fixed properly						SC				
8	Electrical components	Electrical terminations are secure						SC				
9	Functional cleaning	Carry out a functional cleaining of the metal detector unplugged using neutral detergant						SC				
10	Functional cleaning	Carry out a functional cleaining of the metal detector unplugged using neutral detergant						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, MEZZANINES - 4
APM Object	BLDG.MEZZANINE
APM EC	AMZ.BLDG.MEZZANINE.GRP
BBM Handbook Title	Mezzanines
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.FAC.BUILDING			**Assets included in this PM:**	MEZZANINES	**Schedule With:**	BLDG.STRUCTURE BLDG.INT		

Description of System / Technology (According to BBM Handbook)

Mezzanines - Raised access floors/metal mezzanines

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						SC				
2	Steelworks	Are there visible deformations, cracked welds, broken or missing bolts/nuts/rivets in the joints						SC				
3	Steelworks	Check for corrosion or other damage						SC				
4	Safety	Are there missing plates which could cause an injury						SC				
5	Safety	Are handrails and other protective equipment fixed properly, free from damage & corrosion						SC				
6	Safety	Is the walkway free from blocking obstacles						SC				
7	Safety	Are emergency letter, etc. freely accessible, functioning properly & free from damage						SC				
8	Lighting	Is the lighting in the accessible area sufficient						SC				
9	Steelworks	Check if suspended and attached equipment is loose, missing or defect						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Updated task plan, adding task 7 and 8.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, OIL SEPARATOR - 5
APM Object	BLDG.OILSEP
APM EC	AMZ.BLDG.OILSEP.GRP
BBM Handbook Title	Oil Separator (Waste water containing oil / gasoline)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	5	**Related CT Areas:**	CT.ENVIRO.INTERCEPTOR			**Assets included in this PM:**	OIL SEPARATOR	**Schedule With:**	BLDG.GREASESEP		

Description of System / Technology (According to BBM Handbook)

Oil Separator (Waste water containing oil / gasoline)

Oil separators are designed to prevent oil and other hydrocarbons from entering the drainage system. They separate oil from water, and safely retain the oil until it is removed. Oil cannot be treated easily and will therefore cause severe pollution if allowed to enter mains sewers or drainage fields. Statutory controls enforce strict regulations on the discharge of such pollutants. Oil separators should be used in such applications as petrol stations, industrial yards and garages; or virtually anywhere that a risk of oil contamination exists. Discharge requirements for oil separators may vary by region.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note - The drainage system to be checked within this maintenance is the pressure pipe system.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Guideline	If there are signs of clogging, schedule a CCTV inspection asap					PM	PM				
2	Documentation	Is the documentation of installed BBA available & complete						PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)					PM	PM				
5	Safety	Test all safety relevant switches						PM				
6	Separator unit	Check pumps, pipes, chambers and attachments for damage, corrosion, correct suspension & leakage					PM	PM				
7	Separator unit	Measurement of the layer thickness of the light liquids in the separator					PM	PM				
8	Separator unit	Schedule an emptying & cleaning if required as FWO (Waste Transfer Note must be provided)			SC		PM	PM				
9	Separator unit	Measure the sludge level					PM	PM				
10	Separator unit	Visual inspection of the water level before & after the coalescence separator (if installed)					PM	PM				
11	Separator unit	Check for any signs of leakage			SC		PM	PM				
12	Separator unit	Check the correct function of the coalescing device (if installed)					PM	PM				
13	Separator unit	Empty & clean the unit (inside & outside)					PM	PM				
14	Separator unit	Check for damage & corrosion						PM				
15	Separator unit	Clean and check function of backflow prevention						PM				
16	Separator unit	Check unit correct function if applicable					PM	PM				
17	Pump & panel	Check whether an alarm is displayed			SC			PM				
18	Pump & panel	If more than 1 pump installed, check if pumps starts one after the other						PM				
19	Pump & panel	Check the pumps for unusual noise & vibration (bearing and impeller)						PM				
20	Pump & panel	Measure power consumption of the pumps and compare to design						PM				
21	Pump & panel	Are all cables properly routed						PM				
22	Pump & panel	Are all cables, terminal blocks & devices properly labeled or marked						PM				
23	Pump & panel	Are all metal parts of the unit connected to the protection earth (ground)						PM				
24	Pump & panel	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
25	Pump & panel	Visual check of cable connections such as pinched insulation in the contact area						PM				
26	Pump & panel	Visual check for the protection against direct contact with live parts						PM				
27	Pump & panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
28	Drainage pipe system	Are the pipes on the pressure site installed correctly, free from damage and are the suspensions ok						PM				
29	Valves	Check correct function of all manual & automatic valves						PM				
30	Valves	Check valves for corrosion, dirt deposits and leakage						PM				
31	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM description as shows the BBM Handbook.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, RAINWATER COLLECTORS - 3
APM Object	BLDG.RAINCOLL
APM EC	AMZ.BLDG.RAINCOLL
BBM Handbook Title	Rainwater Collectors- Rainwater drainage Systems
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	3	**Related CT Areas:**	CT.RAINWATERPUMP			**Assets included in this PM:**	RAINWATER COLLECTORS	**Schedule With:**	BLDG.EXT BLDG.EXTSURFACES BLDG.BUSSHELTER BLDG.GATEBARRIER LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

Rainwater Collectors - Rainwater drainage Systems
All surfaces and installed equipment throughout the parking area.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Drainage systems	Manholes/inspection shafts, grit chamber - check for dirt, damage and corrosion						SC				
2	Drainage systems	Clearing of the sand/dirt trap if necessary						SC				
3	Drainage systems	Clearing of gutters/rainwater inlets if necessary						SC				
4	Drainage systems	Schedule a cleaning of deposits around the rainwater inlets if necessary						SC				
5	Drainage systems	Check the main (accessible) drainage pipes for dirt deposit and schedule a flush truck for cleaning if necessary						SC				
6	Rain Water Retention	Check all water retention devices for correct functionality (Environmental protection)						SC				
7	Rain Water Retention	Check rain retention basins for clenliness and react appropriately if necessary (e.g. intense vegetation. etc.)						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Updating the APM Object according to the last OCB updates and the APM description as well.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, ROOF AND ROOF DRAINAGE - 7
APM Object	BLDG.ROOF
APM EC	AMZ.BLDG.ROOF.GRP
BBM Handbook Title	Roof and Roof Drainage
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	7	**Related CT Areas:**	CT.FAC.ROOFTOPINSPECT			**Assets included in this PM:**	ROOF AND ROOF DRAINAGE - ROOFLIGHTS	**Schedule With:**	BLDG.LIGHTNING		

Description of System / Technology (According to BBM Handbook)

Roof and Roof Drainage.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: Roof drainage up to the inlet in the base plate, from there PM under the drainage system.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of installed BBA available & complete - e.g. drainage, skylights						PM		PM		
2	Roof surface	Check if any kind material is stored on the rioof Schedule removal it in case of any kind of risk for the building or people			SC		SC	PM		PM		
3	Roof surface	Check for coarse dirt and gravel deposits on the roof Schedule cleaning the surface if required			SC		SC	PM		PM		
4	Roof surface	Check for unwanted vegetation from the roof Schedule removal it from any surface if required			SC		SC	PM		PM		
5	Roof surface	Visual check of the membrane including seam connection for obvious damage						PM		PM		
6	Roof surface	Gravel roof - check unwanted shifting of the gravel						PM		PM		
7	Roof surface	Gravel roof - check walkway plates for correct position & damage						PM		PM		
8	Roof surface	Visual check for water retention on the roof (visible puddles) Schedule action in case of any risk for the building or people			SC		SC	PM		PM		
9	Connections / Seals	Check the connections for damage (roof to facade, skylights & other structures)						PM		PM		
10	Drainage	Visual check for damage & dirt build-up of gutters Schedule cleaning gutters if necessary			SC		SC	PM		PM		
11	Drainage	Visual check of the surfaces around drainage inlets Schedule cleaning if debris accumulated			SC		SC	PM		PM		
12	Drainage	Visual check of the drainage inlet grids for damage & dirt Schedule cleaning if blocked (primary & secondary)			SC		SC	PM		PM		
13	Drainage	Dismount drain inlet grids, clean drain inlet and surrounding area						PM		PM		
14	Drainage	Syphonic system - dismount grid & check correct function of the flap						PM		PM		
15	Drainage	Visual check of drainage outlets incl. emergency outlets at the walls Schedule cleaning if blocked			SC		SC	PM		PM		
16	Drainage	Check if there are any damaged or loose parts at the drainage pipes which is attached to the building								PM		
17	Drainage pipe system	Carry out a camera inspection of the drainage system (inside the drain pipes)								PM		
18	Drainage pipe system	Check for damage of the drain pipes, insulation, suspension inside the building						PM		PM		
19	Drainage pipe system	Open maintenance flaps & check drain pipe inside for deposits and clogging								PM		
20	Roof installations	Check all handrails and other structures (installations) are not damaged & fixed properly					SC	PM		PM		
21	Rooflights	Check the rooflights for damage						PM		PM		
22	Roof installations	Check Installations (e.g. cable trays, pipe systems,etc.) for corrosion & damage								PM		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, SEWAGE SYSTEM, SEWAGE WATER PUMPS - 5
APM Object	BLDG.SEWAGE.WTRPMP
APM EC	AMZ.BLDG.SEWAGE.PMP
BBM Handbook Title	Sewage Water Pumps (including pressure pipe system)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	5	**Related CT Areas:**	CT.SEWAGE.SEWAGEPUMP			**Assets included in this PM:**	SEWAGE WATER PUMP	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Sewage Water Pumps (including pressure pipe)

A sewage pump (also known as an ejector pump) has a tank that collects sewage. When the waste reaches a certain level, the pump turns on and pushes the waste into a sewer system or septic tank.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note - The drainage system to be checked within this maintenance is the pressure pipe system.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Guideline	Inspect for signs of clogging						PM	PM			
2	General	Is the documentation of installed BBA available & complete						PM	PM			
3	Panel & Electrical components	Check wether an alarm is displayed			SC			PM	PM			
4	Panel & Electrical components	Measure power consumption of the pumps and compare to design						PM	PM			
5	Panel & Electrical components	Are all cables properly routed						PM	PM			
6	Panel & Electrical components	Are all cables, terminal blocks & devices properly labeled or marked						PM	PM			
7	Panel & Electrical components	Are all metal parts of the unit connected to the protection earth (ground)						PM	PM			
8	Panel & Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM	PM			
9	Panel & Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM	PM			
10	Panel & Electrical components	Visual check for the protection against direct contact with live parts						PM	PM			
11	Panel & Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM	PM			
12	Panel & Electrical components	Test all safety relevant switches						PM	PM			
13	Sewage lifting unit	Check the for signs of leaks			SC			PM	PM			
14	Sewage lifting unit	Check the pump for unusual noises or vibrations.			SC			PM	PM			
15	Sewage lifting unit	Check pumps, pipes, chambers and attachments for damage, corrosion, suspension & leaks						PM	PM			
16	Sewage lifting unit	Check the pumps for unusual noise & vibration (bearing and impeller)						PM	PM			
17	Sewage lifting unit	Check if the unit is functioning correctly						PM	PM			
18	Sewage lifting unit	Check condition of filters and schedule an exchange if required (if applicable)						PM	PM			
19	Sewage lifting unit	Check if the level switch is functioning correctly and triggers start of the pump						PM	PM			
20	Sewage lifting unit	Clean the inside of the container and check for corrosion						PM	PM			
21	Sewage lifting unit	Clean and check function of backflow prevention						PM	PM			
22	Sewage lifting unit	Check oil level of oil chamber (if oil chamber is installed)						PM	PM			
23	Sewage lifting unit	If more than 1 pump installed, check if pumps starts one after the other						PM	PM			
24	Sewage lifting unit	Clean Level Switch						PM	PM			
25	Sewage lifting unit	Remove Pump and Clean inlet / impeller							PM			
26	Pump gasket	Tighten the gland if applicable (gasket DE Stoffbuchse)						PM	PM			
27	Drainage pipe system	Are the pipes on the pressure site installed correctly, free from damage and are the suspensions ok						PM	PM			
28	Valves	Check correct function of all manual & automatic valves						PM	PM			
29	Valves	Check valves for corrosion, dirt deposits and leaks						PM	PM			
30	Manual pump	Check correct function of the manual water pump						PM	PM			
31	Pit	Check overflow alarm switch of the pit for correct function (if applicable)						PM	PM			
32	Final Check	Check the O&M manual and carry out additional required tasks						PM	PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, aligmment with CT.
June 2024 - Changed the APM description as shows the BBM Handbook.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, SUN PROTECTION / SHADING SYSTEM - 11
APM Object	BLDG.SHADING
APM EC	AMZ.BLDG.SHADING
BBM Handbook Title	Sun Protection / Shading System (Automatic Blinds)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	SUN PROTECTION / SHADING SYSTEM	**Schedule With:**	BLDG.WINDOWS		

Description of System / Technology (According to BBM Handbook)

Sun Protection / Shading System (Automatic Blinds)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of installed BBA available & complete						PM				
2	Shading system	Carry out a functional test & visual check for damage (from inside & outside the building)					SC	PM				
3	Shading system	Check condition of armor/slats						PM				
4	Shading system	Check the condition of the suspension & tighten any loose components						PM				
5	Electrical components	Check the condition of the electrical wiring for correct installation and loose components						PM				
6	Electrical components	Check if electrical components are protected against direct contact with life parts						PM				
7	Electrical components	Check the motor & shutter for unusual noise & vibration during operation					SC	PM				
8	Electrical components	Check panel for alarms, available and correct drawings & torque check all connections						PM				
9	Shading system	Check the condition of the guide rails						PM				
10	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, ENTRANCE SPEED GATES - 4
APM Object	BLDG.SPEEDGATE
APM EC	AMZ.BLDG.SPEEDGATE
BBM Handbook Title	Entrance Speed Gates
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.WORK.AUTOGATE-PEDESTRIAN			**Assets included in this PM:**	ENTRANCE SPEED GATES	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Entrance Speed Gates - Similar to turnstiles, a mechanical gate allowing only one person at a time to pass through.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Safety	Check the safety devices for correct function						PM				
4	Speed gate	Visual inspection of the buttons, card reader, motion detector and opto-sensor for damage						PM				
5	Speed gate	Are there any visual damage at the door leaf						PM				
6	Speed gate	Check the light barrier on both sides and clean to maintain functionality if necessary						PM				
7	Speed gate	The Speed gate does not close as long as there are objects in the closing area.						PM				
8	Electrical components	The cables are routed and fixed properly						PM				
9	Electrical components	Electrical terminations are secure						PM				
10	Electrical components	Check connections to fire system and verify the opening when the signal is activated.						PM				
11	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed ENTRANCE TURNSTILES from APM Description Cell.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, SMART ROOF MONITORING SYSTEM - 7
APM Object	BLDG.SRMS
APM EC	AMZ.BLDG.SRMS
BBM Handbook Title	Smart roof monitoring system
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Sep-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	/	**Delivered By:**	**OCB:** BBM
Evidence for CT:	YES	**Pricing template Position:**	7	**Related CT Areas:**	CT.FAC.ROOFTOPINSPECT	**Assets included in this PM:**	SMART ROOF MONITORING SYSTEM	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

NO INFO

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Base Station	Check orientation of solar panel (must be south)						PM	PM			
2	Base Station	Check weighting platform for damage and remove any dirt (e.g. leaves, bird droppings, etc.) Do not use any chemicals						PM	PM			
3	Base Station	On main Base Station, the wind sensor must be checked for free rotation					PM	PM	PM			
4	Base Station	On main Base Station, remove the sieve and clean at the precipitation sensor					PM	PM	PM			
5	Base Station	Replace Battery with a fully charged one, charge and store the replaced battery							PM			
6	Water Sensor	The measuring rods should be cleaned of dirt with a damp towel. Caution: Do not use any chemical cleaning aids					PM	PM	PM			
7	Water Sensor	Check the vertical alignment of the antenna and the positioning of the weight block.					PM	PM	PM			
8	Water Sensor	Replace Battery with a fully charged one, charge and store the replaced battery						PM	PM			
9	Snow Sensor	Check weighting platform for damage and remove any dirt (e.g. leaves, bird droppings, etc.) Do not use any chemicals					PM	PM	PM			
10	Snow Sensor	Check the vertical alignment of the antenna and the positioning of the weight block.						PM	PM			
11	Snow Sensor	Replace Battery with a fully charged one, charge and store the replaced battery						PM	PM			

Change Log

Error - Entry for specified object not found on change log

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, STRUCTURE/ WALLS AND PILLARS - 4
APM Object	BLDG.STRUCTURE
APM EC	AMZ.BLDG.STRCTR
BBM Handbook Title	Structure/ Walls and Pillars
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Feb-25	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.FAC.BUILDING			**Assets included in this PM:**	CEILINGS - FLOORS - STRUCTURE/WALLS AND PILLARS	**Schedule With:**	BLDG.INT BLDG.MEZZANINE		

Description of System / Technology (According to BBM Handbook)

Structure/ Walls and Pillars - External walls and cladding and interior walls and pillars

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Training	Confirm that the knet training "Structural Inspection Handbook for Concrete Buildings" was undertaken (link attached in Instructions tab).						SC				
2	Documentation	Follow the "Structural Inspection Handbook" attached in documents to carry out the inspection.						SC				
3	Interior walls and pillars	Check the interior walls and pillars according to the SOP. (Steel and concrete). Warehouse, technical rooms, car park building, robotics floors, stairs, offices.						SC				
4	Ceilings	Check the beams and ceilings according to the SOP.(Steel and concrete).Warehouse, technical rooms, car park building, robotics floors, stairs, offices.						SC				
5	Floors	Check the floors according to the SOP.(Steel and concrete).Warehouse, technical rooms, car park building, robotics floors, stairs, offices.						SC				
6	Attachments	Check suspended and attached equipment for signs of movement due to structural issues (e.g. shifted connections/displacement on sprinkler lines, drainage lines, ventilation ducts, etc.)						SC				
7	Exterior walls/cladding	Check the external walls and cladding according to the SOP. Warehouse, car park building, technical rooms.						SC				
8	Report	Once the report is validated, attach the completed "Inspection Report Template" to the WO Documents tab.						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the object where is applied the PM from BLDG (STEELWORK) to BLDG.STRUCTURE. Removed steelworks in the component cell, adding steelworks in the task cell. Added in component cell: Interior walls and pillars. Moved tasks from BLDG.INT, BLDG.EXT PM to BLDG.STRUCTURE PM.
February 2025 - Aligning PM according to D&C Inspection.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, TOILETS - 14
APM Object	BLDG.TOIL
APM EC	AMZ.TOILET.BLOCK
BBM Handbook Title	Toilets
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	TOILETS - HAND DRYER	**Schedule With:**	BLDG.DISABL.CLLPNT BLDG.DRAIN		

Description of System / Technology (According to BBM Handbook)

Toilets

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Room	The mirrors are free from damage			SC							
2	Room	The tiles and seals are free from damage			SC							
3	Room	The doors, door locks and partitions free from damage and functioning properly			SC							
4	Room	The ceiling plates are free from damage and no leakage is visible			SC							
5	Room	Are any installations damaged or loose (e.g. picture frame, dispenser, etc.)			SC							
6	Room	The light is working properly and is free from damage			SC							
7	Water supply & drainage	Check the wash basin drainage for leaks and blockages if easily accessible If not, check for water accumulation on the floor			SC							
8	Water supply & drainage	The faucets are functional and free from damage			SC							
9	Hand Dryer	Check the hand dryer for damage and correct function			SC							

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, ENTRANCE TURNSTILES - 4
APM Object	BLDG.TURNST
APM EC	AMZ.BLDG.TRNSTIL
BBM Handbook Title	Entrance Turnstiles
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.WORK.AUTOGATE-PEDESTRIAN	**Assets included in this PM:**	ENTRANCE TURNSTILES	**Schedule With:**	-				

Description of System / Technology (According to BBM Handbook)

Entrance Turnstiles - A mechanical gate consisting of revolving horizontal arms fixed to a vertical post, allowing only one person at a time to pass through. Turnstiles can be found internally and externally. All images below represent entrance turnstiles.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Safety	Check the safety devices for correct function						PM				
4	Operating device	Visual inspection of the buttons, card reader, motion detector and opto-sensor for damage						PM				
5	Functional cleaning	Carry out a functional cleaning to maintain a reliable operation						PM				
6	Rotating column	Check the free movement of the linkage in the unlocked state & correct function of the electromagnetic clutch						PM				
7	Rotating column	Backstop is functioning correctly						PM				
8	Motor/gearbox	Check if the motor is fixed properly & doesn`t make any unusual noise						PM				
9	Motor/gearbox	Check for oil leakages and lubricate bearings if required						PM				
10	Electrical components	The lighting is working properly						PM				
11	Electrical components	The intercom is working properly						PM				
12	Electrical components	The cables are routed and fixed properly						PM				
13	Electrical components	Electrical terminations are secure						PM				
14	Electrical components	Check connections to fire system and verify the opening when the signal is activated.						PM				
15	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removing SPEEDGATES from APM Description Cell.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, WINDOWS - 2
APM Object	BLDG.WINDOWS
APM EC	AMZ.BLDG.WINDOW
BBM Handbook Title	Windows
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	2	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	WINDOWS	**Schedule With:**	BLDG.SHADING BLDG.DOOR		

Description of System / Technology (According to BBM Handbook)

Windows

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Window	Perform a site walk to check for damage at the windows						SC				
2	Window	Operate all windows and check for correct operation, noise, proper seals								SC		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	AIR.COMPRESSORS - 13
APM Object	COMPR
APM EC	AMZ.COMPRESSORS
BBM Handbook Title	Air Compressors
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	13	**Related CT Areas:**	CT.PRESSURE.SYS			**Assets included in this PM:**	AIR COMPRESSOR - COMPRESSOR AIR DRYER - COMPRESSED AIR TANK - LIQUID SEPARATOR - COMPRESSOR WATER PUMP	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

An air compressor is a pneumatic device that takes ambient air from the surroundings and discharges it at a higher pressure.

Important

The time intervals correspond to the operating hours given below. Make sure that the threshold that is reached first triggers the appropriate maintenance.

12 monthly or 3000 operational hrs

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Important

The time intervals correspond to the operating hours given below. Make sure that the threshold that is reached first triggers the appropriate maintenance.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed BBA available & complete						PM	PM	PM	PM	
2	Safety	Are all safety switches & other safety components functioning correctly	SC					PM	PM	PM	PM	
3	Visual check	Is the unit accessible	SC									
4	Visual check	Is there any visual damage, missing / loose components or corrosion	SC									
5	Controller & Control Panel	Is there an alarm at the main controller or at one of the compressors	SC									
6	Controller & Control Panel	Is the main air manager and the single compressors in an automatic mode	SC									
7	Controller & Control Panel	Is the system air pressure on the required level	SC									
8	Controller & Control Panel	Is the compressor oil temperature ok (check the IOM/O&M)			PM		PM					
9	Controller & Control Panel	Add the compressor oil temperature into the notes			PM		PM					
10	Controller & Control Panel	Do any of the counters indicate a PM due in < 800 hrs - if yes schedule PM			PM							
11	Controller & Control Panel	Add the operational hours of the compressor into the notes			PM		PM	PM	PM	PM	PM	
12	Controller & Control Panel	Switch running compressors off & check automatic start of next compressor					PM	PM	PM	PM	PM	
13	Controller & Control Panel	Did the next compressor start automatically					PM	PM	PM	PM	PM	
14	Controller & Control Panel	Are all settings according to design of the system						PM	PM	PM	PM	
15	Controller & Control Panel	Were any obvious changes made in the panel (e.g. rewiring, hanging cables)						PM	PM	PM	PM	
16	Controller & Control Panel	Is the documentation and the circuit diagram complete						PM	PM	PM	PM	
17	Controller & Control Panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM	PM	PM	PM	
18	Controller & Control Panel	Change the filter of the electrical control cabinet						PM	PM	PM	PM	
19	Air compressor	Test the condensate drain unit			PM		PM	PM	PM	PM	PM	
20	Air compressor	Are there any leakages at the connections of the pipe system (air & drainage)			PM		PM	PM	PM	PM	PM	
21	Air compressor	Is the oil level on the oil separator ok			PM		PM	PM	PM	PM	PM	
22	Air compressor	Is the oil level of the unit ok			PM		PM	PM	PM	PM	PM	
23	Air compressor	Change the oil of the unit						PM	PM	PM	PM	
24	Air compressor	Change air intake filter						PM	PM	PM	PM	
25	Air compressor	Change the oil filter							PM		PM	
26	Air compressor	Change filter cartridge of oil separator							PM		PM	
27	Air compressor	Lubricate bearings of compressor & fan							PM		PM	
28	Air compressor	Carry out a valve service using service kit (change of O-rings, etc.)									PM	
29	Air compressor	Lubricate bearings of the compressor									PM	
30	Air compressor	Change bearings of the fan									PM	
31	Oil - water separator	Is the quality of the drain water behind the oil water separator ok			PM		PM	PM	PM	PM	PM	
32	Oil - water separator	Is the drainage of the oil water separator unblocked			PM		PM	PM	PM	PM	PM	
33	Oil - water separator	Is the quality of the drain water behind the oil water separator ok						PM	PM	PM	PM	
34	Oil - water separator	Change filter of oil water separator unit						PM	PM	PM	PM	
35	Water pump	Is the water pump functioning properly					PM	PM	PM	PM	PM	

36	Compressed air tank	Vent the water sump at the bottom of the air tank			PM		PM	PM	PM	PM	PM	
37	Compressed air tank	Is the over pressure valve of the air tank functioning properly					PM	PM	PM	PM	PM	
38	Compressed air dryer	Is the air dryer functioning correctly						PM	PM	PM	PM	
39	Compressed air dryer	Is the refrigerant circuit of the air dryer free from leakages (refrigerant)						PM	PM	PM	PM	
40	Functional cleaning	Organize a cleaning of the mezzanine floor if it`s dusty			PM		PM	PM	PM	PM	PM	
41	Functional cleaning	Clean the filter of the electrical control cabinet (vacuum from outside)			PM		PM	PM	PM	PM	PM	
42	Functional cleaning	Clean the in- & outlet fins of the unit			PM		PM	PM	PM	PM	PM	
43	Functional cleaning	Damp clean all outside surfaces of the main compressed air equipment					PM	PM	PM	PM	PM	
44	Final Check	Check the O&M manual and carry out additional required tasks						PM	PM	PM	PM	

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	DOCKS, 1 - 12
APM Object	DOCKS.01
APM EC	AMZ.DOCK.SUB
BBM Handbook Title	Dock System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Sep-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	12	**Related CT Areas:**	CT.WORK.DOCK			**Assets included in this PM:**	LOCK - DOOR - RAMP - SHELTER SURROUND - AIR BAG DOOR SEAL - BUMPER - (DOCKS) FAN - (DOCKS) LIGHT - TRAFFICLIGHT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

DOCK DOOR: Dock doors are a type of loading dock which are usually raised in the air in order to be level with trucks carrying goods.
DOCK RAMP: Dock ramps act as a liaison between the warehouse and trucks, making up for differences in height and filling the gap between truck and building.
DOCK LOCK: The Lock locks trailers onto the loading bay By locking the rear wheel, the docked vehicles will no longer move away from the dock. Also, vehicle "creeping', caused by momentum incurred during the loading and unloading process is prevented. This guarantees optimal safety.
DOCK AIR BAG SEAL: Inflatable lining around the entrance of the Dock door which reduces airflow and dust particles entering in the warehouse when trailers are loading/unloading via the Dock door.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: Tasks are based on maintenance of an Expresso system, but can be applied on other vehicle restraint systems as well. Tasks are not relevant, you can mark them as N/A and names of the equipment used vary depending on the manufacturer.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	All components General	Is the unit operational & no alarms indicated				PM	PM	PM				
2	All components General	Are there any visual damage, missing / loose components or corrosion				PM	PM	PM				
3	All components General	Are the technical documentation & electrical drawings complete						PM				
4	All components Safety	Are all safety switches & other safety components functioning correctly				PM	PM	PM				
5	All components Safety	Are disconnecting devices lockable in the safe position (LOTO)				PM	PM	PM				
6	Dock Traffic light	Is the traffic light system functioning correctly				PM	PM	PM				
7	Dock Door	Is the electric wheel wedge functioning correctly				PM	PM	PM				
8	Dock Door	Test sliding clutch by holding the door in motion until the motor stops.						PM				
9	Dock Door	Is the manual emergency operation unit functioning correctly						PM				
10	Dock Door	Are all cables (flexible/spiral) free from damage & tightly connected				PM	PM	PM				
11	Dock Door	Does the limit switches deactivate the motor at endpoints						PM				
12	Dock Door	Are photo cells fitted correctly, beams are aligned & clean						PM				
13	Dock Door	Are the photocells activated when the beams are interrupted						PM				
14	Dock Door	Does the pass door switch disable the door from being operated						PM				
15	Dock Door	Can the door be moved when engaged to the motor						PM				
16	Dock Door	Is it possible to unlock the door from the motor (drive)						PM				
17	Dock Door	Is the motor fixed properly						PM				
18	Dock Door	Does the motor make unusual noise						PM				
19	Dock Door	Does the motor emit excessive hot during multiple runs						PM				
20	Dock Door	Is the power consumption as per design of the motor						PM				
21	Dock Door	Are all wires in the panel connected tightly						PM				
22	Dock Door	Can all remote control functions of the door be used properly						PM				
23	Dock Door	Are traction wire ropes securely fixed to the bottom bracket				PM	PM	PM				
24	Dock Door	Are all sealings free of damage & closing leaks as designed						PM				
25	Dock Door	Is the anti lifting device functioning properly						PM				
26	Dock Door	Is the pull down rope or chain functioning properly & free of damage						PM				
27	Dock Door	Functional cleaning and lubrication of roller & relevant equipment						PM				
28	Dock Door	Are the Roller blocks, roller holders and rollers seated correctly						PM				
29	Dock Door	Does the roller make unusual noise when operating manually & electrically						PM				
30	Dock Door	Are the roller in a good condition						PM				
31	Dock Door	Is the door leaf in balance and running straight						PM				
32	Dock Door	Is the bottom bracket free of damage						PM				
33	Dock Door	Are all locks aligned, closing smoothly & functioning properly						PM				
34	Dock Door	Are beam brackets, hangers or suspensions securely fixed						PM				
35	Dock Door	Are wall tracks fixed properly, free of damage & corrosion						PM				

36	Dock Door	Are roof tracks fixed securely to the suspension, free of damage & corrosion						PM					
37	Dock Door	Are bends connected securely to vertical & horizontal tracks						PM					
38	Dock Door	Carry out a functional cleaning of all tracks						PM					
39	Dock Door	Are all tracks in balance						PM					
40	Dock Door	Does the door run smoothly through the bends						PM					
41	Dock Door	Are track covers securely fixed to the track &are free of damage						PM					
42	Dock Door	Are pulley wheels fixed securely and working properly						PM					
43	Dock Door	Carry out a functional cleaning & lubrication of pulley wheels						PM					
44	Dock Door	Are rope roller fixed & functioning properly and free of damage						PM					
45	Dock Door	Are buffers free from damage & functioning properly						PM					
46	Dock Door	Are torsion springs balanced according to IOM						PM					
47	Dock Door	Are torsion springs connection between spring & winding sleeve correctly fixed						PM					
48	Dock Door	Are there any damage like hairline cracks at the torsion springs						PM					
49	Dock Door	Spring Break Device functioning correctly & free of damage						PM					
50	Dock Door	Is the shaft straight & there are no signs of wear & tear or damage						PM					
51	Dock Door	Are the shaft coupling centered correctly & fixed into place to retain the shaft						PM					
52	Dock Door	Does the safety pull set/rope have enough tension						PM					
53	Dock Door	Are there any signs of wear & tear or damage at the safety pull set/ropes						PM					
54	Dock Door	Are support bearings fitted correctly, secure & lubricated						PM					
55	Dock Door	Is the pneumatic safety device functioning correctly						PM					
56	Dock Door Operational cycles	Read operating cycles & at quantity into notes				PM	PM	PM					
57	Dock Door Operational cycles	Reset Service counter according to IOM recommendation Note: Use manufacturer recommended tools						PM					
58	Dock Door Final Check	Check the O&M manual and carry out additional required tasks						PM					
59	Dock Fan	Is the fan functioning properly, attached correctly free from debris & corrosion				PM	PM	PM					
60	Dock Fan	Is there any abnormal sound or vibration while the fan in running				PM	PM	PM					
61	Dock Light	Is the light functioning correctly, attached correctly, free from debris & corrosion				PM	PM	PM					
62	Dock Ramp	Check the correct function of safety devices -> e.g. end-, main- & emergency switches					PM	PM					
63	Dock Ramp	Lock the leveller for maintenance under the platform					PM	PM					
64	Dock Ramp	All necessary markings are present					PM	PM					
65	Dock Ramp	Check the gap seal for proper sealing, dirt & damage					PM	PM					
66	Dock Ramp	The leveller is free from damage deformation & welds free from cracks					PM	PM					
67	Dock Ramp	All moving parts are operating smoothly & doesn`t make unusual noise (Deck, lip, sliding lamel, central unit)					PM	PM					
68	Dock Ramp	Carry out a functional cealing of moving parts and lubricate -> e.g. bearings, joints, etc.					PM	PM					
69	Dock Ramp	There are no leaks at the hydraulic components					PM	PM					
70	Dock Ramp	Carry out a functional cleaning of the hydraulic components						PM					
71	Dock Ramp	Check hydraulic oil level -> Refill if necessary & eliminate the root cause (e.g., leakage)						PM					
72	Dock Ramp	Undertake oil sample analysis -> Create FWO if results determine oil replacement or hydraulic system servicing is required						PM					
73	Dock Ramp	The cables are routed and fixed properly						PM					
74	Dock Ramp	Electrical terminations are secure						PM					
75	Dock Ramp	Check motor/pump for unusual noise and too high powerconsumption						PM					
76	Dock Ramp	Lubricate bearings of Motor/pump (if applicable)						PM					
77	Dock Ramp Final Check	Check the O&M manual and carry out additional required tasks						PM					
78	Dock Lock	Verify the correct operation of all components Weekly only for Expresso systems		PM	PM	PM	PM	PM					
79	Dock Lock	Remove all items that may interfere with the proper operation of the system | Weekly only for Expresso systems		PM	PM	PM	PM	PM					
80	Dock Lock	Check the condition of all moving mechanical components and springs for signs of wear and tear | Weekly only for Expresso systems		PM	PM	PM	PM	PM					
81	Dock Lock	Check the condition of the locking arm (no cracks) Weekly only for Expresso systems		PM	PM	PM	PM	PM					
82	Dock Lock	Floor attachment -> Check if screws of all connected components are tight Weekly only for Expresso systems		PM	PM	PM	PM	PM					
83	Dock Lock	If movement is disrupted, lubricate carrier, rack, joints, locking rod, and other moving parts		PM									
83	Dock Lock	Lubricate carrier, rack, joints, the locking rod & additional moving parts Monthly & 3 monthly only for Expresso systems			PM	PM	PM	PM					
84	Dock Lock	Check the wear condition of the toothed rack, the carriage drive pinion and the locking rod.				PM	PM	PM					
84	Dock Lock	Check lubrication of the wearer (lubricating spray) and reapply if necessary			PM	PM	PM	PM					
84	Dock Lock	Apply white grease to the rack, articulation joints, and locking rod			PM	PM	PM	PM					
85	Dock Lock	Check the condition of the structural parts (welds, deformations) the system				PM	PM	PM					
86	Dock Lock	Check the oil level in the tanks of the hydraulic units						PM					
87	Dock Lock	Check the condition of the hoses (obvious leaks, cuts, blockages, friction, etc.)			PM	PM	PM	PM					
88	Dock Lock	Conduct an oil condition analysis on 30% of the equipment to verify oil quality and ensure reliable operation						PM					
88	Dock Lock	Replace hydraulic oil									PM		
89	Dock Lock	Check proper function of warning signals/lights			PM	PM	PM	PM					
90	Dock Lock	Check the operation of the emergency stop devices		PM	PM	PM	PM	PM					
91	Dock Lock	Check the operating cycles and plan extensive PM according to O&M If required prior to yearly PM cycle			PM	PM	PM						
92	Dock Lock	Check the cable carrier and the cables for cuts, crushing, etc.		PM	PM	PM	PM	PM					

93	Dock Lock	Clean the wheel detection sensors.			PM	PM	PM	PM				
94	Dock Lock Operational Cycles	Add the number of operational cycles			PM	PM	PM	PM				
95	Dock Lock Final Check	Check the O&M manual and carry out additional required tasks					PM	PM				
96	Dock Airbag seal	All components are properly fastened , free from damage and corrosion					PM	PM				
97	Dock Airbag seal	The airbags do not show any damage					PM	PM				
98	Dock Airbag seal	Check airbags for proper airtightness on occupied dock doors					PM	PM				
99	Dock Airbag seal	The fan is functioning correctly and doesn`t make any unusual noise					PM	PM				
100	Dock Airbag seal	Are all cables properly routed and fixed					PM	PM				
101	Dock Airbag seal	Are all electrical terminations secure					PM	PM				
102	Dock Airbag seal	Measure the power consumption of the fan and compare to manufacturer specification					PM	PM				
103	Dock Airbag seal	Lubricate bearings of fan & motor if possible7necessary						PM				
104	Dock Airbag seal	Carry out a functional cleaning of air intakes, outlets & dirty aomponents to maintain a reliable operation (e.g. airbags air intake, motor cooling air intake, etc.)					PM	PM				
105	Dock Airbag seal Final Check	Check the O&M manual and carry out additional required tasks					PM	PM				
106	Dock Shelter	All components are properly fastened, free from damage & corrosion					PM	PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, DIESEL POWER GENERATORS - 11
APM Object	ELEC.GEN
APM EC	AMZ.ELEC.GEN
BBM Handbook Title	Diesel Power Generators
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.POWERGENERATOR			**Assets included in this PM:**	DIESEL GENERATOR UNIT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A diesel generator is the combination of a diesel engine with an electric generator (often an alternator) to generate electrical energy.
A temporary generator connection box provides a safe and efficient means of connecting a commercial or industrial business with a portable power source in the event of an electrical outage. A generator connection box is most frequently situated on the exterior of a building, wall- or floor-mounted, and used in conjunction with a transfer switch or kirk keyed breaker on switchboard.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the room properly ventilated						PM				
2	General check	Are the components clean - free from debris & leakage						PM				
3	General check	Check of the equipment for damage & missing components						PM				
4	General check	Check oil tanks for damage & leakages						PM				
5	General check	Check collection tray for deposits -> identify the root cause in case of deposit						PM				
6	General check	Are there any alarms indicated						PM				
7	General check	Did any circuit breaker trip						PM				
8	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
9	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
10	Safety	Are all relevant safety notices visible and free from damage						PM				
11	Safety	Is appropriate fire-fighting equipment available in the rooms						PM				
12	Safety	Are disconnecting devices lockable in the open position (LOTO)						PM				
13	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
14	Electrical components	Visual check for the protection against direct contact with live parts						PM				
15	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
16	Electrical components	Are all cables properly routed						PM				
17	Electrical components	Are all components properly labeled or marked						PM				
18	Electrical components	Test all safety relevant switches						PM				
19	Electrical components	Are all components properly attached						PM				
20	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Battery & Charger	Check if the battery charging device is working correctly & is free from damage						PM				
24	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
25	Battery & Charger	Check the batteries for leakages						PM				
26	Battery & Charger	Check the fluid level of the batteries and recharge if required						PM				
27	Battery & Charger	Schedule a battery change for any kind of deviation from standard or design						PM				
28	Fuel supply	Check the fuel tank and supply pipes for leakages and damage						PM				
29	Fuel supply	Check fuel filter and change if required						PM				
30	Fuel supply	Check all valves including safety valves for correct function						PM				
31	Engine cooling system	Is the level of the cooling fluid ok -> refill if required						PM				
32	Engine cooling system	Check for proper corrosion and freezing protection of the cooling fluid						PM				
33	Engine cooling system	Check hoses & pipes for damage & wear						PM				
34	Engine cooling system	Check connections at hoses & pipes for tightness						PM				
35	Engine cooling system	Check cooling water pre heater for correct function						PM				

36	Engine function	Exchange oil & oil filter						PM					
37	Engine function	Check valve setting and readjust if necessary						PM					
38	Engine function	Check vibration decoupling for damage						PM					
39	Engine function	Check V-belt tension and wear						PM					
40	Engine function	Check the function of the limit & safety switches						PM					
41	Engine function	Check injection system for damage and correct function						PM					
42	Engine function	Check correct settings of the speed controller						PM					
43	Engine function	Check the engine starter and alternator for correct function						PM					
44	Engine function	Check all value transmitters and display elements for damage and correct function						PM					
45	Engine function	Check Engine clutch for function						PM					
46	Engine function	Are there any unusual noises during start, operation or stop of the engine						PM					
47	Engine function	Grease all possible greasing points						PM					
48	Engine function	Check that the screws and nuts are tight						PM					
49	Engine function	Check engine block for leakages						PM					
50	Engine function	Is the exhaust tight and free from damage						PM					
51	Electrical function	Check the automatic & correct function of all air in- & outlet flaps			PM			PM					
52	Electrical function	Check the synchronization & automatic transfer switch for correct function (Test with load, only if there won`t be any impact on connected assets			PM			PM					
53	Electrical function	Functional test with highest possible load (Test with load, only if there won`t be any impact on connected assets			PM			PM					
54	Electrical function	Is the generator voltage and current flow as designed/demanded			PM			PM					
54	Electrical function	Check emergency shut off system for correct function						PM					
55	Operational Hours	Record the operational hours of the unit into the notes			PM			PM					
56	Functional cleaning	Clean the air intakes on the engine, generator and main air intake grilles on the outer walls						PM					
57	Functional cleaning	Carry out a functional cleaning of all equipment if required						PM					
58	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Added task to capture the operating hours of the unit for Sustainability purposes

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, HIGH VOLTAGE, SWITCHGEAR SYSTEM - 11
APM Object	ELEC.HV.SWGR
APM EC	AMZ.ELEC.HV.SWGR.GRP
BBM Handbook Title	High Voltage Switchgear
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained technician certified in the MV electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST			**Assets included in this PM:**	HV SWITCHGEAR	**Schedule With:**	ELEC.HV.TX		

Description of System / Technology (According to BBM Handbook)

Switchgear is a centralized collection of circuit breakers, fuses and switches (circuit protection devices) that function to protect, control and isolate electrical equipment.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Station outside check	Is the entrance freely accessible & free of obstacles			SC			PM				
2	Station outside check	Are there any visual damage or excessive vegetation at the building or around			SC			PM				
3	Station outside check	Check roof & roof drainage - clean drain inlets if necessary			SC			PM				
4	Station outside check	Check if the lightning protection is fixed appropriately & not damaged			SC			PM				
5	Station outside check	Are there any damage or corrosion at the cable trays			SC			PM				
6	Station outside check	Is the door locked properly - protection against unauthorized entry			SC			PM				
7	Station inside check	Does the light work properly			SC			PM				
8	Station inside check	Is the heater working			SC			PM				
9	Station inside check	Check heater for dirt, damage, corrosion			SC			PM				
10	Station inside check	Are there any water leaks visible at the walls or ceiling			SC			PM				
11	Station inside check	Are there any damage at the walls, ceiling or transformer cage			SC			PM				
12	Station inside check	Is the transformer cage door locked properly - protection against unauthorized entry			SC			PM				
13	Station inside check	Are technical installations damaged or loose (e.g. cable trays, MCP, fire extinguisher)			SC			PM				
14	Station inside check	Are flammable or unnecessary goods stored in the room			SC			PM				
15	Station inside check	Check the function of the room ventilation - natural & mechanical			SC			PM				
16	Safety	Are all relevant safety notices visible and free from damage			SC			PM				
17	Safety	Is appropriate fire-fighting equipment available in the rooms			SC			PM				
18	Safety	Is a rescue pole available in the room and in good condition?			SC			PM				
19	Safety	Is insulated floor matting installed and in good condition?			SC			PM				
20	Safety	Is HV detection pole available and in good working order?			SC			PM				
21	Safety	Inspect and test all tools, test instruments to ensure serviceable condition						PM				
22	Safety	Are disconnecting devices lockable in the open position (LOTO)						PM				
23	Documentation & Switchgear check	Are the circuit diagrams and relevant technical documentation available and complete						PM				
24	Documentation & Switchgear check	Are technical drawings hanging at the wall						PM				
25	Documentation & Switchgear check	Is there an active alarm displayed -> identify and eliminate the root cause			SC			PM				
26	Documentation & Switchgear check	Check correct function of the display elements (e.g. electrical current, voltage, etc.)			SC			PM				
27	Documentation & Switchgear check	Is the panel/cabinet clean - free from debris						PM				
28	Thermographic scan	Perform thermographic scans of the whole system (e.g. Switchgear, Busbars, etc.) -> Create a WO for over-temperature to determine the root cause immediately						PM				
29	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature-> Upload the thermographic scan						PM				
30	Shut down	De-energize the transformer						PM				
32	Shut down	Measure whether the system is voltage-free						PM				
33	Shut down	Perform earthing & short-circuit of all phases against each other & Protection Earth (ground)						PM				
34	Shut down	Block of neighboring live parts						PM				
35	Switchgear	Test the condition and mechanical operation of all switches, contactors, etc.						PM				
36	Switchgear	Clean & lubricate or schedule a replacement of mechanical components of disconnecting devices						PM				

37	Switchgear	Check all safety and Disconnecting devices for correct function						PM					
38	Switchgear	Are the correct disconnecting devices installed (e.g. switch connector, fuses, circuit breaker, etc.)						PM					
39	Switchgear	Are the settings at the disconnecting devices correct						PM					
40	Switchgear	Are all cables, terminal blocks & devices properly labeled or marked						PM					
41	Switchgear	Check for leakages of SF gas						PM					
42	Switchgear	Carry out functional cleaning						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT. Removed task regarding LOTO.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, HIGH VOLTAGE, TRANSFORMERS - 11
APM Object	ELEC.HV.TX
APM EC	AMZ.ELEC.HV.TX.GRP
BBM Handbook Title	High Voltage Transformers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained technician certified in the MV electrical field	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.TROILTEST CT.ELEC.ELECINST	**Assets included in this PM:**	OIL TRANSFORMER - DRY TRANSFORMER	**Schedule With:**	ELEC.HV.SWGR				

Description of System / Technology (According to BBM Handbook)

Transformers are used in electric circuits to change the voltage of electricity flowing in the circuit. It is used to increase the voltage (called 'stepping up') or decrease the voltage ('stepping down'). There are 2 types of transformer oil filled or dry-type that need differentiate by nameplate.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Station outside check	Is the entrance freely accessible & free of obstacles			SC			PM				
2	Station outside check	Are there any visual damage or excessive vegetation at the building or around			SC			PM				
3	Station outside check	Check roof & roof drainage - clean drain inlets if necessary			SC			PM				
4	Station outside check	Check if the lightning protection is fixed appropriately & not damaged			SC			PM				
5	Station outside check	Are there any damage or corrosion at the cable trays			SC			PM				
6	Station outside check	Is the door locked properly - protection against unauthorized entry			SC			PM				
7	Station inside check	Does the light work properly			SC			PM				
8	Station inside check	Is the heater working			SC			PM				
9	Station inside check	Check heater for dirt, damage, corrosion			SC			PM				
10	Station inside check	Are there any water leaks visible at the walls or ceiling			SC			PM				
11	Station inside check	Are there any damage at the walls, ceiling or transformer cage			SC			PM				
12	Station inside check	Is the transformer cage door locked properly - protection against unauthorized entry			SC			PM				
13	Station inside check	Are technical installations damaged or loose (e.g. cable trays, MCP, fire extinguisher)			SC			PM				
14	Station inside check	Are flammable or unnecessary goods stored in the room			SC			PM				
15	Station inside check	Check the function of the room ventilation - natural & mechanical			SC			PM				
16	Safety	Are all relevant safety notices visible and free from damage			SC			PM				
17	Safety	Is appropriate fire-fighting equipment available in the rooms			SC			PM				
18	Safety	Is a rescue pole available in the room and in good condition?			SC			PM				
19	Safety	Is insulated floor matting installed and in good condition?			SC			PM				
20	Safety	Is HV detection pole available and in good working order?			SC			PM				
21	Safety	Inspect and test all tools, test instruments to ensure serviceable condition						PM				
22	Safety	Are disconnecting devices lockable in the open position (LOTO)						PM				
23	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
24	Documentation	Are technical drawings hanging at the wall						PM				
25	Thermographic scan	Perform thermographic scans of the whole system (e.g. Busbars & Transformer, etc.) -> Create a FWO for over-temperature to determine the root cause immediately						PM				
26	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature-> Upload the thermographic scan						PM				
27	Shut down	De-energize the transformer						PM				
29	Shut down	Measure whether the system is voltage-free						PM				
30	Shut down	Perform earthing & short-circuit of all phases against each other & Protection Earth (ground)						PM				
31	Shut down	Block of neighboring live parts						PM				
32	Transformer	Visual check of the transformer for dirt, damage, corrosion & oil leakage, etc.						PM				
33	Transformer	Carry out functional cleaning						PM				
34	Transformer	Check breathers for correct function & damage (dehumidifier)						PM				
35	Transformer	Check transformer protection for correct function and damage (e.g. Buchholz relay)						PM				
36	Transformer	Inspect all cable and busbar terminations for signs of overheating						PM				

37	Transformer	Ensure all cable & busbar connections are correctly torqued according to manufacturers specification						PM					
38	Transformer	Inspect all cables and connections insulation/shields for damage						PM					
39	Transformer	Check if the system is properly connected to the PE (ground), check also for damage & corrosion						PM					
40	Transformer	Are all devices properly labeled or marked						PM					
41	Final Check	Check the O&M manual and carry out additional required tasks						PM					
42	Re-energize	Remove barriers of neighboring live parts						PM					
43	Re-energize	Remove earthing & short-circuit the equipment						PM					
45	Re-energize	Energize the transformer						PM					
46	Re-energize	Measure system voltage using appropriate tools						PM					

Change Log

June 2024 - New PM according to the last OCB changes. Removed task regarding LOTO.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, LOW VOLTAGE, BUSBAR - 11
APM Object	ELEC.LV.BSBR
APM EC	AMZ.ELEC.LV.BSBR
BBM Handbook Title	Low Voltage Busbar
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST CT.ELEC.THERMAL			**Assets included in this PM:**	LV BUSBAR	**Schedule With:**	ELEC.MET ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD BLDG.EARTHING		

Description of System / Technology (According to BBM Handbook)

A busbar is a metallic strip or bar, typically housed inside switchgear, panel boards, and busway enclosures for local high current power distribution. They are also used to connect high voltage equipment at electrical switchyards, and low voltage equipment in battery banks. They are generally uninsulated, and have sufficient stiffness to be supported in air by insulated pillars. These features allow sufficient cooling of the conductors, and the ability to tap in at various points without creating a new joint.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note: This standard PM package is specific to all Busbars which are installed in the FC to distribute electrical power to consumers. Busbars which are installed in any electrical panel/cabinets are always captured in the PM of those equipment.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Are the circuit diagrams and relevant technical documentation available and complete						SC				
2	General check	Are there any visual damage or loose components at the busbar system throughout the building check also for proper suspension						SC				
3	Thermographic scan	Perform thermographic scans at connection point & create a WO for over-temperature to determine the root cause						SC				
4	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature-> Upload the thermographic scan						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, LOW VOLTAGE, ELECTRICAL CABINETS - 11
APM Object	ELEC.LV.CABS
APM EC	AMZ.ELEC.LV.CABS.GRP
BBM Handbook Title	Low Voltage Electrical Cabinet
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST CT.ELEC.FIXEDWIRE CT.ELEC.RCDMETER CT.ELEC.TVSS CT.ELEC.THERMAL	**Assets included in this PM:**	ELECTRICAL CABINETS	**Schedule With:**	ELEC.MET ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD BLDG.EARTHING				

Description of System / Technology (According to BBM Handbook)

The function is to distribute power from a main electrical circuit to several assets. It should include fuses to protect the output cables due to diameter reduction.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the panel/cabinet clean - free from debris						PM				
2	General check	Is the air filter of the electrical panel/cabinet clean -> clean or change if necessary						PM				
3	General check	Is the cooling fan operating appropriately and doesn`t make any unusual noise						PM				
4	General check	Visual check of the panel outside & inside for damage & missing components						PM				
5	General check	Are there any alarms indicated					PM	PM				
6	General check	Are any circuit breakers tripped					PM	PM				
7	General check	Are disconnecting devices lockable in the open position (LOTO)						PM				
8	General check	Are the circuit diagrams and relevant technical documentation available and complete						PM				
9	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
10	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause					PM	PM				
11	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan					PM	PM				
12	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
13	Electrical components	Visual check for the protection against direct contact with live parts						PM				
14	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
15	Electrical components	Are all cables properly routed						PM				
16	Electrical components	Are all cables, terminal blocks & devices properly labeled or marked						PM				
17	Electrical components	Test all safety relevant switches						PM				
18	Electrical components	Test and maintain surge protection device according to manufacturer recommendation						PM				
19	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
20	Electrical components	Are all metal parts correctly connected to the protection earth (ground)						PM				
21	Electrical components	Is the ground connection to the building ground as per design						PM				
22	Functional cleaning	Damp clean the cabinet & fan if dusty						PM				
23	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, LOW VOLTAGE, POWER FACTOR CORRECTION - 11
APM Object	ELEC.LV.PFC
APM EC	AMZ.ELEC.LV.PFC
BBM Handbook Title	Low Voltage Power Factor Correction
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	POWER FACTOR CORRECTION CABINET	**Schedule With:**	ELEC.LV.CABS ELEC.LV.BSBR ELEC.MET ELEC.LV.SWBD BLDG.EARTHING		

Description of System / Technology (According to BBM Handbook)

Low Voltage Power factor correction (PFC) aims to improve power factor in systems less than 1kV, and therefore power quality. It reduces the load on the electrical distribution system, increases energy efficiency and reduces electricity costs. It also decreases the likelihood of instability and failure of equipment. These are often installed to meet utility requirements for minimum PF.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the panel/cabinet clean - free from debris						PM				
2	General check	Is the air filter of the electrical panel/cabinet clean -> Please clean or change if necessary						PM				
3	General check	Is the cooling fan operating appropriately and doesn`t make any unusual noise					PM	PM				
4	General check	Visual check of the panel outside & inside for damage & missing components					PM	PM				
5	General check	Are there any alarms indicated					PM	PM				
6	General check	Did any circuit breaker trip					PM	PM				
7	General check	Are disconnecting devices lockable in the open position (LOTO)					PM	PM				
8	General check	Are the circuit diagrams and relevant technical documentation available and complete						PM				
9	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
10	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause immediately					PM	PM				
11	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan					PM	PM				
12	Electrical components	Inspect all cables and connections insulation/shields for damage						PM				
13	Electrical components	Inspect all cable/busbar terminations and capacitors for signs of overheating						PM				
14	Electrical components	Inspect the capacitors for visual damage						PM				
15	Electrical components	Check if the system is properly connected to the PE (ground), check also for damage & corrosion						PM				
16	Measurement	Measure the capacitance of the capacitors and compare to manufacturer specification -> schedule an exchange if required						PM				
17	Functional cleaning	Carry out functional cleaning						PM				
18	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, LOW VOLTAGE, SWITCHBOARD - 11
APM Object	ELEC.LV.SWBD
APM EC	AMZ.ELEC.LV.SWBD
BBM Handbook Title	Low Voltage Switchboard
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST CT.ELEC.FIXEDWIRE CT.ELEC.THERMAL	**Assets included in this PM:**	LV SWITCHBOARD	**Schedule With:**	ELEC.LV.CABS ELEC.LV.BSBR ELEC.LV.PFC ELEC.MET BLDG.EARTHING				

Description of System / Technology (According to BBM Handbook)

Switchboard is a component of an electrical distribution system which divides an electrical power feed into branch circuits while providing a protective circuit breaker or fuse for each circuit in a common enclosure.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This PM includes the low voltage main distribution panels/switchboards.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Station outside check	Is the entrance freely accessible & free of obstacles			SC			PM				
2	Station outside check	Are there any visual damage or excessive vegetation at the building or around			SC			PM				
3	Station outside check	Check roof & roof drainage - clean drain inlets if necessary			SC			PM				
4	Station outside check	Check if the lightning protection is fixed appropriately & not damaged			SC			PM				
5	Station outside check	Are there any damage or corrosion at the cable trays			SC			PM				
6	Station outside check	Is the door locked properly - protection against unauthorized entry			SC			PM				
7	Station inside check	Does the light work properly			SC			PM				
8	Station inside check	Is the heater working			SC			PM				
9	Station inside check	Check heater for dirt, damage, corrosion			SC			PM				
10	Station inside check	Are there any water leaks visible at the walls or ceiling			SC			PM				
11	Station inside check	Are there any damage at the walls or ceiling			SC			PM				
12	Station inside check	Are technical installations damaged or loose (e.g. cable trays, MCP, fire extinguisher)			SC			PM				
13	Station inside check	Are flammable or unnecessary goods stored in the room			SC			PM				
14	Station inside check	Check the function of the room ventilation - natural & mechanical			SC			PM				
15	Safety	Are all relevant safety notices visible and free from damage			SC			PM				
16	Safety	Is appropriate fire-fighting equipment available in the rooms			SC			PM				
17	Safety	Inspect and test all tools, test instruments to ensure serviceable condition						PM				
18	Safety	Are disconnecting devices lockable in the open position (LOTO)						PM				
19	Documentation & display	Are the circuit diagrams and relevant technical documentation available and complete						PM				
20	Documentation & display	Are technical drawings hanging at the wall						PM				
21	Documentation & display	Is there an active alarm displayed -> identify and eliminate the root cause			SC			PM				
22	Documentation & display	Check correct function of the display elements (e.g. electrical current, voltage, etc.)			SC			PM				
23	Switchgear	Is the panel/cabinet clean - free from debris						PM				
24	Shut down	De-energize the system						PM				
26	Shut down	Measure whether the system is voltage-free						PM				
27	Shut down	Block of neighboring live parts						PM				
28	Thermographic scan	Perform thermographic scans of the whole system (e.g. Switchgear, Busbars, etc.) -> Create a WO for over-temperature to determine the root cause immediately						PM				
29	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan						PM				
30	Switchboard	Check for leakages of SF gas						PM				
31	Switchboard	Are all cables, terminal blocks & devices properly labeled or marked						PM				
32	Switchboard	Test the condition and mechanical operation of all switches, contactors, etc.						PM				
33	Switchboard	Lubricate, clean or schedule a replacement of mechanical components of disconnecting devices						PM				
34	Switchboard	Check all safety and Disconnecting devices for correct function						PM				
35	Switchboard	Are the correct disconnecting devices installed (e.g. switch connector, fuses, circuit breaker, etc.)						PM				
36	Switchboard	Are the settings at the disconnecting devices correct						PM				

37	Switchboard	Inspect all cable and busbar terminations for signs of overheating						PM					
38	Switchboard	Inspect all cables and connections insulation/shields for damage						PM					
39	Switchboard	Ensure all cable & busbar connections are correctly torqued according to manufacturers specification						PM					
40	Switchboard	Check if the system is properly connected to the PE (ground), check also for damage & corrosion						PM					
41	Switchboard	Test and maintain surge protection device according to manufacturer recommendation						PM					
42	Switchboard	Carry out functional cleaning						PM					
43	Re-energize	Re-energize system & measure system voltage using appropriate tools						PM					
44	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed Object and Title according to the last OCB changes, from ELEC.LV.SWITCHGEAR to ELEC.LV.SWBD. Removed task regarding LOTO.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, METERS - 11
APM Object	ELEC.MET
APM EC	AMZ.ELEC.METERS.GRP
BBM Handbook Title	Electrical Meters
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST			**Assets included in this PM:**	ELECTRICAL METER	**Schedule With:**	ELEC.LV.CABS ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD BLDG.EARTHING		

Description of System / Technology (According to BBM Handbook)

Electric meters -> analog – manual read, or smart meters – connected to BMS. Electrical meter will be the main utility meter and submeters are any meters downstream at the site. Update the Alias description with meter type, if utility meter include utility meter number and if submeter include location of meter.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: smart meters which are connected to the BMS are captured under the BMS PM

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Electric meter	Check all electric meters for correct function, display in the BMS, alarms & damage			SC							
2	Measurement	List all meter names & consumption in kWh to the notes			SC							

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, UNINTERRUPTABLE POWER SUPPLY - 11
APM Object	ELEC.UPS
APM EC	AMZ.ELEC.UPS
BBM Handbook Title	Uninterruptable Power Supply (UPS)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.UPS			**Assets included in this PM:**	BATTERY BACKUP UPS - RACK MOUNTED UPS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Uninterruptible power supply is a type of continual power system that provides automated backup electric power to a load when the input power source is removed. Typically this backup power is supplied by batteries or supercapacitors which gives instantaneous transfer. Each model has a different able to support the load for a set duration depending on design. These are typically supporting network equipment(MDF) or critical process equipment. Rack mounted UPS are small single phase units to supply individual device such as IDF cabinet, arc flash relay, MHE control cabinet gateway.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the room properly ventilated						PM				
2	General check	Are the components clean - free from debris						PM				
3	General check	Is the air filter & grid of the cooling inlets clean -> Clean or change filter if necessary					SC	PM				
4	General check	Are the cooling fans operating appropriately and doesn`t make any unusual noise						PM				
5	General check	Visual check of the equipment for damage & missing components					SC	PM				
6	General check	Are there any alarms indicated					SC	PM				
7	General check	Did any circuit breaker trip						PM				
8	General check	Are disconnecting devices lockable in the open position (LOTO)						PM				
9	General check	Are the circuit diagrams and relevant technical documentation available and complete						PM				
10	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
12	Thermographic scan	Perform thermographic scans of the electrical cabinet and the battery system -> Create a WO for over-temperature to determine the root cause immediately						PM				
13	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scans for overtemparature						PM				
14	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
15	Electrical components	Visual check for the protection against direct contact with live parts						PM				
16	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
17	Electrical components	Are all cables properly routed						PM				
18	Electrical components	Are all components properly labeled or marked						PM				
19	Electrical components	Test all safety relevant switches						PM				
20	Electrical components	Are all components properly attached						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
24	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
25	Battery & Charger	Measure the charging voltage and current before & after functional test						PM				
26	Battery & Charger	Compare to design specification & plan component exchange in case of an issue						PM				
27	Battery & Charger	Check the internal uninterruptable voltage supply of the unit						PM				
28	Battery & Charger	Check the batteries for leakage						PM				
29	Battery & Charger	Check the fluid level of the batteries and recharge if required						PM				
30	Functional test	Simulate a power interruption and test the UPS for correct function (avoid impact on connected assets)						PM				
31	Functional cleaning	Carry out a functional cleaning if required						PM				
33	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
July 2024 - Task 13 updated.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, FIRE ALARM PANELS - 10
APM Object	FIRE.DET.ALRMPNL
APM EC	AMZ.FIRE.ALRMPNL.GRP
BBM Handbook Title	Fire Alarm Panels
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS			**Assets included in this PM:**	FIRE ALARM PANEL - REMOTE POWER SUPPLY - DIALER	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A component of the fire alarm system that receives signals from initiating devices or other fire alarm control units and processes these signals to determine part or all of the required fire alarm system output function(s). Fire alarm panel is also known as a Fire Alarm Control Unit (FACU)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	System Health	System health check - Check if there are any alarms, warnings etc indicated on the fire alrm panels. -> If yes identify & eliminate the root cause	SC									
2	System Health	Compare alarm list with the entries in the logbook and if necessary, determine the alarm cause						PM				
3	System Health	Background memory/event memory for deviations or examine and assess special events						PM				
4	General check	Visual check of the equipment for damage, loose- & missing components						PM				
5	Documentation	Is the documentation available and complete						PM				
6	Documentation	Are the circuit diagrams and relevant technical documentation available, complete & correct						PM				
7	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
8	Documentation	Are all required codes, passwords, etc. to activate & deactivate the system available						PM				
9	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
10	Battery & Charger	Check the EOL recommended by manufacturer and schedule an exchange						PM				
11	Battery & Charger	Check the batteries for leakage or damage						PM				
12	Battery & Charger	Load test of the batteries according to the manufacturer's specifications						PM				
13	Functional test battery	Simulate a power outage & check the system for correct function						PM				
14	Electrical components	Is the air filter & grid of the cooling inlets clean -> vacuum or change filter if necessary						PM				
15	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
16	Electrical components	Visual check for the protection against direct contact with live parts						PM				
17	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
18	Electrical components	Are all cables properly routed						PM				
19	Electrical components	Are all components properly labeled or marked						PM				
20	Electrical components	Are all components properly attached						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
24	Cause and effect	Check for correct output signal according to fire matrix						PM				
25	Obscuration	Check the obscuration rate of detectors and schedule replacement if it exceeds manufacturer specifications or as required						PM				
26	Dialer	Confirm correct function of the dialer and the backup battery						PM				
27	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM Object fromFIRE.DET.FIREALRM to FIRE.DET.ALRMPNL according to the last OCB updates. Removed 3M, 6M, 24M frequencies.
January 2025- Changing component to Obscuration in task 25.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, ASPIRATING SMOKE - 10
APM Object	FIRE.DET.ASD
APM EC	AMZ.FIRE.ASP.GRP
BBM Handbook Title	Aspirating Smoke Detection System (ASD)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.ASD			**Assets included in this PM:**	ASPIRATING SMOKE DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.SMOKEHEAT FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME		

Description of System / Technology (According to BBM Handbook)

An aspirating smoke detector (ASD) is a system used in active fire protection, consisting of a central detection unit which draws air through a network of pipes to detect smoke. The sampling chamber is based on a nephelometer that detects the presence of smoke particles suspended in air by detecting the light scattered by them in the chamber. ASDs can typically detect smoke before it is visible to the naked eye.

Additional Information

Ensure the filters are changed minimum once a year or according to O&M manual if a shorter interval is recommended
All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Aspirating Smoke Detector	Check for alarms on the ASD unit				PM		PM				
2	Aspirating Smoke Detector	Vacuum ASD pipes with a vacuum cleaner				PM		PM				
3	Aspirating Smoke Detector	Check the ASD pipe filter and change if necessary, or clean if it is a reusable filter				PM		PM				
4	Aspirating Smoke Detector	Check, clean & adjust pressure sensor according to manufacturer & Amazon FLS requirements				PM		PM				
5	ASD filter change	Add detail of filter change into notes if changed				PM		PM				
6	Final Check	Consult the O&M manual and perform any additional tasks as specified						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Adding info in Who is for? Removing 6M, 12M, and 24M frecuencies.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, BEAM - 10
APM Object	FIRE.DET.BEAM
APM EC	AMZ.FIRE.BEAM.GRP
BBM Handbook Title	Fire Detection System Overview
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT			**Assets included in this PM:**	BEAM DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.SMOKEHEAT FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD		

Description of System / Technology (According to BBM Handbook)

A beam detector is a fire detection device that uses infrared beams to detect the presence of smoke. Using a detector on one wall and a reflector on the one opposite, the detector shoots the infrared beam across an open area to the reflector, which sends it straight back.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Check for physical damage, dirt, dust, or obstructions on the emitter and receiver lenses. Ensure the beam path is clear of obstacles						PM	PM			
2	Detection	Verify proper alignment of the detector using the manufacturer's tool or method. Ensure the alignment indicator is within acceptable tolerance levels						PM	PM			
3	Detection	Simulate a smoke condition to test the detector's response and ensure proper activation of the fire alarm system						PM	PM			
4	Detection	Verify that the detector forwards the alarm correctly to the fire alarm panel with an accurate message of origin						PM	PM			
5	Detection	Confirm the detector's sensitivity setting (e.g., obscuration rate) meets manufacturer specifications and adjust if needed						PM	PM			
6	Detection	Clean the emitter and receiver lenses with a soft, non-abrasive cloth to maintain optimal performance						PM	PM			
7	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
8	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM.
Aug 2024 - Added task to check for battery after learnings from LATAM field RME

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, PUBLIC ADDRESS SYSTEM - 10
APM Object	FIRE.DET.COMM
APM EC	AMZ.FIRE.EVAC
BBM Handbook Title	Public Address System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.EVACUATION			**Assets included in this PM:**	PUBLIC ADDRESS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Public Address System - These devices are designed for broadcasting crystal clear audio messages/live announcements during day-to-day operations or any emergency situations, helping towards safe evacuation.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the room properly ventilated			SC			PM				
2	General check	Are the components clean - free from debris						PM				
3	General check	Visual check of the equipment for alarms & damage & missing components			SC			PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
5	Safety	Test all safety relevant switches for correct function						PM				
6	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
7	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
9	Functional test	Perform a functional test of the equipment						PM				
10	Functional test	Simulate a power outage & check the system for correct function						PM				
11	Panel	Is the air filter & grid of the cooling inlets clean -> Please clean or change filter if necessary			SC			PM				
12	Panel	Are the cooling fans operating appropriately and doesn`t make any unusual noise						PM				
13	Panel	Are there any alarms indicated			SC			PM				
14	Panel	Are any breakers tripped - if yes identify the root cause			SC			PM				
15	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
16	Electrical components	Visual check for the protection against direct contact with live parts						PM				
17	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
18	Electrical components	Are all cables properly routed						PM				
19	Electrical components	Are all components properly labeled or marked						PM				
20	Electrical components	Are all components properly attached						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
24	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
25	Battery & Charger	Measure the charging voltage and current before & after functional test						PM				
26	Battery & Charger	Compare to design specification & plan component exchange in case of an issue						PM				
27	Battery & Charger	Check the internal uninterruptable voltage supply of the unit						PM				
28	Battery & Charger	Check the batteries for leakage or damage						PM				
29	Battery & Charger	Check the fluid level of the batteries and recharge if required						PM				
30	Functional cleaning	Carry out a functional cleaning if required						PM				
31	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM Object from FIRE.DET.BOSS to FIRE.DET.RADIO according to the last OCB updates. Removed thermal scan task because it's part of the LV inspection. Removed task regarding CE certification.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, DUCT DETECTION - 10
APM Object	FIRE.DET.DUCT
APM EC	AMZ.FIRE.DUCT.GRP
BBM Handbook Title	Duct Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT	**Assets included in this PM:**	DUCT DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.SMOKEHEAT FIRE.DET.BEAM FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD				

Description of System / Technology (According to BBM Handbook)

Duct smoke detectors provide early detection of smoke and products of combustion present in air moving through HVAC ducts. These devices are designed for prevention of smoke recirculation in areas by the air handling systems.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all smoke detectors detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
3	Detection	Check for change in sensor position. Are the detectors maps updated?						PM	PM			
4	Detection	Clean the air sampling tube						PM	PM			
5	Detection	Is the device free for damage						PM	PM			
6	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
7	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM.
Aug 2024 - Added task to check for battery after learnings from LATAM field RME

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, FLAME - 10
APM Object	FIRE.DET.FLAME
APM EC	AMZ.FIRE.FLAME.GRP
BBM Handbook Title	Flame Detection
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT			**Assets included in this PM:**	FLAME DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.SMOKEHEAT FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.ASD		

Description of System / Technology (According to BBM Handbook)

A flame detector is a sensor designed to detect and respond to the presence of a flame or fire. Typically this sensor will respond to a separate panel that it's designed to communicate with. This separate panel will communicate to the main Fire Alarm Control Unit.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all detectors, including the associated display of the origin of the message						PM				
2	Detection	Clean the lens of the detector						PM				
3	Detection	Check all accustic and illumintaed signals for correct function						PM				
4	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM				
5	Final Check	Consult the O&M manual and perform any additional tasks as specified						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, HEAT - 10
APM Object	FIRE.DET.HEAT
APM EC	AMZ.FIRE.HEAT.GRP
BBM Handbook Title	Heat Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT	**Assets included in this PM:**	HEAT DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.SMOKEHEAT FIRE.DET.SMOKEHEATCO FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD				

Description of System / Technology (According to BBM Handbook)

Heat detector is a fire-protection device that automatically detect and gives a warning when high temperature is reached.
Warning: the used heat detectors must be static and not RoR They should be used around hot sources: kitchens, microwaves, showers, cleaning cupboards.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Is there any debris around detector that could create an issue						PM	PM			
3	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
4	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM	PM			
5	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
6	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.
Aug 2024 - Added task to check for battery after learnings from LATAM field RME

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, LINEAR HEAT - 10
APM Object	FIRE.DET.LINEAR
APM EC	AMZ.FIRE.LNHT.GRP
BBM Handbook Title	Linear Heat Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT			**Assets included in this PM:**	LINEAR HEAT DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.SMOKEHEAT FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.FLAME FIRE.DET.ASD		

Description of System / Technology (According to BBM Handbook)

Linear Heat Detection (LHD) is a continuous heat detector designed to detect heat along the length of a sensor cable. This sensor cable is made up of two conductors, both insulated by heat sensitive polymers. The heat sensitive polymer is protected by an outer jacket.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test different positions along the cable, including the associated display of the origin of the message						PM				
2	Detection	Check all accustic and illumintaed signals for correct function						PM				
3	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM				
4	Detection	Is there any reasonable damage to the cable						PM				
5	Final Check	Consult the O&M manual and perform any additional tasks as specified						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, MANUAL CALL POINTS - 10
APM Object	FIRE.DET.MCP
APM EC	AMZ.FIRE.MCP.GRP
BBM Handbook Title	Manual Call Points (MCP)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS			**Assets included in this PM:**	MANUAL CALL POINT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

It is a device for the manual initiation of a fire alarm.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Manual Call Point	Verify that reset keys are available for all relevant stakeholders						PM	PM			
2	Manual Call Point	Visual check of the MCPs & covers for damage, loose- & missing components						PM	PM			
3	Manual Call Point	Change battery of the MCP cover							PM			
4	Manual Call Point	Carry out a functional test of the cover alarm						PM	PM			
5	Manual Call Point	Ensure that the seal is present after task completion						PM	PM			
6	Manual Call Point	Test of all Manual Call Points						PM	PM			
7	Manual Call Point	Are all Manual Call Points free from damage						PM	PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM according to the OCB structure.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, PUBLIC SAFETY RADIO SYSTEM - 10
APM Object	FIRE.DET.RADIO
APM EC	AMZ.FIRE.RADIO
BBM Handbook Title	Public Safety Radio System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.EVACUATION			**Assets included in this PM:**	PUBLIC SAFETY RADIO	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Public Safety Radio System - A combination of components, RF-emitting devices, antennas, cables, power supplies, control circuitry, and programming installed at a specific location to improve wireless communications within the building and between on-scene emergency responders and communications centers.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the room properly ventilated			SC			PM				
2	General check	Are the components clean - free from debris						PM				
3	General check	Visual check of the equipment for alarms & damage & missing components			SC			PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
5	Safety	Test all safety relevant switches for correct function						PM				
6	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
7	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
9	Functional test	Perform a functional test of the equipment						PM				
10	Functional test	Simulate a power outage & check the system for correct function						PM				
11	Panel	Is the air filter & grid of the cooling inlets clean -> Please clean or change filter if necessary			SC			PM				
12	Panel	Are the cooling fans operating appropriately and doesn`t make any unusual noise						PM				
13	Panel	Are there any alarms indicated			SC			PM				
14	Panel	Are any breakers tripped - if yes identify the root cause			SC			PM				
15	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
16	Electrical components	Visual check for the protection against direct contact with live parts						PM				
17	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
18	Electrical components	Are all cables properly routed						PM				
19	Electrical components	Are all components properly labeled or marked						PM				
20	Electrical components	Are all components properly attached						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
24	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
25	Battery & Charger	Measure the charging voltage and current before & after functional test						PM				
26	Battery & Charger	Compare to design specification & plan component exchange in case of an issue						PM				
27	Battery & Charger	Check the internal uninterruptable voltage supply of the unit						PM				
28	Battery & Charger	Check the batteries for leakage or damage						PM				
29	Battery & Charger	Check the fluid level of the batteries and recharge if required						PM				
30	Functional cleaning	Carry out a functional cleaning if required						PM				
31	Antenna	Check the antenna for fixed/correct installation & damage trhoughout the building (at all visible locations)						PM				
32	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

Error - Entry for specified object not found on change log

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, SMOKE - 10
APM Object	FIRE.DET.SMOKE
APM EC	AMZ.FIRE.SMOKE.GRP
BBM Handbook Title	Smoke Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT			**Assets included in this PM:**	SMOKE DETECTOR	**Schedule With:**	FIRE.DET.HEAT FIRE.DET.SMOKEHEAT FIRE.DET.SMOKEHEATCO FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD		

Description of System / Technology (According to BBM Handbook)

Smoke detector is a fire-protection device that automatically detect and gives a warning of the presence of smoke.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Is there any debris around detector that could create a False Activation						PM	PM			
3	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
4	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM	PM			
5	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
6	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, SMOKE AND HEAT COMBINED - 10
APM Object	FIRE.DET.SMOKEHEAT
APM EC	AMZ.FIRE.SMOKEHEAT.GRP
BBM Handbook Title	Smoke & Heat Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT	**Assets included in this PM:**	SMOKE AND HEAT COMBINE DECTECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEATCO FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD				

Description of System / Technology (According to BBM Handbook)

These are a combined optical smoke and heat detector. Using the combined detection method a fire condition can be confirmed if both heat and smoke sensors are activated.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Is there any debris around detector that could create a False Activation						PM	PM			
3	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
4	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM	PM			
5	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
6	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.
Aug 2024 - Added task to check for battery after learnings from LATAM field RME

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, SMOKE HEAT AND CO DETECTORS - 10
APM Object	FIRE.DET.SMOKEHEATCO
APM EC	AMZ.FIRE.SMOKEHEATCO.GRP
BBM Handbook Title	Smoke, Heat & Carbon Monoxide Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT	**Assets included in this PM:**	SMOKE HEAT AND CO DETECTOR	**Schedule With:**	FIRE.DET.SMOKE FIRE.DET.HEAT FIRE.DET.SMOKEHEAT FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD				

Description of System / Technology (According to BBM Handbook)

Multi-sensor detectors, also called multi-criteria detectors, combine one or more fire detection technologies into a single device. By using multiple sensors — for smoke, heat and carbon monoxide — these devices can provide more accurate fire detection, reduce false alarms and simplify installation.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Is there any debris around detector that could create a False Activation						PM	PM			
3	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
4	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM	PM			
5	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
6	Battery	Replace battery if applicable							PM			

Change Log

JAN 2025 - New PM after OCB update in 2024

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, DAMPERS - 10
APM Object	FIRE.FLS.DMP
APM EC	AMZ.FIRE.DMP
BBM Handbook Title	Dampers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DAMPERS			**Assets included in this PM:**	AUTOMATIC CONTROL DAMPER - FIRE DAMPER - FIRE/SMOKE COMBO DAMPER	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Dampers as part of the life safety system open or close during an emergency event. Automatic control dampers are typically found on the exterior of the building and open to provide make-up air for smoke exhaust fans. Fire dampers are installed in an air-distribution system, that is designed to close automatically upon detection of heat to interrupt migratory airflow and to restrict the passage of flame. Combination Fire/Smoke Damper, is a motorized damper located within HVAC ducting that closes both detection of fire, and is also interfaced with the fire alarm control unit to close upon the detection of smoke.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed equipment available & complete						PM				
2	Functional test	Trigger all fire dampers in the duct system & check for correct operation						PM				
3	Functional test	Closed Position: Ensure the damper fully closes to block airflow Open Position: Ensure the damper fully opens for unobstructed airflow						PM				
4	Functional test	Motor driven damper - check drive for damage and obvious noises or vibration while operating						PM				
5	Installation	Are the fire dampers installed according to local regulation & O&M (e.g. correctly cemented)						PM				
6	AHU control	Are the alarms indicated properly & units control process is working as designed (e.g. unit shut down)						PM				
7	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM object from FIRE.SUP.DMP to FIRE.FLS.DMP according to the last updates in the OCB.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, FIRE DOORS - 10
APM Object	FIRE.FLS.FIREDOOR
APM EC	AMZ.FIRE.FIREDOOR.GRP
BBM Handbook Title	Fire Door
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certification	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DOORS			**Assets included in this PM:**	FIRE DOOR	**Schedule With:**	FIRE.FLS.HOLDDOOR BLDG.EMERDOOR		

Description of System / Technology (According to BBM Handbook)

A combination of a fire door, a frame, hardware, and other accessories that together provide a specific degree of fire protection to the opening. Used as part of a passive fire protection system to reduce the spread of fire and smoke between separate compartments of a structure and to enable safe egress from a building.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed equipment available & complete						PM				
2	Documentation	Compare the installed equipment to design (e.g. correct fire class)						PM				
3	Safety	Is the door safely accessible and free from obstacles						PM				
4	Safety	Does the panic door opening work correctly (in the case of an emergency escape door)						PM				
5	Door	Is the door leaf & door frame free from damage and corrosion						PM				
6	Door	Is there anything incorrectly fixed to the door leaf (e.g. screw mounted plates)						PM				
7	Door	Are the door hinges free from damage and corrosion Clean and lubcricate if it's necessary						PM				
8	Door	Does the door move smoothly without resistance and doesn`t drag on the floor, bang against door frame, or stick at the rail in case of sliding doors						PM				
9	Door	Are all door & frame sealings ok						PM				
10	Door	Does the door close properly and stay closed						PM				
11	Door	Are the mechanism functioning correctly (handles & lock)						PM				
12	Door	Door handle does not hit the wall when opening						PM				
13	Door	It is possible to lock the door properly						PM				
14	Door	Doorstop is properly fixed						PM				
15	Door	Check pinch protection for damage and correct function						PM				
16	Door	Are there any unusual noises when the door is moving						PM				
17	Electronic Locks	Verify the functionality of the electronic lock, ensuring proper locking, unlocking, and secure operation as per system requirements						PM				
18	Overhead closer	Is the overhead closer connected & functioning correctly						PM				
19	Functional cleaning	Carry out a functional cleaning of all relevant components						PM				
20	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM OBJECT from FIRE.DOOR to FIRE.FLS.FIREDOOR according to the OCB updates. From SC to PM.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, FIRE SLIDING DOORS - 10
APM Object	FIRE.FLS.FIRESLD
APM EC	AMZ.FIRE.SLD
BBM Handbook Title	Fire Sliding Door
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SHUTTERS			**Assets included in this PM:**	FIRE SLIDING DOOR	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Fire Sliding Doors, also known as Rolling Steel Fire Doors, are allocated in walls where people or vehicles pass from different building areas. Shutters would close in case of a fire to isolate the areas.
NOTE: Smaller window style fire shutters for conveyors are listedn in FIRE SUPPRESSION SYSTEMS.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed doors available & complete						PM				
2	Safety	Check pinch protection for damage and correct function						PM				
3	Safety	Check for correct function of safety switches						PM				
4	Door	Is the door and frame free from damage and corrosion						PM				
5	Door	Are rollers and guides free from obstruction, debris and clean						PM				
6	Door	Are all door sealing ok						PM				
7	Door	Does the door move smoothly without resistance and doesn`t drag, bang against door frame, or stick at the rail in case of sliding doors						PM				
8	Door	Does the door close properly and stay close						PM				
9	Electrical components	Check for correct operation of drive mechanism Lubricate and adjust as necessary						PM				
10	Electrical components	Check motor overload for correct function						PM				
11	Electrical components	Check condition and correct function of limit switches Adjust if necessary						PM				
12	Electrical components	Check the control elements for damage and correct function						PM				
13	Electrical components	Check if cables are properly routed and free from damage						PM				
14	Electrical components	Ensure all cable terminations are secure						PM				
15	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM for FIRE.FLS.FIRESLD.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, FIRE DOORS HOLD OPEN SYSTEM - 10
APM Object	FIRE.FLS.HOLDDOOR
APM EC	AMZ.FIRE.HOLDDOOR.GRP
BBM Handbook Title	Fire Door Hold Open Device
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certification	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DOORS			**Assets included in this PM:**	HOLD OPEN FIRE DOOR	**Schedule With:**	FIRE.FLS.FIREDOOR BLDG.EMERDOOR		

Description of System / Technology (According to BBM Handbook)

The hold-open device is a system for keeping fire doors open. This means that a hold-open device (also known as a hold-open system, or FSA for short) keeps the fire door open and closes it automatically in the event of a fire.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed equipment available & complete						PM				
2	Open hold system	Test the system smoke detector and check system for correct function						PM				
3	Electrical components	Check the control elements for damage and correct function						PM				
4	Electrical components	Check if cables are properly routed and free from damage						PM				
5	Electrical components	Ensure all cable terminations are secure						PM				
6	Functional cleaning	Carry out a functional cleaning of all relevant components						PM				
7	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM for FIRE.FLS.HOLDDOOR.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, WAREHOUSE SMOKE EXTRACTION - 10
APM Object	FIRE.FLS.SMOKEEXT
APM EC	AMZ.FIRE.SMOKEEXT
BBM Handbook Title	Smoke Extraction Fans (Warehouse)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SMOKEVENTS			**Assets included in this PM:**	SMOKE EXTRACTION FAN	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Smoke extract fans extract smoke and heat created from a fire for long enough for occupants to escape from danger

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the system available & complete						PM				
2	General check	Check air inlets for obstacles blocking the airflow						PM				
3	Functional test	Test the fire case matrix						PM				
4	Functional test	Confirm that equipment operates in accordance with the fire case matrix, incl. the activation of smoke extraction fans and the proper functioning of associated automatic dampers and doors, etc.						PM				
5	Measurement	Measure the power consumption of all smoke extraction fans & compare to design						PM				
6	Measurement	Measure the exhaust air volume flow of all smoke extraction fans & compare to design						PM				
7	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, SMOKE HEAT VENTS - 10
APM Object	FIRE.FLS.SMOKEHEATVENT
APM EC	AMZ.FIRE.VENT
BBM Handbook Title	Smoke Heat Vent
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SMOKEVENTS			**Assets included in this PM:**	SMOKE HEAT VENT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Smoke heat vents are active fire protection measures. They are openings in the roof which are intended to vent the heat and smoke developed by a fire inside the building.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the system available & complete						PM				
2	General check	Check all components for damage and corrosion						PM				
3	General check	Check air inlets for obstacles blocking the airflow						PM				
4	Functional test	Ensure that all relevant keys to trigger & reset the system are available						PM				
5	Functional test	Verify the functionality of both natural and mechanical smoke extraction systems by activating the smoke extraction button and confirming proper operation						PM				
6	Functional test	Verify the correct operation of all smoke extraction components (incl. fans and the associated automatic dampers if installed)						PM				
7	Functional test	Verify if any unusual noises are present during fan operation, indicating potential mechanical issues						PM				
8	Functional test	Ensure used gas cartridges, covers, etc. are replaced before the unit will be set back in operation						PM				
9	Pipe system	Check if pipe systems are free from damage and properly fixed						PM				
10	Electrical components	Check the control elements for damage, alarms and correct function						PM				
11	Electrical components	Check if cables are properly routed and free from damage						PM				
12	Electrical components	Ensure all cable terminations are secure						PM				
13	Functional cleaning	Carry out a functional cleaning of all relevant components						PM				
14	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SPECIAL HAZARDS SYSTEM, HYDROGEN DETECTION - NOT INCL
APM Object	FIRE.SPHZRD.HYDRO
APM EC	AMZ.FIRE.HYDRO
BBM Handbook Title	Hydrogen Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	NOT INCL	**Related CT Areas:**	CT.SAFE.FLAMGASDETECT			**Assets included in this PM:**	HYDROGEN DETECTION	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Functional test	Carry out a functional test of the equipment						PM				
3	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SPECIAL HAZARDS SYSTEM, KITCHEN HOOD - 10
APM Object	FIRE.SPHZRD.KITCHEN
APM EC	AMZ.FIRE.KHOOD
BBM Handbook Title	Kitchen Hood Suppression System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Sep-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.HVAC.GASDET CT.SAFE.FLAMGASDETECT	**Assets included in this PM:**	KITCHEN HOOD	**Schedule With:**	NO INFO				

Description of System / Technology (According to BBM Handbook)

Automatic fire extinguishing systems pro vided for the protection of grease removal devices, hoods, duct systems, and cooking equipment.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Piping	Ensure the piping system is free from damage, corrosion, and leaks						PM				
2	Piping	Ensure nozzles are clean and adequate for suppression purposes						PM				
3	System	Verify that system pressure meets code and design specifications						PM				
4	System	Confirm that all valves are in the correct position						PM				
5	Electrical components	Are there any alarms indicated						PM				
6	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

Aug 2024 - New PM after OCB update

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, DRY RISERS - 10
APM Object	FIRE.SUP.DRYRISERS
APM EC	AMZ.FIRE.DRY.RISERS
BBM Handbook Title	Dry Risers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DRYRISERS			**Assets included in this PM:**	DRY RISERS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A dry pipe sprinkler system is one in which pipes are filled with pressurized air or nitrogen, rather than water. This air holds a remote valve, known as a dry pipe valve, in a closed position.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						SC				
2	Equipment check	Check if the dry risers are fixed properly, are free from damage & corrosion						SC				
3	Equipment check	Check if the cabinets & pipe/line ends are closed & freely accessible						SC				
4	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additionally required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, EQUIPMENT, EXTINGUISHERS - 10
APM Object	FIRE.SUP.EQP.EXT
APM EC	AMZ.FIRE.EXT
BBM Handbook Title	Fire Extinguishers (Powder, CO2, Foam and Water)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FIGHTINGEQUIP CT.HVAC.ODS	**Assets included in this PM:**	EXTINGUISHERS	**Schedule With:**	FIRE.SUP.EQP				

Description of System / Technology (According to BBM Handbook)

Fire Extinguishers (Powder, CO2, Foam and Water)
Extinguishers are active fire protection device. Each type is suitable for different fire classes.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Extinguisher check	Check if all (the correct) fire extinguishers are available at the required location, free from damage/corrosion & fixed properly						SC				
2	Extinguisher check	Check the maintenance label for overdues and plan action accordingly						SC				
3	Extinguisher check	Check if the operating instructions are available and easy to read on the fire extinguisher						SC				
4	Extinguisher check	Check if the pressure indicator on the fire extinguisher is in the green area & is leak-free						SC				
5	Extinguisher check	Check whether the security bolt or seal is undamaged						SC				
6	Extinguisher check	Check the trigger mechanism of the fire extinguisher without triggering it (don`t remove the pin)						SC				
7	Extinguisher check	Ensure that all required regulatory PMs for the specific fire extinguisher type will be forecasted on time						SC				
8	Equipment check	Check if all additional firefighting equipment (e.g. fire blanketis) available at the correct location, sealed & free from damage						SC				
9	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						SC				

Change Log

Error - Entry for specified object not found on change log

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, FOAM SUPPRESSION - 10
APM Object	FIRE.SUP.FOAM
APM EC	AMZ.FIRE.FOAM
BBM Handbook Title	Foam Systems
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION			**Assets included in this PM:**	FOAM SUPPRESSION	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Foam Systems - Used mostly in kitchens where water protection systems could be dangerous

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						sc				
2	General check	Verify that system pressure meets code and design specifications			sc			sc				
3	General check	Check the equipment for any kind of damage (e.g. pressure gauges, pipes)			sc			sc				
4	General check	Verify all suppression system outlet nozzles to ensure they are unblocked and free from obstructions			sc			sc				
5	General check	Confirm that all valves are in the correct position			sc			sc				
6	Electrical components	Are there any alarms indicated			sc			sc				
7	Electrical components	Did any circuit breaker trip			sc			sc				
8	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						sc				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, HYDRANT - 10
APM Object	FIRE.SUP.HDRNT
APM EC	AMZ.FIRE.HDRNT
BBM Handbook Title	Hydrant (Hose Cabinets,Fire Hydrants or Wall Hydrants)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.HYDRANTS			**Assets included in this PM:**	PRESSURIZED HYDRANT - FIRE HYDRANT	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.WTRTNK FIRE.SUP.VALV FIRE.SUP.WETRISERS		

Description of System / Technology (According to BBM Handbook)

A fire hydrant is a connection point by which firefighters can tap into a water supply. It is a component of active fire protection.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment including location info available & complete						PM				
2	Equipment check	Check the wall hydrant & cabinet is free from damage, fixed properly & no leakage visible				SC						
3	Equipment check	Check for the correct maintenance labels & overdues				SC						
4	Equipment check	Check if the cabinets are closed and sealed				SC						
5	Equipment check	If the sealing is damaged - check if the hose connection is correct, all components (inc. extinguisher - if located in same box) are available, free from damage or manipulations and appl a new seal				SC						
6	Equipment check	Check if the hose connection is correct, all components (inc. extinguisher - if located in same box) are available, free from damage or manipulations and stick a new seal						PM				
7	Equipment check	Check hose connection devices according to local reuqirements (e.g. DIN EN 671-3)						PM				
8	Equipment check	Measure water flow, flow and static pressure at all hose connection valves						PM				
9	Equipment check	Check extinguishing water lines for stability (2 min at 1.5 times nominal pressure).						PM				
10	Equipment check	Check limit switches (if available) electrically and mechanically						PM				
11	Equipment check	Check the shut-off body for mobility and ease of movement						PM				
12	Equipment check	Check the spindle seal for leaks after test						PM				
13	Equipment check	Check the function of the claw, square and dirt deflector						PM				
14	Equipment check	Check that the claw cover is correctly seated on underground hydrants						PM				
15	Equipment check	Check the function and condition of the drop jacket (if present)						PM				
16	Equipment check	Check the filling and emptying station and the free spout						PM				
17	Equipment check	Extinguishing water lines for leaks (10 min at nominal pressure) check						PM				
18	Equipment check	Check & adjust the pressure reducer (if necessary)						PM				
19	Equipment check	Clean the stone trap						PM				
20	Equipment check	Check for easy findability, free reachability/accessibility						PM				
21	Equipment check	Dirt on the claw and protective cover of underground hydrants to free						PM				
22	Equipment check	Check that the jacket pipe is completely empty						PM				
23	Equipment check	Check the integrity of the claws for the upper tube insert						PM				
24	Equipment check	Check mudguard condition						PM				
25	Equipment check	Condition and correct fit of the sealing cap of underground hydrants						PM				
26	Equipment check	Check the function and condition of the cover cap(s) for pillar hydrants						PM				
27	Equipment check	Check waterquality through short-term water flow (sand, stone, etc.)						PM				
28	Equipment check	Secure the hydrant fasteners						PM				
29	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Adding new category according to the last OCB version.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, PRESSURE WATER VESSELS - 10
APM Object	FIRE.SUP.PRESSWTR.VESSELS
APM EC	AMZ.FIRE.WTR.PRESSVESSELS
BBM Handbook Title	Pressure Water Vessel
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION CT.PRESSURE.SYS	**Assets included in this PM:**	PRESSURE WATER VESSEL	**Schedule With:**	FIRE.SUP.PUMP.AS01 FIRE.SUP.PUMP.JP01				

Description of System / Technology (According to BBM Handbook)

A vessel used in fire protection systems to store water under pressurised conditions.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment is available & complete						SC				
2	Safety	Verify that the safety devices, such as the pressure relief valve, are functioning as specified						SC				
3	Safety	Change pressure relief valve according to local regulation						SC				
4	Equipment check	Are all components are undamaged, securely fastened, and free from visible leaks						SC				
5	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, FIRE PUMPS, FIRE PUMP 01 - 10
APM Object	FIRE.SUP.PUMP.AS01
APM EC	AMZ.FIRE.PUMP.AS
BBM Handbook Title	Fire Pumps - Diesel and Electric
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.PUMP			**Assets included in this PM:**	PUMP FUEL TANK - DIESEL ENGINE PUMP - AC MOTOR PUMP - PUMPS CONTROL PANEL	**Schedule With:**	FIRE.SUP.PUMP.JP01		

Description of System / Technology (According to BBM Handbook)

Diesel fire pumps, also known as booster pumps, are used to boost water pressure from sources that do not provide adequate water pressure for the sprinklers to operate to a given specification. A fire pump can be connected to a city water main, tank or reservoir/pond used for firefighting purposes.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Important
Forecast PM together with PM of the control panel (fire suppression controls)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the room properly ventilated						PM				
2	General check	Are the components clean - free from debris & leakage						PM				
3	General check	Check of the equipment for damage & missing components						PM				
4	General check	Check fuel tanks for damage & leakage						PM				
5	General check	Check collection tray for deposits FPM - identify the root cause in case of deposit						PM				
6	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
7	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
8	Documentation	Verify that system schematics are properly mounted on the walls and clearly visible for easy reference						PM				
9	Safety	Are all relevant safety notices visible and free from damage						PM				
10	Safety	Is appropriate fire-fighting equipment available in the rooms						PM				
11	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
12	Safety	Test all safety relevant switches						PM				
13	Battery & Charger	Check if the battery charging device is working correctly (Correct charge/float voltage)		PM								
14	Battery & Charger	Measure the voltage of each battery (Off-charge, using test button or non-intrusive method where possible)						PM				
15	Battery & Charger	Check the batteries for leakage		PM								
16	Battery & Charger	Check the fluid level of the batteries and refill if required						PM				
17	Battery & Charger	Schedule a battery replacement immediately upon detecting any deficiency or performance issue		PM								
18	Fire Pump Fuel Tank	Are all components labeled correctly						PM				
19	Fire Pump Fuel Tank	Visually inspect all fuel system components for leakage						PM				
20	Fire Pump Fuel Tank	Carry out a functional cleaning of the fuel system						PM				
21	Fire Pump Fuel Tank	Are disconnecting devices lockable in the safe position (LOTO)						PM				
22	Fire Pump Fuel Tank	Inspect fuel pumps for damage, corrosion and unusual noise (if the fuel pump is installed)						PM				
23	Fire Pump Fuel Tank	Ensure the fuel pump, if installed, is securely fixed and properly aligned						PM				
24	Fire Pump Fuel Tank	Check if the fuel pump, if installed, is functioning correctly						PM				
25	Fire Pump Fuel Tank	Change fuel filter						PM				
26	Fire Pump Fuel Tank	Check valves for leakage, corrosion & damage						PM				
27	Fire Pump Fuel Tank	Inspect all valves, including automatic and safety valves, to confirm proper operation and functionality						PM				
28	Fire Pump Fuel Tank	Check fuel tank for leakage corrosion & damage						PM				
29	Fire Pump Fuel Tank	Check position/limit value transmitter and limit position switch for correct function						PM				
30	Fire Pump Fuel Tank	Ensure that fuel tank is always full to enable supression in case of a fire		PM				PM				
31	Fire Pump Diesel Motor	Check the Diesel pumps engine for oil leaks		PM								
32	Fire Pump Diesel Motor	Check oil level, with engine not running		PM								
33	Fire Pump Diesel Motor	Check for Diesel pumps engine coolant leaks		PM								
34	Fire Pump Diesel Motor	Check engine block heater temperature [the temperature should be at least 120 F (50 C)]		PM								
35	Fire Pump Diesel Motor	Assess whether the air filter requires cleaning or replacement based on its condition		PM								

36	Fire Pump Diesel Motor	Check if oil needs replacement (based on date or operational hours)		PM								
37	Fire Pump Diesel Motor	For locations with water tanks – Verify that the isolation valve on the tank return line is open before pump starts		PM								
38	Fire Pump Diesel Motor	Start pump in auto React appropriately if there were any problems when pump started		PM								
39	Fire Pump Diesel Motor	Check oil pressure (Typical: 40-70 psi (2.8 – 4.8 bars)		PM								
40	Fire Pump Diesel Motor	Check the sight glass to make sure water is flowing through to the heat exchanger		PM								
41	Fire Pump Diesel Motor	Check the temperature gauge to make sure that engine is running at 160-200 F (70-93 C. Stop pump immediately if heat reaches 200F (93C)		PM								
42	Fire Pump Diesel Motor	Check exhaust for excessive smoke (white, blue or black) If smoke is observed stop engine immediately!!		PM								
43	Fire Pump Diesel Motor	Record oil pressure while diesel is running		PM								
44	Fire Pump Diesel Motor	Record operational hour meter reading		PM								
45	Fire Pump Diesel Motor	Check for water dripping from packing at both ends (should be no more than one drip a second when pump is NOT in use).		PM								
46	Fire Pump Diesel Motor	Is the level of the cooling fluid ok -> refill if required						PM				
47	Fire Pump Diesel Motor	Check for proper corrosion and freezing protection of the cooling fluid						PM				
48	Fire Pump Diesel Motor	Check hoses & pipes for damage & wear						PM				
49	Fire Pump Diesel Motor	Check connections at hoses & pipes for tightness						PM				
50	Fire Pump Diesel Motor	Check the engine starter and alternator for correct function						PM				
51	Fire Pump Diesel Motor	Check all value transmitters and display elements for damage and correct function						PM				
52	Fire Pump Diesel Motor	Check Engine clutch for correct function						PM				
53	Fire Pump Diesel Motor	Are there any unusual noises during start, operation or stop of the engine						PM				
54	Fire Pump Diesel Motor	Grease all possible greasing points						PM				
55	Fire Pump Diesel Motor	Check that the screws and nuts are tight						PM				
56	Fire Pump Diesel Motor	Check engine block for leakage						PM				
57	Fire Pump Diesel Motor	Verify that the exhaust system is securely sealed and free from any damage or defects						PM				
58	Fire Pump Diesel Motor	Exchange jacket heater hose							PM			
59	Fire Pump Diesel Motor	Is the jacket heater thremostat functioning and the thresholds are set correctly						PM	PM			
60	Fire Pump Diesel Motor	Replace coolant and ensure the correctmix according to manufacturer specifications							PM			
61	Fire Pump Diesel Motor	Verify correct coolant protection level (environment & manufacturer specification)					PM		PM			
62	Fire Pump Diesel Motor	Replace collant hoses							PM			
63	Fire Pump Diesel Motor	Replace coolant water pump							PM			
64	Fire Pump Diesel Motor	Replace batteries							PM			
65	Fire Pump Diesel Motor	Replace thermostat							PM			
66	Fire Pump Diesel Motor	Replace belts							PM			
67	Fire Pump Diesel Motor	Verify that hoses are clear of contact with hot surfaces						PM	PM			
68	Fire Pump Diesel Motor	Record operational hours in the notes						PM	PM			
69	Fire Pump Electrical Motor	Check condition of anti vibration mounts						PM	PM			
70	Fire Pump Electrical Motor	Measure the electrical current flow and compare it with the design specification						PM	PM			
71	Fire Pump Electrical Motor	Torque check of motor cable terminations according to OEM to torque requirements						PM	PM			
72	Fire Pump Electrical Motor	Check if the motor generates any unusual noise or vibration during operation						PM	PM			
73	Fire Pump Electrical Motor	Check for overtemperature of the motor						PM	PM			
74	Fire Pump Electrical Motor	Clean the cooling fins and the air inlet screen						PM	PM			
75	Fire Pump Electrical Motor	Lubricate if applicable						PM	PM			
76	Fire Pump	Check the pump for unusual noise and lubricate bearings						PM	PM			
77	Fire Pump	Check pump seals for exessive leakage						PM	PM			
78	Field devices	Check the automatic & correct function of all air in- & outlet flaps						PM	PM			
79	Emergency check	Simulate a power outage of the regular power supply of the control panel						PM	PM			
80	Emergency check	Check if sprinkler pumps start & operation is possible						PM	PM			
81	Pumps Control	Are disconnecting devices lockable in the safe position (LOTO)						PM	PM			
82	Pumps Control	Conduct thermographic scans and create FMP to identify and address the root cause of any over-temperature issues						PM	PM			
83	Pumps Control	Add a detailed note for all over-temperature measurements -> list the location and temperature						PM	PM			
84	Pumps Control	Upload the thermographic scans in case of overtemperature						PM	PM			
85	Pumps Control	Is the panel/cabinet clean - free from debris						PM	PM			
86	Pumps Control	Change the air filter of the electrical panel/cabinet						PM	PM			
87	Pumps Control	Is the cooling fan operating appropriately and doesn`t make any unusual noise						PM	PM			
88	Pumps Control	Visual check of the panel outside & inside for damage & missing components						PM	PM			
89	Pumps Control	Are there any alarms indicated -> if yes identify the root cause						PM	PM			
90	Pumps Control	Are any circuit breakers tripped						PM	PM			
91	Pumps Control	Visual check of cable connections such as pinched insulation in the contact area						PM	PM			
92	Pumps Control	Visual check for the protection against direct contact with live parts						PM	PM			
93	Pumps Control	Were any obvious changes made (e.g. rewiring, hanging cables)						PM	PM			
94	Pumps Control	Are all cables properly routed						PM	PM			
95	Pumps Control	Are all components properly labeled or marked						PM	PM			
96	Pumps Control	Test all safety relevant switches						PM	PM			

97	Pumps Control	Are all components properly attached						PM	PM				
98	Pumps Control	Ensure all cable connections are correctly torqued according to manufacturers specification						PM	PM				
99	Pumps Control	Are all metal parts connected to the protection earth (ground)						PM	PM				
100	Pumps Control	Is the ground connection to the building ground as designed?						PM	PM				
101	Pumps Control	Check if the panel is connected to the emergency power supply correctly (if applicable)						PM	PM				
102	Pumps Control	Carry out functional cleaning of relevant components						PM	PM				
103	Functional cleaning	Clean the air intakes on the engine, generator and main air intake grilles on the outer walls						PM	PM				
104	Functional cleaning	Carry out a functional cleaning of all equipment if required						PM	PM				
105	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additionally required tasks						PM	PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed frequency, changed the whole PM and added tasks for electrical pump motor, added tasks from 10 - FIRE SUPRESSION CONTROL PANELS. Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, FIRE PUMPS, JOCKEY PUMP 01 - 10
APM Object	FIRE.SUP.PUMP.JP01
APM EC	AMZ.FIRE.JPUMP
BBM Handbook Title	Fire Pumps - Jockey Pump
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.PUMP	**Assets included in this PM:**	JOCKEY PUMP - JOCKEY PUMP CNTRL	**Schedule With:**	FIRE.SUP.PUMP.AS01				

Description of System / Technology (According to BBM Handbook)

A jockey pump, also know as a pressure maintenance pump, maintains the pressure in the fire sprinkler system to avoid non emergency starting of the main fire pump.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the technical documentation of the equipment available & complete						PM				
2	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
3	Function	Run jockey pump for 5 minutes (start in auto and verify if the pump started as intended)		PM								
4	Function	Check the pump for correct funtion and abnormal sound or vibration		PM								
5	Function	Did pump shutoff when line pressure was reached		PM								
6	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
7	Safety	Test all safety relevant switches						PM				
8	System Refill	Check the water volume pumped into the system			SC			PM				
9	System Refill	Add the amount in liter into the notes			SC			PM				
10	System Refill	If there is a sign of a leakage, create a WO to identify the root cause			SC			PM				
11	Power consumption	Measure the power consumption & compare to design						PM				
12	Pump	Check pump for unusual noises and lubricate bearings if possible						PM				
13	Jockey Pump Control	Visual check of the electrical panel outside & inside for damage & missing components						PM				
14	Jockey Pump Control	Are there any alarms indicated						PM				
15	Jockey Pump Control	Did any circuit breaker trip						PM				
16	Jockey Pump Control	Visual check of cable connections such as pinched insulation in the contact area						PM				
17	Jockey Pump Control	Visual check for the protection against direct contact with live parts						PM				
18	Jockey Pump Control	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
19	Jockey Pump Control	Are all cables properly routed						PM				
20	Jockey Pump Control	Are all components properly labeled or marked						PM				
21	Jockey Pump Control	Are all components properly attached						PM				
22	Jockey Pump Control	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
23	Jockey Pump Control	Are all metal parts connected to the protection earth (ground)						PM				
24	Functional cleaning	Carry out functional cleaning						PM				
25	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 204 - Moved tasks from Sprinkler System. Changed Component from "Jockey Pumps"

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, CONVEYOR FIRE SHUTTERS - 10
APM Object	FIRE.SUP.SHUTTER
APM EC	AMZ.FIRE.SHUTTER.GRP
BBM Handbook Title	Conveyor Fire Shutters
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SHUTTERS			**Assets included in this PM:**	CONVEYOR FIRE SHUTTER	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

Conveyor Fire Shutters are allocated in walls where conveyors pass from different building areas. Shutters would close in case of a fire to isolate the areas.

Additional Information

Conveyor Fire Shutters are allocated in walls where conveyors pass from different building areas. Shutters would close in case of a fire to isolate the areas.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed equipment available & complete						PM				
2	Functional test	Trigger all shutters via fire alarm & check for correct operation						PM				
3	Functional test	Simulate the operation of the fusible link to ensure the shutter fully closes the fire compartment as per requirement						PM				
4	Functional test	Simulate the operation of the solenoid to ensure the shutter fully closes the fire compartment as per requirement						PM				
5	Functional test	Motor driven parts - check drive for damage and obvious noises or vibration while operating						PM				
6	Functional test	Check the solenoid battery backup panel for proper function						PM				
7	Functional test	Are all relevant connected systems functioning as intended (e.g., stopping the conveyor, if designed to do so)						PM				
8	Functional test	Verify that Emergency Stop mechanisms are functioning correctly (where installed)						PM				
9	Shutter	Is the shutter free from damage and corrosion						PM				
10	Shutter	Verify that hood & hood brackets are in place and secure						PM				
11	Shutter	Verify that End Lugs are Secure						PM				
12	Shutter	Verify that all limit and safety switches are free from damage and ensure that the system operates correctly according to the signal output						PM				
13	Shutter	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
14	Shutter	Inspect all bearings for any signs of wear or damage						PM				
15	Shutter	Inspect curtain roll alignment & tracking for any signs of wear or damage						PM				
16	Shutter	Check for clutch slippage to ensure proper operation of the conveyor fire shutter						PM				
17	Shutter	Check and adjust drive chain tension to ensure proper operation of the conveyor fire shutter						PM				
18	Shutter	Check and correct drive chain alignment to ensure optimal operation of the conveyor fire shutter						PM				
19	Shutter	Inspect and tighten sprockets, and ensure proper alignment to maintain optimal operation of the conveyor fire shutter						PM				
20	Shutter	Lightly lubricate chains and bearings, ensuring that the safety brake is not lubricated						PM				
21	Shutter	Check and adjust spring/curtain tension on self-coiling doors, to ensure proper operation						PM				
22	Shutter	Confirm that the motor hand chain effectively opens the shutter						PM				
23	Shutter	Ensure that the fusible link is not painted or coated, maintaining its proper function						PM				
24	Panel	Inspect panel and all connected electrical components for damage						PM				
25	Panel	Ensure all relevant electrical connections are securely tightened						PM				
26	Panel	Ensure that all live parts are properly enclosed and not accessible						PM				
27	Panel	Replace the cooling filter, clean the inlets, and verify that the cooling fan is functioning correctly						PM				
28	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

Aug 2024 - New PM based on RME field learnings from HIE

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, SPRINKLERS - 10
APM Object	FIRE.SUP.SPRK
APM EC	AMZ.FIRE.SPRK
BBM Handbook Title	Sprinkler System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION			**Assets included in this PM:**	SPRINKLERS	**Schedule With:**	FIRE.SUP.WTRTNK FIRE.SUP.VALV FIRE.SUP.WETRISERS FIRE.SUP.HDRNT		

Description of System / Technology (According to BBM Handbook)

Fire sprinkler systems are active fire protection methods, consisting of a water supply system providing adequate pressure and flowrate to a water distribution piping system, to which fire sprinklers are connected.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Safety	Are all safety devices, are correctly installed and free from damage (e.g., pressure relief devices)						PM				
3	Safety	Ensure that inspection valves has been positioned and locked as per AMZ standard						PM				
4	Sprinkler house/room	Is the entrance freely accessible & free of obstacles		PM								
5	Sprinkler house/room	Is there any visual damage or excessive vegetation at the building or around						PM				
6	Sprinkler house/room	Verify that the roof and roof drainage systems are free from damage and clogging						PM				
7	Sprinkler house/room	Check if the lightning protection is fixed appropriately & not damaged Forecast FPM against Lightning Protection						PM				
8	Sprinkler house/room	Is the door locked properly - protection against unauthorized entry		PM								
9	Sprinkler house/room Indoor	Is the light functioning and the room is illuminated properly		PM								
10	Sprinkler house/room Indoor	Is the heater & temperature control functioning correctly (freezing protection)		PM								
11	Sprinkler house/room Indoor	Check heater for dirt, damage, corrosion		PM								
12	Sprinkler house/room Indoor	Are there any water leaks visible at the walls or ceiling		PM								
13	Sprinkler house/room Indoor	Are there any visible leaks of the sprinkler system		PM								
14	Sprinkler house/room Indoor	Inspect the condition of all visible pipes, hangers, attachments and seismic bracing					PM	PM				
15	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
16	Panel	Check if there are any alarms, warnings etc indicated on the control panels (If dedicated panel installed)		PM								
17	Panel	Check circuit diagrams for completion (If dedicated panel installed)						PM				
18	Panel	If anything is missing or unclear in the circuit diagrams create a WO (If dedicated panel installed)						PM				
19	Panel	Are all cables properly routed (If dedicated panel installed)						PM				
20	Panel	Are all cables, terminal blocks & devices properly labeled or marked (If dedicated panel installed)						PM				
21	Panel	Test all safety relevant switches (If dedicated panel installed)						PM				
22	Panel	Were any obvious changes made (e.g. rewiring, hanging cables) (If dedicated panel installed)						PM				
23	Panel	Visual check for the protection against direct contact with live part (If dedicated panel installed)						PM				
24	Panel	Tight cable connections in the control cabinets & main supply connection boxes (If dedicated panel installed)						PM				
25	Panel	Are all metal parts connected to the protection earth (ground) (If dedicated panel installed)						PM				
26	Panel	Replace the air filters of the cabinet & check operation of cooling fan (If dedicated panel installed)						PM				
27	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause (If dedicated panel installed)						PM				
28	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan (If dedicated panel installed)						PM				
29	Sprinkler system	Inspect the condition of all visible pipes, hangers, attachments and seismic bracing						PM				
30	Sprinkler system	Inspect condition of sprinkler heads for signs of damage, corrosion & risks that could trigger an FFA						PM				
31	Sprinkler system	Conduct a full functional test of the sprinkler system, including alarm system						PM				
32	Sprinkler system	Inspect the condition of all visible pipes, hangers, attachments and seismic bracing for corrosion, damage, or wear						PM				
33	Sprinkler system	Verify the hydraulic design data, including flow & pressure requirements						PM				
34	Sprinkler system	Release condensate water from any dry pipe string						PM				
35	Spare parts	Check the condition of spare sprinklers, ensure they are properly stored & available for the SME in case needed						PM				

36	Spare parts	Check the condition of special tools, ensure they are properly stored & available for the SME in case needed						PM					
37	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 1M and 3M and added 6M.Added tasks due to HIE (FFA).

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, VALVES - 10
APM Object	FIRE.SUP.VALV
APM EC	AMZ.FIRE.VALV
BBM Handbook Title	Fire Suppression Valves
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**		**Delivered By:**	**OCB:** BBM
Evidence for CT:	NO	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION	**Assets included in this PM:**	FIRE VALVES	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.WTRTNK FIRE.SUP.WETRISERS FIRE.SUP.HDRNT		

Description of System / Technology (According to BBM Handbook)

GATE VALVE: Gate valves are used to isolate the specific area of water supply to the network during maintenance, repair works, new installations, as well as to reroute water flow throughout the pipeline.
BUTTERFLY VALVE: Butterfly valves can be used for throttling or regulating flow as well as in the full open and fully closed position. The pressure loss through a butterfly valve is small in comparison with the gate valve.
PRESSURE REDUCING VALVE: A Pressure Reducing Valve (PRV) is an Automatic Control Valve designed to reduce a higher unregulated inlet pressure to a constant, reduced downstream (outlet) pressure regardless of variations in demand and/or upstream (inlet) water pressure.
FIRE BACKFLOW PREVENETER: Backflow preventers provide a critical interface between a building's fire protection system and the water supply that feeds it. A backflow preventer is a device designed to ensure that water inside a building's fire sprinkler system

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Gate valve	Is the valve in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
2	Gate valve	Inspect the valve to ensure it is undamaged, leakage free, functioning properly & moving smoothly		PM								
3	Gate valve	Is the valve properly labeled according to Amazon standards		PM								
4	Gate valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)						PM				
5	Butterfly Valve	Is the valve in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
6	Butterfly Valve	Inspect the valve to ensure it is undamaged, leakage free, functioning properly & moving smoothly		PM								
7	Butterfly Valve	Is the valve in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
8	Pressure Reducing Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
9	Pressure Reducing Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)						PM				
10	Fire Backflow Preventer Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
11	Fire Backflow Preventer Valve	Is the valve properly labeled according to Amazon standards		PM								
12	Fire Backflow Preventer Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)		PM								
13	Fire Backflow Preventer Valve	Open the maintenance cover on the supply site and release the water						PM				
14	Fire Backflow Preventer Valve	Check if there is not water flowing back from the building pipes						PM				
15	Auxiliary Drain Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
16	Auxiliary Drain Valve	Is the valve properly labeled according to Amazon standards		PM								
17	Auxiliary Drain Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)						PM				
18	Auxiliary Drain Valve	Carry out a functional test and ensure dirt deposit is drained out						PM				
19	Check Valve	Inspect the valve to ensure it is undamaged, leakage free & functioning properly		PM								
20	Check Valve	Is the valve properly labeled according to Amazon standards		PM								
21	Check Valve	Verify that connected sensors and manometers are fucntioning correctly (if applies)						PM				
22	Check Valve	Check if there is not water flowing back from outlet side						PM				
23	Alarm Valve	Inspect the valve to ensure it is undamaged, leakage free, functioning properly		PM								
24	Alarm Valve	Verify that connected sensors & manometers are fucntioning correctly (if applies)		PM								
25	Alarm Valve	Verify tthe correct function of the waterflow alarm						PM				

Change Log

June 2024 - New PM specific for fire valves.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, WET RISERS - 10
APM Object	FIRE.SUP.WETRISERS
APM EC	AMZ.FIRE.WET.RISERS
BBM Handbook Title	Wet Risers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**		**Delivered By:**	**OCB:** BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION	**Assets included in this PM:**	WET RISERS	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.WTRTNK FIRE.SUP.VALV FIRE.SUP.HDRNT		

Description of System / Technology (According to BBM Handbook)

A sprinkler system employing automatic sprinklers attached to a piping system containing water and connected to a water supply so that water discharges immediately from sprinklers opened by heat from a fire. Includes a water supply source, a control valve, a waterflow alarm, and a drain Wet pipe sprinkler systems are the most common form of fire sprinkler system.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Wet risers	Verify that all protecting components (e.g., fences & doors) are undamaged		PM								
2	Wet risers	Spring test of all Post Indicating Valves (PIV) and valve supervidory switches				PM		PM				
3	Wet risers	Are additional valves in the correct poisition, properly labeled and locked if necessary according to Amazon standards		PM								
4	Wet risers	Inspect additional valves to ensure it is undamaged, leakage free, functioning properly & moving smoothly		PM								
5	Wet risers	Are additional valves properly labeled according to Amazon standards		PM								
6	Wet risers	Verify that connected sensors & manometers to Are additional valves are fucntioning correctly (if applies)						PM				
7	Wet risers	Turn every sprinkler control valve based on NFPA guidelines Ensure valves are reopened and locked after the test				PM		PM				
8	Wet risers	Verify that the main drain is open and free from obstruction						PM				
9	Wet risers	Conduct a main drain test to assess water supply & system performance						PM				

Change Log

June 2024 - New PM specific for wet risers.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, WATER STORAGE TANKS - 10
APM Object	FIRE.SUP.WTRTNK
APM EC	AMZ.FIRE.WT
BBM Handbook Title	Water Storeage Tanks
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SUPPRESSION	**Assets included in this PM:**	WATER STORAGE FIRE TANKS	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.VALV FIRE.SUP.WETRISERS FIRE.SUP.HDRNT				

Description of System / Technology (According to BBM Handbook)

Emergency supply of water for fire suppression equipment e.g. Sprinkler System

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Tank	Record the tank temperature in °C		PM								
2	Tank	Check if the tank is filled correctly (correct water level)		PM								
3	Tank	Check if all tank equipment is free from damage, rust & corrosion, fixed properly & leak-free		PM								
4	Tank	Check the tank relief valve or overflow for correct function						PM				
5	Tank	Verify proper functioning of the tank and pipe heaters						PM				
6	Tank	Does the Sprinkler tank has a free flow inlet separation and can`t contaminate the drinking water						PM				
7	Hygiene	Carry out a CCTV check for debris inside the tank						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM for FIRE.SUP.WTRTNK.
Aug 2024 - Added task to verify correct function tank and pipe heating after lesson learned during site visit

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	GAS SYSTEM - 9
APM Object	GAS
APM EC	AMZ.GAS
BBM Handbook Title	Gas System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.GASINSTALL			**Assets included in this PM:**	GAS SYSTEM	**Schedule With:**	HVAC.BLR HVAC.GH WTR.SUPPLY.HTR.01		

Description of System / Technology (According to BBM Handbook)

Gas System includes: Gas Valves, Meters, Booster pumps, Reduction valves and Natural gas generators.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the gas system documentation complete & are there drawings on the wall						PM				
2	Gas distribution rooms	Are the gas connection & distribution rooms freely accessible						PM				
3	Gas distribution rooms	Are meters & valves freely accessible						PM				
4	Gas distribution rooms	Are the gas connection & distribution rooms properly ventilated						PM				
5	Gas distribution rooms	Marking of the room incl. warning and prohibition instructions / safety instructions are correct and visible						PM				
6	Measurement devices	Are installed Gas detectors functioning as designed						PM				
7	Gas pipe system	Are all installed devices working properly (e.g. booster pump, pressure reduction)						PM				
8	Gas pipe system	Check gas pipe connections in gas connection & distribution room for leakages						PM				
9	Gas pipe system	Is there any visual damage at the gas pipe system throughout the building check also for proper suspension						PM				
10	Gas pipe system	Are the connections at all gas consumers free from damage, corrosion & free from leakages - Only the visible connections (it`s not required to dismantle the kitchen appliances)						PM				
11	Electrical	Maintain electrical elements components to local regulations (e.g. DIN VDE)						PM				
12	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Added "forecast with".

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, AIR CONDITION - 9
APM Object	HVAC.AC
APM EC	AMZ.HVAC.AC.GRP
BBM Handbook Title	Air Conditioning and Air Condensing (VRF / DX) Units
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	Refrigeration certificate could be required	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	AIR CONDITIONER UNIT	**Schedule With:**	HVAC.CU		

Description of System / Technology (According to BBM Handbook)

Air Condition (AC unit- indoor)
An air conditioning system is used to cool down the temperature in an inside space by removing the existing heat and moisture from the room.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
This PM covers the direct evaporating & water supplied fan-coil units installed inside the building in the offices & shop floor. (AC system - e.g. single split, multi split, VRF, VRV, etc.)

Note : Forecast the PM for the indoor (AC.ACU) & outdoor (AC.CU) units together and combine it with regulatory tasks (e.g. leakage test F Gas regulation)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of installed BBA available & complete						PM				
2	General	Is the unit freely accessible & maintainable					SC	PM				
3	Measurement	Is the fan coil unit operating correctly (speed & temperature)					SC	PM				
4	Unit operation	Are there any obvious leakage of condensated water					SC	PM				
5	Unit operation	Check the fan for unusual noises (e.g. imbalance & bearing damage)					SC	PM				
6	Hygiene & Filter	Clean reusable filter or exchange disposable filter 80% of the capacity is reached					SC	PM				
7	Hygiene & Filter	Clean air inlet & outlet frames & surrounding surfaces						PM				
8	Hygiene & Filter	Clean impeller (fan) & reachable surfaces						PM				
9	Hygiene & Filter	Spray AC disinfection into running unit (coil disinfection)						PM				
10	Hygiene & Filter	Check Textile air hose for damage, contamination & dirt					SC	PM				
11	Hygiene & Filter	Schedule exchange or washing of the textile air hose if necessary					SC	PM				
12	Pipe system	DX unit - refrigeration pipes & connections for corrosion & oil build up (leakage)						PM				
13	Pipe system	Water supplied unit - Check pipes & connections for corrosion & leakage						PM				
14	Pipe system	Water supplied unit - Check control valves for correct functionality						PM				
15	Pipe system	Water supplied unit - Check pipe filters for free flow						PM				
16	Pipe system	Check Pipe insulation for damage						PM				
17	Drain	Check condensate pump & condensate pipes for correct operation, damage						PM				
18	Drain	Does the condensate pipe has a free outlet to the drainage (not connected directly to drainage)						PM				
19	Final Check	Check the O&M manual and carry out additional required tasks						PM				
1	General check & Documentation	Is the unit freely accessible & maintainable						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed task "Is there ice build on the coil -> if yes eliminate root cause"

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, AIR HANDLING UNITS - 9
APM Object	HVAC.AHU
APM EC	AMZ.HVAC.AHU.GRP
BBM Handbook Title	Air Handling Units (AHUs)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	Hygiene certification required in some countries (e.g. VDI 6022)	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.INDOOR			**Assets included in this PM:**	AIR HANDLER UNIT	**Schedule With:**	HVAC.HMD HVAC.BLR (if installed)		

Description of System / Technology (According to BBM Handbook)

An air handler, or air handling unit (AHU), is a device used to regulate and circulate air that is a typical of HVAC system types seen across Amazon FC's. An AHU typically contains the fans, filter chambers and dampers. Heating elements can be integrated (I.e. gas burners) or separate via a DX heating/cooling unit for example. AHU's can also provide free cooling.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed system available & complete						PM		PM		
2	AHU outside check	Is the unit freely accessible & maintainable			SC	SC	SC	PM		PM		
3	AHU outside check	Is the unit in operation & no alarms indicated - check unit control cabinet			SC	SC	SC	PM		PM		
4	AHU outside check	Check unit air intakes & outlets for corrosion & damage, contamination & condensation			SC	SC	SC	PM		PM		
5	AHU outside check	Is there any unusual noise or vibration that could be caused by a faulty unit component			SC	SC	SC	PM		PM		
6	AHU outside check	Are there any visual damage, missing- or loose components at the unit			SC	SC	SC	PM		PM		
7	AHU outside check	Is water dropping out of the unit			SC	SC	SC	PM		PM		
8	AHU outside check	Check of the drain & drain trap (e.g. ball siphon) connected to the unit, chek for correct function & damage						PM		PM		
9	AHU filter	Check filters for unacceptable contamination, damage, leaks (can the air bypass the filter medium?)			SC	SC	SC	PM		PM		
10	AHU filter	Measure differential pressure of all filter stages by using adequate tools			SC	SC	SC	PM		PM		
11	AHU filter	List the differential pressures in the notes			SC	SC	SC	PM		PM		
12	AHU filter	Schedule filter change when 80% of the capacity is reached			SC	SC	SC	PM		PM		
13	AHU filter	(An increased filter change is ok due to environmental impact)						PM		PM		
14	AHU filter	In the notes, please enter the number of filter changes per filter stage within the year						PM		PM		
15	AHU Fan	Change belts and check pulleys at belt driven fans						PM		PM		
16	AHU Hygiene & damages	Check droplet eliminator and tray for contamination e.g. mold, corrosion & damage				SC	SC	PM		PM		
17	AHU Hygiene & damages	Check cooling coil & condensate tray for contamination, corrosion & damage				SC	SC	PM		PM		
18	AHU Hygiene & damages	Clean unit air intakes and outlets						PM		PM		
19	AHU Hygiene & damages	Clean droplet eliminator & tray and check for contamination e.g. mold, corrosion & damage						PM		PM		
20	AHU Hygiene & damages	Clean cooling- & heating coil, as well as condensate tray using professional cleaning materials						PM		PM		
21	AHU Hygiene & damages	Check for contamination, corrosion & damage						PM		PM		
22	AHU Hygiene & damages	Clean fans & impeller and check for contamination, corrosion & damage						PM		PM		
23	AHU Hygiene & damages	Clean Chamber surfaces inside the unit and check for contamination, corrosion & damage						PM		PM		
24	AHU Hygiene & damages	Visual check of heat recovery for contamination, corrosion & damage					SC	PM		PM		
25	AHU Hygiene & damages	Visual check of heating coil for contamination, corrosion & damage					SC	PM		PM		
26	AHU Hygiene & damages	Visual check of silencers for contamination, corrosion & damage						PM		PM		
27	AHU Heat exchange	Functional check of frost protection thermostat						PM		PM		
28	AHU Heat exchange	Check the electrical heater for contamination, corrosion & damage						PM		PM		
29	AHU Heat exchange	Check the electrical heater according to local electrical regulations						PM		PM		
30	AHU Heat exchange	Check directly heated heat exchanger for tightness						PM		PM		
31	AHU Heat exchange	Vacuum all remaining heat exchanger carefully						PM		PM		
32	AHU Heat exchange	Check of reheater & cooler installed in the duct system for contamination, corrosion & damage						PM		PM		
33	AHU Heat exchange	Change filter of reheater & cooler installed in the duct system						PM		PM		
34	AHU Heat exchange	Measure differential pressure of all heat exchanger, compare with design and schedule professional cleaning if differential pressure is 30% higher than designed -> use professional tool								PM		
35	AHU Heat Recoery wheel	Check the heat recovery wheel for correct functionality & for damage						PM		PM		

36	AHU duct system	Check air outlets & intakes of the duct system for debris, contamination, corrosion & damage						PM		PM			
37	AHU duct system	Choose 5 locations and add the locations into the notes Check inner duct system checks for contamination, corrosion, condensation & dirt						PM		PM			
38	AHU duct system	Check Textile air hose for damage, contamination & dirt						PM		PM			
39	AHU duct system	Schedule exchange or washing of the textile air hose if necessary						PM		PM			
40	AHU duct system	Underground components - check for contamination, corrosion & dirt deposit inside of the duct						PM		PM			
41	Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM		PM			
42	Control cabinet	Check circuit diagrams for completion						PM		PM			
43	Control cabinet	If anything is missing or unclear in the circuit diagrams create a WO						PM		PM			
44	Control cabinet	Are all cables properly routed						PM		PM			
45	Control cabinet	Are all cables, terminal blocks & devices properly labeled or marked						PM		PM			
46	Control cabinet	Test all safety relevant switches						PM		PM			
47	Control cabinet	Were any obvious changes made (e.g. rewiring, hanging cables)						PM		PM			
48	Control cabinet	Visual check for the protection against direct contact with live part						PM		PM			
49	Control cabinet	Tight cable connections in the control cabinets & main supply connection boxes						PM		PM			
50	Control cabinet	Are all metal parts connected to the protection earth (ground)						PM		PM			
51	Control cabinet	Replace the air filters of the cabinet & check operation of cooling fan						PM		PM			
52	Measurements	Measure the power consumption of the Fans in full speed with open dampers						PM		PM			
53	Measurements	Add the values into the notes indicating the fans & compare to design specifications of the fan						PM		PM			
54	Measurements	Measure the main discharge & return air volume flow - add airflow and position into the notes						PM		PM			
55	Measurements	Compare measured airflow with design specification						PM		PM			
56	Measurements	Measure the main discharge & return air temperature						PM		PM			
57	Measurements	Compare measured temperature with value in the BMS, add temperature and create a FWO under BMS in case of deviation						PM		PM			
58	Final Check	Check the O&M manual and carry out additional required tasks						PM		PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Moved "Humidifier tasks" to HVAC.HMD PM.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, BOILER UNITS - 9
APM Object	HVAC.BLR
APM EC	AMZ.HVAC.BLR.GRP
BBM Handbook Title	Boiler Units (natural gas)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.BOILERS			**Assets included in this PM:**	NATURAL GAS BOILER UNIT	**Schedule With:**	HVAC.RTU HVAC.AHU HVAC.WTR HVAC.GH		

Description of System / Technology (According to BBM Handbook)

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The PM should be carried out before the heating / winter season starts.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the boiler documentation complete & are there drawings on the wall						PM				
2	Visual check	Are installations damaged or loose (incl. cables connected to equipment)						PM				
3	Gas Burner	Check the gas burner for correct function and leakage (burner & exhaust)						PM				
4	Visual check	Check any flexible gas pipes and connections for damage or leakage						PM				
5	Boiler check	Check the sequence of operation of the burner						PM				
6	Boiler check	Check the combustion fan and proceed to the cleaning						PM				
7	Boiler check	Check the pressure of the gas supplying the unit						PM				
8	Boiler check	Check the state of the flame						PM				
9	Boiler check	Perform a flue gas analysis						PM				
10	Final Check	Undertake inspection and maintenance in line with O&M + local regulations						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New tasks added. Included "forecast with".

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, CHILLER UNITS - 9
APM Object	HVAC.CHILL
APM EC	AMZ.HVAC.CHILL.GRP
BBM Handbook Title	Chillers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	Refrigeration certificate could be required	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.12KW CT.HVAC.ODS CT.HVAC.FGAS			**Assets included in this PM:**	CHILLER UNIT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

In HVAC systems, chillers provide chilled water to heat exchangers, or coils, in AHU's or other types of terminal devices, which cool the air in their respective space(s).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
This standard also applies for Heat pumps to supply assets with heating & chilled water.
The yearly PM should be planned before the summer season starts.

Refrigerant part -> Ensure that leakage and any other requirements according to F Gas Regulation are followed - combine regulatory WOs with a non regulatory PM to be efficient

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the technical documentation & blueprints of installed system available & complete						PM				
2	Unit check	Is there any unusual noise or vibration that could be caused by a faulty unit component			SC		SC	PM				
3	Unit check	Is the condenser coil free from dirt, damage & corrosion Schedule cleaning if airflow through coil is impaired			SC		SC	PM				
4	Unit check	Is there any visual damage, missing- or loose components at the unit			SC		SC	PM				
5	Unit check	Is there any deposit in the drip tray (system fluid)			SC		SC	PM				
6	Unit check	Is there oil deposit visible at the connections of the pipe system					SC	PM				
7	Unit check	Is the refrigerant pipe insulation free from damage						PM				
8	Controller & Control cabinet	Is the unit in operation & no alarms indicated - check unit control cabinet						PM				
9	Controller & Control cabinet	Are any settings in manual mode -clarify the reason & set back to automatic mode						PM				
10	Controller & Control cabinet	Did any circuit breaker trip - identify & eliminate the root cause or create a WO						PM				
11	Controller & Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM				
12	Controller & Control cabinet	Check circuit diagrams for completion						PM				
13	Controller & Control cabinet	If anything is missing or unclear in the circuit diagrams create a WO						PM				
14	Controller & Control cabinet	Are all cables properly routed						PM				
15	Controller & Control cabinet	Are all cables, terminal blocks & devices properly labelled or marked						PM				
16	Controller & Control cabinet	Test all safety relevant switches						PM				
17	Controller & Control cabinet	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
18	Controller & Control cabinet	Visual check for the protection against direct contact with live part						PM				
19	Controller & Control cabinet	Tight cable connections in the control cabinets & main supply connection boxes						PM				
20	Controller & Control cabinet	Are all metal parts connected to the protection earth (ground)						PM				
21	Unit check	Replace the air filters of the cabinet & check operation of cooling fan						PM				
22	Refrigerant leakage	Is an appropriate record for the refill of refrigerant physically available						PM				
23	Refrigerant leakage	Add to notes the refill of refrigerant during the last year in KG (year in maintenance interval, not calendar year)						PM				
24	Refrigerant leakage	Add to notes details of reasaon for refrigerant refill						PM				
25	Functional cleaning	Clean condenser coil with state-of-the-art technology (professional)						PM				
26	Functional cleaning	Clean condenser fan blades (& housing in case of dirt deposit)						PM				
27	Functional cleaning	Carry out a functional cleaning of all reachable components						PM				
28	Measurements	Connect the refrigerant manometer & temperature sensors (always compare with controller data)						PM				
29	Measurements	Are the refrigeration pressures and refrigerant temperatures correct						PM				
30	Measurements	Is the expansion valve working properly & superheat OK						PM				
31	Measurements	Is the undercooling temperature ok						PM				
32	Measurements	Are the condenser & evaporator temperatures ok						PM				
33	Measurements	Measure the power consumption of the compressors while operating on 100% Compare the power consumption with the manufacturer specification - react in case of deviation						PM				
34	Measurements	Measure the power consumption of the condenser fans while operating on 100% Compare the power consumption with the manufacturer specification - react in case of deviation						PM				
35	Measurements	Add the operational hours of all compressors into the notes						PM				

36	Measurements	Identify & eliminate the root cause if there are big differences in operational hours						PM					
37	Measurements	Are the compressors switched in the correct order						PM					
38	Measurements	Measure the oil pressure & adjust if required						PM					
39	Measurements	Is the oil temperature/presuure before & after refrigerant filter ok						PM					
40	Measurements	Is the compressor oil level ok						PM					
41	Measurements	Conduct oil analyses & schedule actions if required						PM					
42	Compressor & Safety	Does the low-pressure switch work properly						PM					
43	Compressor & Safety	Does the high-pressure switch work properly						PM					
44	Compressor & Safety	Simulate safety switches of the system (e.g. thermostats, timers, etc.)						PM					
45	Compressor & Safety	Is the crankcase heater working properly (attached to compressor)						PM					
46	Compressor & Safety	Is the oil separator working properly						PM					
47	Compressor & Safety	Check if there is water in the refrigeration system (show glass)						PM					
48	Compressor & Safety	Check refrigerant flow through show glass						PM					
49	Compressor & Safety	Does the condensate tub heater work properly						PM					
50	Compressor & Safety	At Screw Compressor - return valve check						PM					
51	Compressor & Safety	Lubricate all moving parts and bearings if reachable						PM					
52	Chilled water system	Is the water flow sensor functioning correctly						PM					
53	Chilled water system	Is the chilled water system free from visible leakages						PM					
54	Chilled water system	Are there damage or corrosion at the heat exchanger (refrigeration to water)						PM					
55	Chilled water system	Are in- & outlet temperatures at the heat exchanger correct (refrigeration to water)						PM					
56	Chilled water system	Is the chilled water pressure according to design (system fill)						PM					
57	Chilled water system	Is the buffer tank free from damage & filled properly						PM					
58	Chilled water system	Does the expansion tank functioning properly						PM					
59	Chilled water system	Are all system valves working correctly						PM					
60	Chilled water system	Check the water flow rate if possible						PM					
61	Chilled water system	Is the pipe & buffer tank insulation free from damage						PM					
62	Chilled water system	Does the glycol concentration in the water ensures avoidance of component damage during winter season - check the technical docs for more information, if glycol is required						PM					
63	Chilled water system	Does the trace heating work properly (chilled water pipes)						PM					
64	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, CONVECTOR RADIATOR UNITS - 9
APM Object	HVAC.CNV
APM EC	AMZ.HVAC.CNV.GRP
BBM Handbook Title	Convector Heater Units
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Certified electrician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.ELEC.PAT	**Assets included in this PM:**	ELECTRICAL HEATER UNIT	**Schedule With:**	-				

Description of System / Technology (According to BBM Handbook)

A convection radiator is a heating terminal unit which uses electricity has its heating source and utilizes convection (ie : fan) heat principles and not radiation. Amazon considers other non water supplied heating systems which are primarily electric driven within this Convector Radiator Unit System. (ie : Air Curtains,heated or non heated).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The yearly PPM should be carried out before the start of the heating season (winter)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the unit free from damage or corrosion						PM				
2	Safety	Are all safety devices functioning correctly						PM				
3	Safety	All electrical components free for damage and live parts not accesible						PM				
4	Function	Is the unit functioning correctly						PM				
5	Function	Is there any unusual noise or vibration						PM				
6	Hygiene & Filter	Clean reusable filter or exchange disposable filter						PM				
7	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM according to the new category created in the OCB.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, AIR CONDENSING - 9
APM Object	HVAC.CU
APM EC	AMZ.HVAC.CU.GRP
BBM Handbook Title	Air Condition (AC unit- indoor)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	Yes	**Special Certificaion Required:**	Refrigeration certificate could be required	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.12KW CT.HVAC.FGAS			**Assets included in this PM:**	CONDENSER UNIT	**Schedule With:**	HVAC.AC		

Description of System / Technology (According to BBM Handbook)

Air Condensing- (AC unit – outside)

An air conditioning condenser unit is the outdoor part of the AC system. The outdoor unit contains the fan, the condenser and a compressor. Both the indoor unit and the outdoor unit are required to work together to provide cool air to the rooms of your home. The condenser is the most vital part of the outdoor unit. Available options: single & multi split, VRV, VRF, etc.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
This PM covers the direct evaporating outdoor unit of an AC system including heat pumps (e.g. single split, multi split, VRF, VRV, etc.)

Note : Forecast the PM for the indoor (AC.ACU) & outdoor (AC.CU) units together and combine it with regulatory tasks (e.g. leakage test F Gas regulation)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
2	General check & Documentation	Is the documentation of the system complete (circuit diagrams, blueprints, etc.)						PM				
3	General check & Documentation	Is the unit in operation & no alarms indicated - unit controller or control cabinet					SC	PM				
4	General check & Documentation	Are there any visual damage, missing- or loose components or corrosion					SC	PM				
5	Refrigerant leakage	Is an appropriate record for the refill of refrigerant physically available						PM				
6	Refrigerant leakage	Add to notes the refill of refrigerant during the last year in KG (year in maintenance interval, not calendar year)						PM				
7	Refrigerant leakage	Add to notes details of reason for refrigerant refill						PM				
8	AC unit check	Are there unusual noises of running compressors or condenser fans					SC	PM				
9	AC unit check	Is the condenser coil free from dirt, damage & corrosion					SC	PM				
10	AC unit check	Is there any deposit in the drip tray						PM				
11	AC unit check	Is there oil deposit visible at the connections of the pipe system					SC	PM				
12	AC unit check	Is the pipe insulation free from damage					SC	PM				
13	Functional cleaning	Clean condenser coil with state-of-the-art technology						PM				
14	Functional cleaning	Clean condenser fan blades & frame						PM				
15	Measurement	Connect the refrigerant manometer & temperature sensors (always compar with controller data)						PM				
16	Measurement	Are the refrigerant pressures and refrigerant temperatures correct						PM				
17	Measurement	Is the expansion valve working properly & superheat OK						PM				
18	Measurement	Are the condenser & evaporator temperatures ok						PM				
19	Measurement	Is the undercooling temperature ok						PM				
20	Measurement	Is the oil temperature/presuure before & after refrigerant filter ok (if appicable)						PM				
21	Measurement	Is the compressor running according to the controls (frequencies)						PM				
22	Measurement	Are the condenser fans running properly (cond. pressure ctrl., frequency, etc.)						PM				
23	Measurement	Check the compressor operation time and quantity of switching cycles if possible and react properly in case of abnormalities						PM				
24	Measurement	Add to notes operation hours of the compressors						PM				
25	Measurement	Conduct oil analyses & plan action if required (if possible)						PM				
26	Measurement	Measure the oil pressure & adjust if required (if possible)						PM				
27	Measurement	Measure the power consumption of the compressors while operating on 100% & compare the power consumption with the manufacturer specification - react in case of deviation						PM				
28	Measurement	Measure the power consumption of the condenser fans while operating on 100% & compare the power consumption with the manufacturer specification - react in case of deviation						PM				
29	Compressor & Safety	Does the low-pressure switch work properly						PM				
30	Compressor & Safety	Does the high-pressure switch work properly						PM				
31	Compressor & Safety	Simulate other safety switches of the system						PM				
32	Compressor & Safety	Is the crankcase heater working properly (attached to compressor)						PM				
33	Compressor & Safety	Is the compressor oil level ok (if visible)						PM				
34	Compressor & Safety	Is the oil separator working properly						PM				
35	Compressor & Safety	Check if there is humidity in the refrigeration system (show glass)						PM				
36	Compressor & Safety	Check refrigerant flow through show glass						PM				

37	Compressor & Safety	Check correct funcitonlity of coil defrost						PM				
38	Compressor & Safety	Does the condensate tub heater work properly						PM				
39	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, aligmment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, KITCHEN EXHAUST DUCT SYSTEM - 9
APM Object	HVAC.DH
APM EC	AMZ.HVAC.DH
BBM Handbook Title	Kitchen Exhaust Duct System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.ENVIRO.EXTRACT			**Assets included in this PM:**	KITCHEN EXHAUST DUCT SYSTEM	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A Kitchen Exhaust Duct System is a set of components that remove smoke, heat, and odors from a commercial kitchen or cooking area. Typically the system consists of an exhaust hood, fan, duct and vent, all working together to ventilate the smoke and odors to the outside.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Ensure that the kitchen exhaust duct cleaning is carried out according to loacal rgulations/requirements

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the system complete & available					PM					
2	Duct system	Is there any damage or corrosion at the exhaust hoods or duct system visible			SC		PM					
3	Duct system	Is the inner duct system free from grease deposit			SC		PM					
4	Duct system	Schedule duct system & exhaust fan cleaning in case of thig grease deposit (fire hazard)			SC		PM					
5	Duct system	Clean inner duct system, hoods & exhaust fan At least once in every 6 months of operation - use state-of-art technology					PM					
6	Electrical & fan condition	Is the power consumption of the fan as per manufacturer`s specs (after cleaning)					PM					
7	Electrical & fan condition	Does the fan make unusual noises or vibration			SC		PM					
8	Electrical & fan condition	The cooking devices & dishwashers switch off in case of missing exhaust airflow					PM					
9	Electrical & fan condition	Change the belt of the exhaust fan (if belt driven)					PM					
10	Electrical & fan condition	Check other mechanical components like pulleys and bearings for defects					PM					
11	Measurement	Measure the airflow of the kitchen exhaust & compare to design					PM					
12	Final Check	Check the O&M manual and carry out additional required tasks					PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, EXHAUST FAN UNITS - 9
APM Object	HVAC.EF
APM EC	AMZ.HVAC.EF.GRP
BBM Handbook Title	Exhaust Fan
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.ENCSPACE			**Assets included in this PM:**	EXHAUST FANS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Exhaust fans are generally connected to the roof and operate to discharge warm internal air to the outside atmosphere. There are used in Amazon FC's to cool the FC space before active cooling is initiated.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Ensure that the kitchen exhaust duct cleaning is carried out according to loacal rgulations/requirements

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the system complete & available						PM				
2	General	Check the room for unusual odur from e.g., drainage Create action to eliminate the root cause				SC	PM	PM				
3	Duct system	Check inner duct system, exhaust intakes (rooms) & exhaust outlet (fan) Scheule cleaning if blocked or in case of high accumulation of dirt						PM				
4	Duct system	Check inner duct system for blockages & extensive dirt accumulation 30% of the outlets 1m of the system - Ensure correct rotation						PM				
5	Measurement	Is the power consumption of the fan as per manufacturer`s specs						PM				
6	Measurement	Measure the airflow of the exhaust & compare to design						PM				
7	Electrical & fan condition	Does the fan make unusual noises or vibration				SC	PM	PM				
8	Electrical & fan condition	Change the belt of the exhaust fan (if belt driven)					PM	PM				
9	Electrical & fan condition	Check other mechanical components like pulleys and bearings for defects					PM	PM				
10	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, GAS DARK HEATERS - 9
APM Object	HVAC.GH
APM EC	AMZ.HVAC.GH.GRP
BBM Handbook Title	Gas Heater Unit
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.HVAC.GASAPPLIANCE			**Assets included in this PM:**	GAS HEATER UNIT	**Schedule With:**	GAS HVAC.BLR WTR.SUPPLY.HTR.01		

Description of System / Technology (According to BBM Handbook)

A gas heater is a space heater used to heat a room or outdoor area by burning natural gas, liquefied petroleum gas, propane, or butane.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This PM yearkly Gas Radiant Tube Heater should be carried out before the winter season starts

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Functional check	Is the heater functioning properly						PM				
2	General	Is the documentation of installed BBA available & complete						PM				
3	Unit check	Are there any damage at the heater (e.g. loose parts)						PM				
4	Burner	Is the burner engine functioning as designed						PM				
5	Burner	Are there any unusual noises (e.g. bearings)						PM				
6	Burner	Is the impeller free from dirt & damage						PM				
7	Burner	Is the flame sensor functioning as designed						PM				
8	Burner	Is the ignition device functioning as designed						PM				
9	Control & safety device	Is the mixing device free from dirt & damage (gas & air)						PM				
10	Control & safety device	Is the air adjustment device functioning as designed						PM				
11	Control & safety device	Is the lack of air protection device functioning as designed						PM				
12	Control & safety device	Are the air seal flaps functioning as designed						PM				
13	Control & safety device	Are the manual control valves functioning properly						PM				
14	Control & safety device	Is the gas pressure regulator functioning as designed						PM				
15	Control & safety device	Are the magnetic valves functioning as designed						PM				
16	Control & safety device	Are the Gas pipes & fittings tight						PM				
17	Control & safety device	Check connection and nozzle pressure						PM				
18	Measurement	Carry out an exhaust analysis						PM				
19	Measurement	Determine exhaust loss						PM				
20	Measurement	Add measurement log into the notes						PM				
21	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, HUMIDIFIERS - 9
APM Object	HVAC.HMD
APM EC	AMZ.HVAC.HMD.GRP
BBM Handbook Title	Humidifier
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	Hygiene certification required in some countries (e.g. VDI 6022)	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.WATER.COOLINGTOWERS			**Assets included in this PM:**	HUMIDIFIER UNIT	**Schedule With:**	HVAC.RTU HVAC.AHU		

Description of System / Technology (According to BBM Handbook)

A device to add moisture to air or gases. The device must be standalone, not internal nor auxiliary to another technology (ie :RTU).

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed system available & complete						PM		PM		
2	Humidifier	Check for correct function of all safety & additional shut down devices					SC	PM		PM		
3	Humidifier	Carry out a functional check of the humidifier (incl. control valves & moisture limiter)			SC		SC	PM		PM		
4	Humidifier	Check all components & surfaces for damage, deposit & corrosion						PM		PM		
5	Humidifier	Check all pipes, hoses & atomizer nozzles for deposits and damage			SC		SC	PM		PM		
6	Humidifier	Check the pump for correct function if installed					SC	PM		PM		
7	Humidifier	Check the function of the blow-down device					SC	PM		PM		
8	Humidifier	Check conductivity-critical cell for function			SC		SC	PM		PM		
9	Humidifier	Check the function of the sterilization system if installed						PM		PM		
10	Humidifier	Check for precipitation in the humidification chamber			SC		SC	PM		PM		
11	Humidifier	Check steam lance for deposits					SC	PM		PM		
12	Humidifier	Ensure that microbiological tests are carried out according to local requirements					SC	PM		PM		
13	Final Check	Check the O&M manual and carry out additional required tasks						PM		PM		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM, moved these tasks from the HVAC.AHU PM according to the last OCB updates. Added "forecast with".ç

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, AIR ROOFTOP UNITS-OUTDOOR - 9
APM Object	HVAC.RTU
APM EC	AMZ.HVAC.RTU.GRP
BBM Handbook Title	Air Rooftop Units (RTUs)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	Hygiene certification required in some countries (e.g. VDI 6022)	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.INDOOR CT.HVAC.12KW CT.HVAC.FGAS			**Assets included in this PM:**	ROOFTOP UNIT OUTDOOR	**Schedule With:**	HVAC.HMD HVAC.BLR (if installed)		

Description of System / Technology (According to BBM Handbook)

Roof Top Units (or RTUs) are a packaged unit that is a typical HVAC system type seen across Amazon FC's. RTUs contain all the components needed to provide conditioned air in one concise unit with a single unit being able to provide comfort cooling, heating, supply of an adjustable volume of fresh air, as well as free cooling.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: the yearly PPM should be planned before the summer season starts.
Refrigerant part -> Ensure that leakage and any other requirements according to F Gas Regulation are followed

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed system available & complete						PM				
2	Controller	Is the unit in operation & no alarms indicated - check unit control cabinet					PM					
3	Controller	Are any settings in manual mode -clarify the reason & set back to automatic mode										
4	Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM		PM		
5	Control cabinet	Check circuit diagrams for completion						PM		PM		
6	Control cabinet	If anything is missing or unclear in the circuit diagrams create a WO						PM		PM		
7	Control cabinet	Are all cables properly routed						PM		PM		
8	Control cabinet	Are all cables, terminal blocks & devices properly labeled or marked						PM		PM		
9	Control cabinet	Test all safety relevant switches						PM		PM		
10	Control cabinet	Were any obvious changes made (e.g. rewiring, hanging cables)						PM		PM		
11	Control cabinet	Visual check for the protection against direct contact with live part						PM		PM		
12	Control cabinet	Tight cable connections in the control cabinets & main supply connection boxes						PM		PM		
13	Control cabinet	Are all metal parts connected to the protection earth (ground)						PM		PM		
14	Control cabinet	Replace the air filters of the cabinet & check operation of cooling fan						PM		PM		
15	Control cabinet	Are all contacts of the compressor relais colsing & opening properly						PM		PM		
16	RTU outside check	Is the unit freely accessible & maintainable			SC	SC	PM	PM		PM		
17	RTU outside check	Is the unit in operation & no alarms indicated - check unit control cabinet			SC	SC	PM	PM		PM		
18	RTU outside check	Check unit air intakes & outlets for corrosion & damage, contamination & condensation			SC	SC	PM	PM		PM		
19	RTU outside check	Is there any unusual noise or vibration that could be caused by a faulty unit component			SC	SC	PM	PM		PM		
20	RTU outside check	Are there any visual damage, missing- or loose components at the unit			SC	SC	PM	PM		PM		
21	RTU outside check	Is water dropping out of the unit			SC	SC	PM	PM		PM		
22	RTU outside check	Check of the drain & drain trap (e.g. ball siphon) connected to the unit, chek for correct function & damage			SC	SC	PM	PM		PM		
23	Air Handling Part filter	Check filters for unacceptable contamination, damage, leaks (can the air bypass the filter medium?)			SC	SC	PM	PM		PM		
24	Air Handling Part filter	Measure differential pressure of all filter stages by using adequate tools			SC	SC	PM	PM		PM		
25	Air Handling Part filter	List the differential pressures in the notes			SC	SC	PM	PM		PM		
26	Air Handling Part filter	Schedule filter change when 80% of the capacity is reached			SC	SC	PM	PM		PM		
27	Air Handling Part filter	(An increased filter change is ok due to environmental impact)						PM		PM		
28	Air Handling Part filter	In the notes, please enter the number of filter changes per filter stage within the year						PM		PM		
29	Air Handling Part Fan	Change belts and check pulleys at belt driven fans						PM		PM		
30	Air Handling Part Hygiene & damages	Check droplet eliminator and tray for contamination e.g. mold, corrosion & damage				SC	PM	PM		PM		
31	Air Handling Part Hygiene & damages	Check cooling coil & condensate tray for contamination, corrosion & damage				SC	PM	PM		PM		
32	Air Handling Part Hygiene & damages	Clean unit air intakes and outlets						PM		PM		
33	Air Handling Part Hygiene & damages	Clean droplet eliminator & tray and check for contamination e.g. mold, corrosion & damage						PM		PM		
34	Air Handling Part Hygiene & damages	Clean cooling- & heating coil, as well as condensate tray using professional cleaning materials						PM		PM		
35	Air Handling Part Hygiene & damages	Check for contamination, corrosion & damage						PM		PM		

36	Air Handling Part Hygiene & damages	Clean fans & impeller and check for contamination, corrosion & damage						PM		PM			
37	Air Handling Part Hygiene & damages	Clean Chamber surfaces inside the unit and check for contamination, corrosion & damage						PM		PM			
38	Air Handling Part Hygiene & damages	Visual check of heat recovery for contamination, corrosion & damage					PM	PM		PM			
39	Air Handling Part Hygiene & damages	Visual check of heating coil for contamination, corrosion & damage					PM	PM		PM			
40	Air Handling Part Hygiene & damages	Visual check of silencers for contamination, corrosion & damage						PM		PM			
41	Air Handling Part Heat exchange	Functional check of frost protection thermostat						PM		PM			
42	Air Handling Part Heat exchange	Check the electrical heater for contamination, corrosion & damage						PM		PM			
43	Air Handling Part Heat exchange	Check the electrical heater according to local electrical regulations						PM		PM			
44	Air Handling Part Heat exchange	Check directly heated heat exchanger for tightness						PM		PM			
45	Air Handling Part Heat exchange	Vacuum all remaining heat exchanger carefully						PM		PM			
46	Air Handling Part Heat exchange	Check of reheater & cooler installed in the duct system for contamination, corrosion & damage						PM		PM			
47	Air Handling Part Heat exchange	Change filter of reheater & cooler installed in the duct system						PM		PM			
48	Air Handling Part Heat exchange	Measure differential pressure of all heat exchanger, compare with design and schedule professional cleaning if differential pressure is 30% higher than designed -> use professional tool								PM			
49	Air Handling Part Heat Recoery wheel	check the heat recovery wheel for correct functionality & for damage						PM		PM			
50	Air Handling Part duct system	Check air outlets & intakes of the duct system for debris, contamination, corrosion & damage						PM		PM			
51	Air Handling Part duct system	Choose 5 locations and add the locations into the notes Check inner duct system checks for contamination, corrosion, condensation & dirt						PM		PM			
52	Air Handling Part duct system	Check Textile air hose for damage, contamination & dirt						PM		PM			
53	Air Handling Part duct system	Schedule exchange or washing of the textile air hose if necessary						PM		PM			
54	Air Handling Part duct system	Underground components - check for contamination, corrosion & dirt deposit inside of the duct						PM		PM			
55	Air Handling Part Measurements	Measure the power consumption of the Fans in full speed with open dampers						PM		PM			
56	Air Handling Part Measurements	Add the values into the notes indicating the fans & compare to design specifications of the fan						PM		PM			
57	Air Handling Part Measurements	Measure the main discharge & return air volume flow - add airflow and position into the notes						PM		PM			
58	Air Handling Part Measurements	Compare measured airflow with design specification						PM		PM			
59	Air Handling Part Measurements	Measure the main discharge & return air temperature						PM		PM			
60	Air Handling Part Measurements	Compare measured temperature with value in the BMS, add temperature and create a FWO under BMS in case of deviation						PM		PM			
61	Refrigerant Part outside check	Is there any unusual noise or vibration that could be caused by compressors or condenser fans					PM	PM		PM			
62	Refrigerant Part outside check	Is the condenser coil free from dirt, damage & corrosion Schedule cleaning if airflow through coil is impaired			SC	SC	PM	PM		PM			
63	Refrigerant Part outside check	Are there any visual damage, missing- or loose components or corrosion at the unit					PM	PM		PM			
64	Refrigerant Part outside check	Is there any deposit in the drip tray (system fluid)					PM	PM		PM			
65	Refrigerant Part outside check	Is there oil deposit visible at the connections of the pipe system					PM	PM		PM			
66	Refrigerant Part outside check	Is the pipe insulation free from damage					PM	PM		PM			
67	Refrigerant Part Refrigerant leakage	Is an appropriate record for the refill of refrigerant physically available						PM		PM			
68	Refrigerant Part Refrigerant leakage	Add to notes the refill of refrigerant during the last year in KG (year in maintenance interval, not calendar year)						PM		PM			
69	Refrigerant Part Refrigerant leakage	Add to notes details of reasaon for refrigerant refill						PM		PM			
70	Refrigerant Part functional cleaning	Clean condenser coil with state-of-the-art technology (professional)						PM		PM			
71	Refrigerant Part functional cleaning	Clean condenser fan blades (& housing in case of dirt deposit)						PM		PM			
72	Refrigerant Part functional cleaning	Carry out a functional cleaning of all reachable components						PM		PM			
73	Refrigerant Part Measurements	Connect the refrigerant manometer & temperature sensors (always compare with controller data)						PM		PM			
74	Refrigerant Part Measurements	Are the refrigeration pressures and refrigerant temperatures correct						PM		PM			
75	Refrigerant Part Measurements	Is the expansion valve working properly & superheat OK						PM		PM			
76	Refrigerant Part Measurements	Is the undercooling temperature ok						PM		PM			
77	Refrigerant Part Measurements	Are the condenser & evaporator temperatures ok						PM		PM			
78	Refrigerant Part Measurements	Measure the power consumption of the compressors while operating on 100%Compare the power consumption with the manufacturer specification - react in case of deviation						PM		PM			
79	Refrigerant Part Measurements	Measure the power consumption of the condenser fans while operating on 100% Compare the power consumption with the manufacturer specification - react in case of deviation						PM		PM			
80	Refrigerant Part Measurements	Add the operational hours of all compressors into the notes						PM		PM			
81	Refrigerant Part Measurements	Identify & eliminate the root cause if there are big differences in operational hours						PM		PM			
82	Refrigerant Part Measurements	Are the compressors switched in the correct order						PM		PM			
83	Refrigerant Part Measurements	Measure the oil pressure & adjust if required						PM		PM			
84	Refrigerant Part Measurements	Is the oil temperature/presuure before & after refrigerant filter ok						PM		PM			
85	Refrigerant Part Measurements	Is the compressor oil level ok						PM		PM			
86	Refrigerant Part Measurements	Conduct oil analyses & schedule actions if required						PM		PM			
87	Refrigerant Part Compressor & Safety	Does the low-pressure switch work properly						PM		PM			
88	Refrigerant Part Compressor & Safety	Does the high-pressure switch work properly						PM		PM			
89	Refrigerant Part Compressor & Safety	Simulate safety switches of the system (e.g. thermostats, timers, etc.)						PM		PM			
90	Refrigerant Part Compressor & Safety	Is the crankcase heater working properly (attached to compressor)						PM		PM			
91	Refrigerant Part Compressor & Safety	Is the oil separator working properly						PM		PM			
92	Refrigerant Part Compressor & Safety	Check if there is humidity in the refrigeration system						PM		PM			
93	Refrigerant Part Compressor & Safety	Check refrigerant flow through show glass						PM		PM			
94	Refrigerant Part Compressor & Safety	Does the condensate tub heater work properly						PM		PM			
95	Refrigerant Part Compressor & Safety	Check correct funcitonlity of coil defrost						PM		PM			
96	Refrigerant Part Compressor & Safety	Screw Compressor - return valve check						PM		PM			

97	Refrigerant Part Compressor & Safety	Lubricate all moving parts and bearings if reachable						PM		PM		
98	Final Check	Check the O&M manual and carry out additional required tasks						PM		PM		

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Moved "Humidifier tasks" to HVAC.HMD PM.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, SUPPLY FAN UNITS - 9
APM Object	HVAC.SUP
APM EC	AMZ.HVAC.FAN.GRP
BBM Handbook Title	Supply Fans
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	NO	**Pricing template Position:**	9	**Related CT Areas:**	CT.AIR.INDOOR	**Assets included in this PM:**	SUPPLY FANS	**Schedule With:**	-				

Description of System / Technology (According to BBM Handbook)

Ceiling fans, with a minimum blade diameter of 4 feet/1.5 meters, circulate the air within the building space. System includes High Volume, Low Speed (HVLS) are considered as supply fans.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Electrical Panel	Check whether an alarm is dispalyed If applicable					SC	PM				
2	Visual check	Visual check from the ground for visible damage at the fan (e.g. loose parts)					SC	PM				
3	Visual check	Visual check from the ground wether the fan is working properly					SC	PM				
4	Visual check	Are there any unusual noise of the bearing, motor, blades or other Test while in operation						PM				
5	Visual check	Check the fan for unbalance Test while in operation						PM				
6	Visual check	Check whether the electrical wires/cables are free from damage and fixed properly						PM				
7	Visual check	Check whether the fan is mounted correctly/firmly Tighten as required according to manufacturer guideline						PM				
8	Visual check	Check whether the safety cable is properly secured/attached to prevent the fan from falling						PM				
9	Visual check	Check whether the fan blades are properly attached Tighten as required according to manufacturer guideline						PM				
10	Visual check	Inspect motor/gearbox for oil leaks If present consult manufacturer						PM				
11	Functional cleaning	Clean fan blades to maintain functionality						PM				
12	Measurement	Measure power consumption & compare to manufacturer specification If possible & on the ground						PM				
13	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	HVAC SYSTEMS, WATER HEATED SYSTEM - 9
APM Object	HVAC.WTR
APM EC	AMZ.HVAC.WTR.GRP
BBM Handbook Title	Water Heated System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	Trained Plumber and certified electrician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	9	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	WATER HEATED UNIT	**Schedule With:**	HVAC.BLR HVAC.GH		

Description of System / Technology (According to BBM Handbook)

A hot water heating system recirculates heated water through a system of pipes to radiators or air handler units, which then release the heat to the surrounding air. The water is usually heated by a boiler, which burns a fuel such as natural gas or oil to generate heat.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The yearly PPM should be carried out before the start of the heating season (winter)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the heating system complete & are there drawings on the wall						PM				
2	Leakage check	Are there any visible water leakages at the heating water system						PM				
3	Unit check	Are technical installations damaged or loose (incl. cables connected to equipment)						PM				
4	Unit check	Are there any damage at pipe or equipment insulation (pipes, buffer, valves, etc.)						PM				
5	Hygiene & Safety	Is the drinking water separation working properly, free from damage & corrosion						PM				
6	Hygiene & Safety	Do the safety devices work as required (e.g. pressure relief valve)						PM				
7	Hygiene & Safety	Is the expansion tank function as intended						PM				
8	Hygiene & Safety	Ensure all valves to expansion are open & secured						PM				
9	Functional cleaning	Clean system filters & check for damage						PM				
10	Functional cleaning	Clean all fittings & other equipment to maintain their functionality						PM				
11	Measurement	Are there any damage at the thermostats and pressure manometer						PM				
12	Measurement	Are the values showing any indication of incorrect water flow						PM				
13	Measurements	Measure the power consumption of the pumps while operating on 100% Compare the power consumption with the manufacturer specification - react in case of deviation						PM				
14	System devices	Are the pumps working properly, are free from damage & corrosion						PM				
15	System devices	Are the motor driven valves working properly						PM				
16	System devices	Check balancing valves for correct function (Strangregulierung)						PM				
17	System devices	Test all manual control devices for correct function						PM				
18	System devices	Lubricate the spindle of all control fittings						PM				
19	System devices	Are the filling, emptying and sludge removal devices working correctly						PM				
20	System devices	Is the system pressure according to design (high enough to supply the building)						PM				
21	System devices	Check all temperatures for abnormalities which indicates a clogged heat exchanger, incorrect operating pumps, valve, etc.						PM				
22	System devices	Are automatic air vents working properly & are free from damage & corrosion						PM				
23	System devices	Manual air vents - release air at the possible locations of air bubbles in the system						PM				
24	System devices	Are expansion joints connected tightly & are free from damage						PM				
25	System devices	Check sacrificial anode (if installed)						PM				
26	System devices	Check buffer for damage & correct water level (no air, or damaged membrane)						PM				
27	System devices	Check correct function of electrical heaters						PM				
28	Electrical	Is the pipe trace heating working properly (if installed)						PM				
29	Radiator	Are the radiators working correctly & are free from damage & corrosion						PM				
30	Radiator	Are there obvious air bubbles in the radiator						PM				
31	Air curtain water supplied	Are all safety devices functioning correctly										
32	Air curtain water supplied	All components free for damage and live parts not accesible										
33	Air curtain water supplied	Is the unit functioning correctly										
34	Air curtain water supplied	Is there any unusual noise or vibration										
35	Air curtain water supplied	Is the unit leakage free										

36	Air curtain water supplied	Are the heating water supply valves functioning correctly											
37	Air curtain water supplied	Is the hot water supply valve adjusted correctly and free water flow possible to supply the heat exchanger properly											
38	Air curtain water supplied	Clean reusable filter or exchange disposable filter											
39	Controller & Control cabinet	Is the unit in operation & no alarms indicated - check unit control cabinet						PM					
40	Controller & Control cabinet	Are any settings in manual mode -clarify the reason & set back to automatic mode						PM					
41	Controller & Control cabinet	Did any circuit breaker trip - identify & eliminate the root cause or create a WO						PM					
42	Controller & Control cabinet	Visual check of the control cabinets inside & outside for damage, debris & missing components						PM					
43	Controller & Control cabinet	Check circuit diagrams for completion						PM					
44	Controller & Control cabinet	If anything is missing or unclear in the circuit diagrams create a WO						PM					
45	Controller & Control cabinet	Are all cables properly routed						PM					
46	Controller & Control cabinet	Are all cables, terminal blocks & devices properly labelled or marked						PM					
47	Controller & Control cabinet	Test all safety relevant switches						PM					
48	Controller & Control cabinet	Were any obvious changes made (e.g. rewiring, hanging cables)						PM					
49	Controller & Control cabinet	Visual check for the protection against direct contact with live part						PM					
50	Controller & Control cabinet	Tight cable connections in the control cabinets & main supply connection boxes						PM					
51	Controller & Control cabinet	Are all metal parts connected to the protection earth (ground)						PM					
52	Pumps	Can you identify unsusual noise or vibration of operating pumps						PM					
53	Pumps	Can you identify unsusual noise or vibration of operating pumps						PM					
54	System devices	Maintain all electrical heating devices according to O&M & local regulations (e.g. DIN VDE)						PM					
55	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Aligned the APM Object according to the last OCB updates.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LADDERS, FIXED LADDERS - 14
APM Object	LADDERS.FIXED
APM EC	AMZ.LAD.FIX
BBM Handbook Title	Fixed Ladders
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	14	**Related CT Areas:**	CT.HEIGHT.LADDER.F			**Assets included in this PM:**	FIXED LADDER	**Schedule With:**	LADDERS.MOBILE		

Description of System / Technology (According to BBM Handbook)

All sites with fixed ladders installed serving for BBM o MHE equipment.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Policy	Please refer to the Policy and complete required tasks accordingly				SC						
2	Policy	https://policy.a2z.com/docs/31256/publication				SC						

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Changed PM to follow Policy

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LADDERS, MOBILE LADDERS - 14
APM Object	LADDERS.MOBILE
APM EC	AMZ.LAD.MOB
BBM Handbook Title	Mobile Ladders
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	14	**Related CT Areas:**	CT.HEIGHT.LADDER.M			**Assets included in this PM:**	MOBILE LADDER	**Schedule With:**	LADDERS.FIXED		

Description of System / Technology (According to BBM Handbook)

All sites with mobile ladders serving for BBM o MHE equipment.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Policy	Please refer to the Policy and complete required tasks accordingly				SC						
2	Policy	https://policy.a2z.com/docs/31256/publication				SC						

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Changed PM to follow Policy

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIFTS, GOODS LIFTS - 6
APM Object	LIFTS.GOODS
APM EC	AMZ.LIFTS.GOODS
BBM Handbook Title	Goods Lifts
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	6	**Related CT Areas:**	CT.LIFT.GOODS			**Assets included in this PM:**	FREIGHT ELEVATOR	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A goods lift is a machine to lift goods vertically in a safe way. Persons are not allowed on or in the lift, except for for loading and unloading purposes.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note: This PM includes Rope hoist & hydraulic hoists (elevators/lifts)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Alarms	Are there any alarms indicated -> if yes identify & eliminate the root cause or create a WO			PM			PM				
2	Documentation	Are the circuit diagrams and relevant technical documentation available and complete			PM			PM				
3	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
5	Safety	Are disconnecting devices lockable in the safe position (LOTO)			PM			PM				
6	Safety	Are safety markings, notices and pictograms present and legible			PM			PM				
7	Safety	Are all doors to the machinery & shaft rooms locked			PM			PM				
8	Safety	Are emergency release opening accessible on all landing doors			PM			PM				
9	Safety	Doors open again when the light barrier is interrupted			PM			PM				
10	Safety	Emergency call device is functioning correctly			PM			PM				
11	Safety	Is appropriate firefighting equipment available & free from damage						PM				
12	Safety	Check correct function of all other safety related components like overload stop, etc.			PM			PM				
13	Control	The level selection buttons are free from damage and functioning correctly						PM				
14	Doors	Doors are moving, opening & closing without unusual noise			PM			PM				
15	Doors	Door tracks are free from damage and clean -> clean if required			PM			PM				
16	Doors	Check correct function of end- & safety switches of roller, sliding & swing doors			PM			PM				
17	Doors	Door leaves & roller shutter elements are free from damage & corrosion			PM			PM				
18	Doors	Doors can`t be opened before car reached end position of a level			PM			PM				
19	Doors	Door stop switch/reverse switch is functioning correctly			PM			PM				
20	Elevator car	The car floor is on the same level as the floor of the building (check each level)			PM			PM				
21	Elevator car	Is the light inside the car & in front of the elevator at each level sufficient & free from damage						PM				
22	Elevator car	All surfaces are free from damage and corrosion (walls, ceiling & floor)			PM			PM				
23	Elevator car	Handrail, ramp protection, etc. are correctly fixed & free from damage			PM			PM				
24	Elevator car	Are there any unusual noises, vibrations or movements when elevator is operating			PM			PM				
25	Engine room & machinery shaft	Are the rooms freely accessible						PM				
26	Engine room & machinery shaft	Is the light inside the rooms & around technical components sufficient & free from damage						PM				
27	Engine room & machinery shaft	Remove all unnecessary flammable goods out of the rooms						PM				
28	Engine room & machinery shaft	Are components damaged or loose (e.g. cable trays, MCP, fire extinguisher)						PM				
29	Engine room & machinery shaft	Is the emergency release key/tool available						PM				
30	Engine room & machinery shaft	Is the ventilation in the rooms sufficient (humidity & temperature)						PM				
31	Engine room & machinery shaft	Are there any leakages on hydraulic systems						PM				
32	Engine room & machinery shaft	Are there any visible damage at the hoist including ropes						PM				
33	Engine room & machinery shaft	Is the brake functioning properly						PM				
34	Engine room & machinery shaft	Grease all greasing points to maintain a reliable function						PM				
35	Engine room & machinery shaft	Test the hydraulic oil and schedule an exchange if required						PM				
36	Engine room & machinery shaft	Check mechanical breaks						PM				

37	Engine room & machinery shaft	Check gap of the lift and clean it						PM					
38	Electrical components	Is the air filter of the electrical panel/cabinet clean and the cooling fan functioning correctly. Please clean or change if necessary						PM					
39	Electrical components	Are all cables properly routed						PM					
40	Electrical components	Are all metal parts connected to the protection earth (ground)						PM					
41	Electrical components	Is the ground connection to the building ground as designed?						PM					
42	Electrical components	Did any circuit breaker trip -> if yes identify the root cause						PM					
43	Measurement	Measure the electrical current flow of hoist & hydraulic motor						PM					
44	Measurement	Compare to manufacturer specifications						PM					
45	Measurement	Please add the running hours into the notes						PM					
46	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause immediately						PM					
47	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan						PM					
48	Functional cleaning	Carry out a functional cleaning of all components						PM					
49	Final Check	Calibrate overload sensors						PM					
50	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removing Related wrong CT Area: CT.LIFT.ESCALATOR. Changed the APM Description according to the BBM Handbook.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIFTS, PASSENGER LIFTS - 6
APM Object	LIFTS.PASSENGER
APM EC	AMZ.LIFTS.PASS
BBM Handbook Title	Passenger Lifts
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	YES	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	Yes	**Pricing template Position:**	6	**Related CT Areas:**	CT.LIFT.PASSENGER			**Assets included in this PM:**	PASSENGER LIFT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A passenger lift is a type of lift that is designed to take passengers up and down a vertical lift shaft. The lift cab, emergency communication and lighting are also included.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This PM includes Rope hoist & hydraulic hoists (elevators/lifts)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Alarms	Are there any alarms indicated -> if yes identify & eliminate the root cause or create a WO			PM			PM				
2	Documentation	Are the circuit diagrams and relevant technical documentation available and complete			PM			PM				
3	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation			PM			PM				
5	Safety	Are disconnecting devices lockable in the safe position (LOTO)			PM			PM				
6	Safety	Are safety markings, notices and pictograms present and legible			PM			PM				
7	Safety	Are all doors to the machinery & shaft rooms locked			PM			PM				
8	Safety	Are emergency release opening accessible on all landing doors			PM			PM				
9	Safety	Doors open again when the light barrier is interrupted			PM			PM				
10	Safety	Emergency call device is functioning correctly			PM			PM				
11	Safety	Is appropriate firefighting equipment available & free from damage						PM				
12	Safety	Check correct function of all other safety related switches/ measures like overload stop, etc.			PM			PM				
13	Control	The level selection buttons are free from damage and functioning correctly			PM			PM				
14	Doors	Doors are moving without unusual noise			PM			PM				
15	Doors	Door tracks are free from damage and clean -> clean if required			PM			PM				
16	Doors	Door leaves are free from damage & corrosion			PM			PM				
17	Doors	Doors can`t be opened before car reached end position of a level			PM			PM				
18	Doors	Door stop switch/reverse switch is functioning correctly			PM			PM				
19	Elevator car	The car floor is on the same level as the floor of the building (check each level)			PM			PM				
20	Elevator car	Is the light inside the car & in front of the elevator at each level sufficient & free from damage			PM			PM				
21	Elevator car	All surfaces are free from damage and corrosion (walls, ceiling & floor)			PM			PM				
22	Elevator car	Handrail, ramp protection, etc. are correctly fixed & free from damage			PM			PM				
23	Elevator car	Are there any unusual noises, vibrations or movements when elevator is operating			PM			PM				
24	Engine room & machinery shaft	Are the rooms freely accessible						PM				
25	Engine room & machinery shaft	Is the light inside the rooms & around technical components sufficient & free from damage						PM				
26	Engine room & machinery shaft	Remove all unnecessary flammable goods out of the rooms						PM				
27	Engine room & machinery shaft	Are components damaged or loose (e.g. cable trays, MCP, fire extinguisher)						PM				
28	Engine room & machinery shaft	Is the emergency release key/tool available						PM				
29	Engine room & machinery shaft	Is the ventilation in the rooms sufficient (humidity & temperature)						PM				
30	Engine room & machinery shaft	Are there any leakages on hydraulic systems						PM				
31	Engine room & machinery shaft	Are there any visible damage at the hoist						PM				
32	Engine room & machinery shaft	Is the brake functioning properly						PM				
33	Engine room & machinery shaft	Grease all greasing points to maintain a reliable function						PM				
34	Engine room & machinery shaft	Test the hydraulic oil and schedule an exchange if required						PM				
35	Electrical components	Is the air filter of the electrical panel/cabinet clean and the cooling fan functioning correctly. Please clean or change if necessary						PM				
36	Electrical components	Are all cables properly routed						PM				

37	Electrical components	Are all metal parts connected to the protection earth (ground)						PM					
38	Electrical components	Is the ground connection to the building ground as designed?						PM					
39	Electrical components	Did any circuit breaker trip -> if yes identify the root cause						PM					
40	Measurement	Measure the electrical current flow of hoist & hydraulic motor						PM					
41	Measurement	Compare to manufacturer specifications						PM					
42	Measurement	Please add the running hours into the notes						PM					
43	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause immediately						PM					
44	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan						PM					
45	Functional cleaning	Carry out a functional cleaning of all components						PM					
46	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM description as shows the BBM Handbook.Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIFTS, VEHICLE TO GROUND LIFTS - 12
APM Object	LIFTS.V2G
APM EC	AMZ.LIFTS.V2G
BBM Handbook Title	Vehicle to Ground Lift (V2G)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Aug-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	12	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	VEHICLE TO GROUND LIFT	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

Hydraulic lift to support the loading of various vehicle from ground level to double deck lorries.

Additional Information

Hydraulic lift to support the loading of various vehicle from ground level to double deck lorries.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the technical documentation & blueprints of installed equipment available & complete						PM				
2	General	Are the technical documentation & electrical drawings complete						PM				
3	General	Are there any visual damage, missing / loose components or corrosion				SC	PM	PM				
4	Safety	Are all safety switches & other safety components functioning correctly					PM	PM				
5	Safety	Inspect all safety edges and light curtains to ensure they are functioning correctly and free from damage					PM	PM				
6	Safety	Ensure all warning and operational notices are correctly placed and accurate					PM	PM				
7	Safety	Verify that all safe working load signs are correctly placed and display the accurate information					PM	PM				
8	Safety	Check if artificial lighting levels are sufficient and meet required standards					PM	PM				
9	Safety	Ensure there are no sharp edges present that could pose a safety risk					PM	PM				
10	Electrical	Review the main control panel displays and check the fault logs for any errors or issues that need to be addressed				SC	PM	PM				
11	Electrical	Verify the equipment is functioning correctly and in a safe manner				SC	PM	PM				
12	Electrical	Check the settings of all motor overloaddevices, and inspect motor contactors to ensure tightened as per requirements						PM				
13	Electrical	Inspect cables for correct installation and check for any signs of damage						PM				
14	Electrical	Ensure that no live parts are exposed or accessible						PM				
15	Electrical	Verify that all metal parts are properly earthed to ensure safety and compliance with regulations						PM				
16	Electrical	Check all indicators and replace any lamps if necessary						PM				
17	Electrical	Verify that all platform/pod lights are functioning properly						PM				
18	Electrical	Inspect switches and sensors for proper function and overall condition						PM				
19	Electrical	Inspect the condition of all electrical enclosures and panels to ensure they are intact, secure, and free from damage or corrosion						PM				
20	Electrical	Verify the operation of traffic light systems and ensure that all displays are functioning correctly.					PM	PM				
21	Electrical	Inspect the condition of the tail lift transformer system to ensure it is functioning properly and free from any signs of						PM				
22	Electrical	Change air filter of the panel and check cooling fan for correct function and damage						PM				
23	Hydraulic	Inspect all hoses and pipework for any signs of wear, leaks, or damage, ensuring they are securely connected and in good condition						PM				
24	Hydraulic	Inspect all rams for any signs of damage, leaks, or wear, ensuring they are in good working condition						PM				
25	Hydraulic	Inspect valves, seals, and manifolds for proper operation, checking for any signs of wear, leaks, or damage						PM				
26	Hydraulic	Verify the tightness of all hydraulic connections to ensure they are secure and free from leaks						PM				
27	Hydraulic	Inspect the power-pack and motor fixings to ensure they are secure and free from any signs of wear or damage						PM				
28	Hydraulic	Check the hydraulic pump for proper function and inspect for any signs of damage						PM				
29	Hydraulic	Ensure all adjusters are properly locked off and securely tightened						PM				
30	Hydraulic	Verify that hydraulic fluid levels are within the recommended range and top up if necessary						PM				
31	Hydraulic	Check the efficiency of the oil filter and replace it if necessary						PM				
32	Mechanical	Check all grounding straps and cables for wear, corrosion, or damage					PM	PM				
33	Mechanical	Verify that all components of the grounding system, including clamps, bolts, and connectors, are free from signs of wear, loosening, or corrosion						PM				
34	Mechanical	Lubricate & grease all moving parts (follow manufacturer guideline)						PM				
35	Mechanical	Checkt all moving parts for signs of wear or damage						PM				

36	Mechanical	Check Pivot/Hinge Pins for signs of wear or damage						PM					
37	Mechanical	Verify correct operation of "rope failure devices"						PM					
38	Mechanical	Inspect ropes and chains for any signs of wear, and apply lubrication as needed						PM					
39	Mechanical	Inspect runners and rollers for any signs of wear or damage						PM					
40	Mechanical	Inspect pulleys and bearings for wear and overall condition						PM					
41	Mechanical	Inspect all welds and fixings for any signs of damage or corrosion						PM					
42	Mechanical	Check the condition of platform securing bolts and welds for any signs of wear, damage, or corrosion						PM					
43	Mechanical	Verify the alignment of the platform to ensure it is properly positioned and level						PM					
44	Mechanical	Inspect the platform gates for structural integrity and ensure they operate correctly						PM					
45	Mechanical	Inspect adjustable dock plates and ramps for proper tightness and ensure they are level						PM					
46	Mechanical	Verify that the load house is securely fixed to the ground						PM					
47	Mechanical	Ensure that the load house lid is securely fastened to the base frame						PM					
48	Mechanical	Confirm that the dock level is within acceptable tolerance, with a variation of no more than +/-10mm						PM					
49	Mechanical	Inspect the rubber/soft buffers for their condition and ensure that the mountings are secure						PM					
50	Mechanical	Inspect roller/mesh curtains for their condition and verify that they are properly in place						PM					
51	Mechanical	Check the condition of the wheel guides and ensure that all bolts are securely fastened						PM					
52	Mechanical	Inspect safety ladders for structural integrity, signs of wear, and secure attachment						PM					
53	Mechanical	Verify the proper operation of the safety locking system to ensure it functions correctly						PM					
54	Mechanical	Inspect the outer cladding/meshing for its condition and ensure that it is securely mounted						PM					
55	Mechanical	Check the operation and condition of the bridge plate to ensure it is functioning properly and is in good condition						PM					
56	Mechanical	Inspect the outer shutter door for proper operation and overall condition, ensuring it functions smoothly and is free from damage						PM					
57	Functional Cleaning	Clean the grounding points on both the vehicle and the ground connection to remove any dirt, debris, or oxidation that could impair the connection						PM					
58	Functional test	Verify that the operating time for the "up" and "down" functions is aligned with the manufacturer's guidelines						PM					
59	Functional test	Ensure that the hydraulic working pressure is within the manufacturer's recommended guidelines						PM					
60	Operating hours	Record the operating hours of the unit into the notes						PM					
61	Final Check	Check the O&M manual and carry out additional required tasks						PM					

Change Log

Aug 2024 - New PM on request from AGL RME field team

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIGHT, EXTERNAL - 11
APM Object	LIGHT.EXT
APM EC	AMZ.LIGHT.EXT
BBM Handbook Title	External Lighting
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.LIGHTING	**Assets included in this PM:**	EXTERNAL LIGHTS	**Schedule With:**	BLDG.EXT BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.BUSSHELTER BLDG.GATEBARRIER				

Description of System / Technology (According to BBM Handbook)

Lighting located on the buildings external as well as in the Yard, carpark and grounds.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Lighting	Perform a functional cleaning of the exterior lights & check lights for correct function & damage					SC	SC				
2	Controller	For sites with lighting control systems installed (EIB, KNX, etc.) Check the controller for alarms, damage & correct function by changing setpoints and checking reactions of the system						SC				
3	Controller	Is the documentation of the system available and complete						SC				
4	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIGHT, INTERNAL - 11
APM Object	LIGHT.INT
APM EC	AMZ.LIGHT.INT
BBM Handbook Title	Internal Lighting
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.LIGHTING	**Assets included in this PM:**	INTERNAL LIGHTS	**Schedule With:**	BLDG.INT BLDG.STRUCTURE BLDG.MEZZANINE				

Description of System / Technology (According to BBM Handbook)

Lighting located internally.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Lighting	Perform a site walk and check all lights for correct function and damage					SC	SC				
2	Lighting	Measure the illuminance in working areas & Emergency routes Compare to design or local requirements – usually performed by WHS						SC				
3	Lighting	Schedule a functional cleaning or other actions if required						SC				
4	Controller	For sites with lighting control systems installed (EIB, KNX, etc.) Check the controller for alarms, damage & correct function by changing setpoints and checking reactions of the system						SC				
5	Controller	Is the documentation of the system available and complete						SC				
6	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	LIGHT, SAFETY LIGHTING AND SIGNAGE - 10
APM Object	LIGHT.SAFETY
APM EC	AMZ.LIGHT.SAFETY
BBM Handbook Title	Safety Lighting and Signage
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.ELEC.EMERGENCYAC			**Assets included in this PM:**	SAFETY LIGHTING AND SIGNAGE	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Only central battery station - Is the room properly ventilated						PM				
2	General check	Are the components clean & free from debris -> carry out a functional cleaning if necessary						PM				
3	General check	Visual check of the equipment for damage & missing components (incl.lights & signages)			SC			PM				
4	General check	Identify & secure essential spare parts for reactive maintenance			SC			PM				
5	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
6	Safety	Test all safety relevant switches for correct function						PM				
7	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
8	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
9	Functional test	Carry out a flick test - simulate a power outage & check the system for correct function (ensure all emergency lighting turn on or stay illuminated)			SC			PM				
10	Functional test	Only for em. lights with local batteries - Check for alarms at the light/signage			SC			PM				
11	Thermographic scan	Perform thermographic scans of the electrical cabinet and central battery system -> Create a WO for over-temperature to determine the root cause immediately						PM				
12	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scans						PM				
13	Panel & electrical installation	Is the air filter & grid of the cooling inlets clean -> clean or change filter if necessary			SC			PM				
14	Panel & electrical installation	Are the cooling fans operating appropriately and doesn`t make any unusual noise			SC			PM				
15	Panel & electrical installation	Are there any alarms indicated -> if yes identify the root cause immediately			SC			PM				
16	Panel & electrical installation	Has a circuit breaker tripped -> if yes identify the root cause immediately			SC			PM				
17	Panel & electrical installation	Visual check of cable connections -> e.g., pinched insulation in the contact area						PM				
18	Panel & electrical installation	Visual check for the protection against direct contact with live parts						PM				
19	Panel & electrical installation	Have any obvious changes been made (e.g. rewiring, hanging cables)						PM				
20	Panel & electrical installation	Are all cables properly routed						PM				
21	Panel & electrical installation	Are all components properly labeled or marked						PM				
22	Panel & electrical installation	Are all components properly attached						PM				
23	Panel & electrical installation	Are all metal parts connected to the protection earth (ground)						PM				
24	Panel & electrical installation	Is the ground connection to the building ground as designed?						PM				
25	Panel & electrical installation	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
26	Battery & Charger	Only central battery station - Measure the voltage of each battery (disconnected) -> if necessary, plan for a replacement						PM				
27	Battery & Charger	Only central battery station -Measure the charging voltage and current before & after functional test -> Compare to design specification & plan component exchange in case of an issue						PM				
28	Battery & Charger	Only central battery station - Check the internal uninterruptable power supply of the unit for correct function						PM				
29	Battery & Charger	Only central battery station - Check the batteries for leakage or damage						PM				
30	Battery & Charger	Only central battery station - Check the fluid level of the batteries and top up if required						PM				
31	Functional cleaning	Carry out a functional cleaning if required						PM				
32	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, aligmment with CT. Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	STORAGE, HIGH RACKS - 14
APM Object	STOR.HRACK
APM EC	AMZ.HRACK.ZONE
BBM Handbook Title	High Racking
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	Operations
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	CT.WORK.STORAGE			**Assets included in this PM:**	HIGH RACKS ZONE P1A	**Schedule With:**	STOR.SHELV		

Description of System / Technology (According to BBM Handbook)

All sites with high racks installed - Racking dimensions: 10m(L) X 10m(H) x 1m or standard pallet depth(D)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documents	Is the documentation of the equipment available & complete						SC				
2	Frames	The frames does not show any deformation or other damage						SC				
3	Beam	The beams are free from damage						SC				
4	Rack supports	The rack support is upright, not deformed, not twisted & free from damage						SC				
5	Footplates	The footplates are all present and not deformed						SC				
6	Welds	Check the welds for cracks						SC				
7	Building floor	The floor of the building does not have tripping hazards, is level, anti-slip						SC				
8	Loads on the pallet	The loads do not exceed the maximum load. No deformation or deflection detectable						SC				
9	Position of the loading equipment	The load is secured from falling down and the loading equipment is placed in its fixed place.						SC				
10	Dimensions of the loading units	The dimensions correspond to those of the load plates.						SC				
11	Stability of the loading units	The loading units have all the necessary compartments for stabilization.						SC				
12	Attachment	All truss attachments and all required truss connections are in place.						SC				
13	Load tags	The load plates are attached in accordance with the regulations.						SC				
14	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	STORAGE, SHELVING - 14
APM Object	STOR.SHELV
APM EC	AMZ.SHELV
BBM Handbook Title	Picktower Shelving
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	CT.WORK.STORAGE			**Assets included in this PM:**	SHELVES	**Schedule With:**	STOR.HRACK		

Description of System / Technology (According to BBM Handbook)

Picktower Shelving - Shelve dimensions: 1m(L) X 1m(H) X 1m(D)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Is the documentation of the equipment available & complete						SC				
2	Building floor	he floor surrounding the shelves is free of tripping hazards						SC				
3	Shelf feet	Check the rack feet for collision protection, deformations and twists						SC				
4	Shelf feet	Ensure the shelf is securely anchored to the floor and all screws are tightened						SC				
5	Storage	The storage of the pallets/boxes must be checked for proper securing						SC				
6	Beam	The beams are free from damage						SC				
7	Weld	The welds for cracks and other damage						SC				
8	Load tags	Ensure the load plate and warning signs are properly attached in accordance with safety regulation						SC				
9	Final Check	Check the O&M manual and carry out additional required tasks						SC				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
Aug 2024 - Added task to check for anchoring based on learnings from RME field

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING WATER SUPPLY - 5
APM Object	WTR.SUPPLY
APM EC	AMZ.WS
BBM Handbook Title	Water System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	5	**Related CT Areas:**	CT.WATER.LEGIONELLA CT.WATER.COLDSERVICE CT.WATER.HOTSERVICE CT.WATER.LEAD CT.WATER.BACKFLOW			**Assets included in this PM:**	WATER SUPPLY PUMPS - COLD WATER SUPPLY TANK UNIT - WATER SUPPLY VALVES	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Water System

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: The tasks for pumps in this PM is designated to the water supply pumps (booster pumps)

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available and complete						PM				
2	Safety	Test all safety relevant switches						PM				
3	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
4	Attachments	Check if all components are properly fixed						PM				
5	Pumps & panel	Is there any damage or leakages at the pipes, insulation or pumps						PM				
6	Pumps & panel	Are there any unusual noises of the running pump						PM				
7	Pumps & panel	Measure power consumption of the pumps and compare to design						PM				
8	Pumps & panel	Are all cables properly routed						PM				
9	Pumps & panel	Are all cables, terminal blocks & devices properly labeled or marked						PM				
10	Pumps & panel	Are all metal parts of the unit connected to the protection earth (ground)						PM				
11	Pumps & panel	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
12	Pumps & panel	Visual check of cable connections such as pinched insulation in the contact area						PM				
13	Pumps & panel	Visual check for the protection against direct contact with live parts						PM				
14	Pumps & panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
15	Water filter	Backwash filter, if possible					PM	PM				
16	Water filter	Change filter inlet, if possible					PM	PM				
17	Water filter	In case of automatic filter backwash function, check for correct functionality						PM				
18	Softener unit	Check salt tablet level & top up salt tablets if necessary			SC			PM				
19	Softener unit	Measure the water hardness and adjust if necessary						PM				
20	Cold water tanks	Check if cold water tanks are free from damage			SC			PM				
21	Dosing & Chlorination Unit	Measure the water chlorine content in the water and adjust if necessary			SC			PM				
22	Valves & backflow preventer	Close the nearest supply valve in flow direction before the backflow preventer						PM				
23	Valves & backflow preventer	Open the maintenance opening on the supply site and release the water						PM				
24	Valves & backflow preventer	Check if there is not water flowing back from the building pipes						PM				
25	Valves & backflow preventer	If the water flow doesn`t stop means that the bp is defect and needs to be changed						PM				
26	Valves & backflow preventer	Close the maintenance opening & open the supply valve						PM				
27	Valves & backflow preventer	If there are no pressure gauges close to the bp, open the maintenance opening on the building site and check if the bp ensures a water flow into the building						PM				
28	Valves & backflow preventer	Check all water supply valves for correct functionalty & leakages						PM				
29	Final Check	Check the O&M manual of all installed components and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Merged the tasks from WTR.SUPPLY.VALV.BFP, Removed task regarding CE certification.

amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING WATER SUPPLY, DOMESTIC HOT WATER HEATERS - 9
APM Object	WTR.SUPPLY.HTR
APM EC	AMZ.WS.HTR.GRP
BBM Handbook Title	Domestic Water Heaters (Drinking water)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	9	**Related CT Areas:**	CT.WATER.HOTSERVICE			**Assets included in this PM:**	DOMESTIC HOT WATER UNIT	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

Domestic Hot Water (DHW) generators are generally gas direct fired units with the burner integrated in to the bottom of a water cylinder.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Note : Theis PM can be used for electrical domestic water heater and for warm trinking water stations supplied by a separate gas boiler

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General	Are the water treatment rooms accessible						PM				
2	General	Are there any visible water leakages at the system						PM				
3	General	Are technical installations damaged or loose (incl. cables connected to equipment)						PM				
4	General	Are there any damage at pipe or equipment insulation						PM				
5	General	Is the documentation of the hot drinking water treatment system complete & are there drawings on the wall						PM				
6	Controller	Is the unit in operation & no alarms indicated - unit controller or control cabinet						PM				
7	Measurement	Are there any damage at the thermometer or manometer (pressure)						PM				
8	Measurement	Measure the water temperature to verify the thermometer & value on control display						PM				
9	Unit check	Is the buffer tank free from damage & corrosion						PM				
10	Unit check	Is the electrical heater functioning correctly						PM				
11	Unit check	Is the softening system functioning correctly & free from damage						PM				
12	Unit check	Are the motor driven valves functioning correctly						PM				
13	Unit check	Are all manual control valves functioning correctly & are free from damage						PM				
14	Unit check	Check sacrificial anode (if installed)						PM				
15	Safety & hygiene	Are the pressure reducer and non-return valves functioning properly						PM				
16	Safety & hygiene	Is the filter backwash unit functioning correctly						PM				
17	Safety & hygiene	Is the water filter in a good condition						PM				
18	Safety & hygiene	Is the expansion vessel functioning correctly						PM				
19	Safety & hygiene	Do the safety devices work as required (e.g. pressure relief valve, group valve)						PM				
20	Safety & hygiene	Is the legionella program functioning correctly						PM				
21	Safety & hygiene	Is the circulation pump functioning correctly						PM				
22	Electrical	Maintain electrical elements components to local regulations (e.g. DIN VDE)						PM				
23	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

Error - Entry for specified object not found on change log