amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, BUS SHELTER - 14
APM Object	BLDG.BUSSHELTER
APM EC	AMZ.BLDG.BUSSHELTER
BBM Handbook Title	Bus Shelter
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	BUS SHELTER	**Schedule With:**	BLDG.EXTSURFACES BLDG.RAINCOLL BLDG.EXT BLDG.GATEBARRIER LIGHT.EXT		

Description of System / Technology (According to BBM Handbook)

Bus Shelter

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Cladding	Check if the cladding is free from damage & graffiti				SC						
2	Roof	Check if the roof is free from damage & leakage				SC						
3	Drainage	Check if the gutter & drainage pipes are free from damage, blockage & leakage				SC						
4	Lighting	Check if the lighting is working properly				SC						
5	Seats	Check if the seats are free from damage				SC						

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.