amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, DRINK WATER DISPENSERS - 5
APM Object	BLDG.DWDISP
APM EC	AMZ.BLDG.WTRDISP
BBM Handbook Title	Drinking Water Dispensers
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Yes	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	5	**Related CT Areas:**	CT.WATER.DRINKING CT.WATER.LEGIONELLA			**Assets included in this PM:**	DRINK WATER DISPENSERS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Drinking Water Dispensers.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Ensure spare parts like filter cartridges, aerator, etc. are always on stock to enable a smooth PM process.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete				PM						
2	Cover & functionality	Is the unit/cover free from damage				PM						
3	Cover & functionality	Test water dispenser for correct function				PM						
4	Cover & functionality	Test UV light for correct function (if installed)				PM						
5	Gas	Check the CO2 bottle with regard to pressure level (only for unit with sparkling water)				PM						
6	Gas	Check CO2 components for leaks (only for unit with sparkling water)				PM						
7	Gas	Ensure that the CO2 bottle instructions and warning signs are clearly visible, and verify that the correct bottle is in use. (only for unit with sparkling water)				PM						
8	Water	Check water supply hose/pipe for leaks or wear				PM						
9	Water	Check water pipes inside the unit for leaks or wear				PM						
10	Water	Check pumps and valves for correct function				PM						
11	Water	Change water outlet/aerator if applicable				PM						
12	Functional cleaning	Functional clean and test of the fan, compressor & heat exchanger				PM						
13	Functional cleaning	Carry out a functional test of unit drainage system				PM						
14	Functional cleaning	Cleaning of drip tray and base cabinet				PM						
15	Filter cartridge	Check filter cartridge for proper function and change if necessary (max change interval 6 month) -> Add a note in case of a filter change				PM						
16	Cooling	Renew water of the ice bank				PM						
17	Cooling	Check correct function of the ice bank circulation device (e.g., propeller)				PM						
18	Electrical components	Check all cables for signs of wear and exposed live parts, such as abrasion.				PM						
19	Hygiene	Disinfection of all water-carrying components according to instructions				PM						
20	Hygiene	Check water quality with test strips				PM						
21	Hygiene	Ensure testing for legionella and microbiological contamination are carried out according to local requirements				PM						
22	Final Check	Check the O&M manual & local rwuirements and carry out additional required tasks				PM						

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed "gas" in the component cell. Added tasks regarding cooling and electrical components according to the lesson learned during on-site deep dive. Added task according to the gas components.