amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, FUEL STORAGE TANKS - 8
APM Object	BLDG.FUELSTOR
APM EC	AMZ.BLDG.FUELSTOR
BBM Handbook Title	Fuel Storeage Tanks
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jan-25	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	8	**Related CT Areas:**	CT.ENVIRO.OIL			**Assets included in this PM:**	FUEL STORAGE TANKS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Fuel Storeage Tanks - Emergency Fuel Systems
Typically a tank which holds diesel for the fire pump system.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note: This PM is designated to all fuel systems used on site to supply generators and engine driven pumps like sprinkler pumps.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Fuel system	Are all components labeled correctly			PM			PM				
2	Fuel system	Visual inspection of all fuel system components for leakages			PM			PM				
3	Functional cleaning	Carry out a functional cleaning of the fuel system			PM			PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)			PM			PM				
5	Fuel pump - elec. & mech.	Inspect pumps for damage, corrosion and unusual noise (if fuel pump is installed)			PM			PM				
6	Fuel pump - elec. & mech.	Is the device properly fixed -> retighten if required (if fuel pump is installed)			PM			PM				
7	Fuel pump - elec. & mech.	Check if the pump is functioning correctly (if fuel pump is installed)			PM			PM				
8	Fuel filter	Change fuel filter			PM			PM				
9	Valves	Check valves for leakage, corrosion & damage			PM			PM				
10	Valves	Check all valves, incl. automatic & safety valves for correct function			PM			PM				
11	Tank	Check fuel tank for leakage corrosion & damage			PM			PM				
12	Monitoring	Check position/limit value transmitter and limit position switch for correct function			PM			PM				
13	Monitoring	Calibrate all sensors and check correct alarm indication						PM				
14	Final Check	Check the O&M manual and tank permit and carry out additional required tasks			PM			PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed APM Description according to the BBM Handbook.
Removed the Grease bearing task because it is not applicable to this kind of pump. Removed task regarding CE certification.
Jan 2025 - Added tasks to fulfill Compliance Standards requirements and changed WO type from `SC`to `PM`