amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, GREASE SEPARATOR - 5
APM Object	BLDG.GREASESEP
APM EC	AMZ.BLDG.GREASESEP
BBM Handbook Title	Grease Separator– Interceptors (Waste water containing grease)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	5	**Related CT Areas:**	CT.ENVIRO.INTERCEPTOR	**Assets included in this PM:**	GREASE SEPARATOR	**Schedule With:**	BLDG.OILSEP				

Description of System / Technology (According to BBM Handbook)

Grease Separator Interceptors (Waste water containing grease)
ACO Grease Capture removes fat, oil and grease from waste water before it enters the drainage system and protects against blockages and the build up of Fatbergs. Mainly used in kitchen environments.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.
Note - The drainage system to be checked within this maintenance is the pressure pipe system.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Guideline	If there are signs of clogging, schedule a CCTV inspection asap			PM			PM				
2	Documentation	Is the documentation of installed BBA available & complete						PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)			PM			PM				
5	Safety	Test all safety relevant switches						PM				
6	Separator unit	Check pumps, pipes, chambers and attachments for damage, corrosion, correct suspension & leakage			PM			PM				
7	Separator unit	Visual inspection of the water level			PM			PM				
8	Separator unit	Empty & clean the unit (inside & outside) –In Spain it is mandatory (compliance) every 6 months						PM				
9	Separator unit	Check for any signs of leakage			PM			PM				
10	Separator unit	Empty unit & carry out a functional celaning the unit (inside & outside)			PM			PM				
11	Separator unit	Clean and check function of backflow prevention						PM				
12	Separator unit	Check correct function and alarms of the system			PM			PM				
13	Pump & panel	If more than 1 pump installed, check if pumps starts one after the other						PM				
14	Pump & panel	Check the pumps for unusual noise & vibration (bearing and impeller)						PM				
15	Pump & panel	Measure power consumption of the pumps and compare to design						PM				
16	Pump & panel	Are all cables properly routed						PM				
17	Pump & panel	Are all cables, terminal blocks & devices properly labeled or marked						PM				
18	Pump & panel	Are all metal parts of the unit connected to the protection earth (ground)						PM				
19	Pump & panel	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
20	Pump & panel	Visual check of cable connections such as pinched insulation in the contact area						PM				
21	Pump & panel	Visual check for the protection against direct contact with live parts						PM				
22	Pump & panel	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
23	Drainage pipe system	Are the pipes on the pressure site installed correctly, free from damage and are the suspensions ok						PM				
24	Valves	Check correct function of all manual & automatic valves						PM				
25	Valves	Check valves for corrosion, dirt deposits and leakage						PM				
26	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM description as shows the BBM Handbook.Removed task regarding CE certification.