amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, ENTRANCE SPEED GATES - 4
APM Object	BLDG.SPEEDGATE
APM EC	AMZ.BLDG.SPEEDGATE
BBM Handbook Title	Entrance Speed Gates
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	4	**Related CT Areas:**	CT.WORK.AUTOGATE-PEDESTRIAN			**Assets included in this PM:**	ENTRANCE SPEED GATES	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Entrance Speed Gates - Similar to turnstiles, a mechanical gate allowing only one person at a time to pass through.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment available & complete						PM				
2	Safety	Check the safety devices for correct function						PM				
4	Speed gate	Visual inspection of the buttons, card reader, motion detector and opto-sensor for damage						PM				
5	Speed gate	Are there any visual damage at the door leaf						PM				
6	Speed gate	Check the light barrier on both sides and clean to maintain functionality if necessary						PM				
7	Speed gate	The Speed gate does not close as long as there are objects in the closing area.						PM				
8	Electrical components	The cables are routed and fixed properly						PM				
9	Electrical components	Electrical terminations are secure						PM				
10	Electrical components	Check connections to fire system and verify the opening when the signal is activated.						PM				
11	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed ENTRANCE TURNSTILES from APM Description Cell.Removed task regarding CE certification.