amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	BUILDING, TOILETS - 14
APM Object	BLDG.TOIL
APM EC	AMZ.TOILET.BLOCK
BBM Handbook Title	Toilets
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Dec-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	TBC	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	14	**Related CT Areas:**	Not Identified			**Assets included in this PM:**	TOILETS - HAND DRYER	**Schedule With:**	BLDG.DISABL.CLLPNT BLDG.DRAIN		

Description of System / Technology (According to BBM Handbook)

Toilets

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Room	The mirrors are free from damage			SC							
2	Room	The tiles and seals are free from damage			SC							
3	Room	The doors, door locks and partitions free from damage and functioning properly			SC							
4	Room	The ceiling plates are free from damage and no leakage is visible			SC							
5	Room	Are any installations damaged or loose (e.g. picture frame, dispenser, etc.)			SC							
6	Room	The light is working properly and is free from damage			SC							
7	Water supply & drainage	Check the wash basin drainage for leaks and blockages if easily accessible If not, check for water accumulation on the floor			SC							
8	Water supply & drainage	The faucets are functional and free from damage			SC							
9	Hand Dryer	Check the hand dryer for damage and correct function			SC							

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.