amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	ELECTRICAL SYSTEM, LOW VOLTAGE, ELECTRICAL CABINETS - 11
APM Object	ELEC.LV.CABS
APM EC	AMZ.ELEC.LV.CABS.GRP
BBM Handbook Title	Low Voltage Electrical Cabinet
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	11	**Related CT Areas:**	CT.ELEC.ELECINST CT.ELEC.FIXEDWIRE CT.ELEC.RCDMETER CT.ELEC.TVSS CT.ELEC.THERMAL	**Assets included in this PM:**	ELECTRICAL CABINETS	**Schedule With:**	ELEC.MET ELEC.LV.BSBR ELEC.LV.PFC ELEC.LV.SWBD BLDG.EARTHING				

Description of System / Technology (According to BBM Handbook)

The function is to distribute power from a main electrical circuit to several assets. It should include fuses to protect the output cables due to diameter reduction.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the panel/cabinet clean - free from debris						PM				
2	General check	Is the air filter of the electrical panel/cabinet clean -> clean or change if necessary						PM				
3	General check	Is the cooling fan operating appropriately and doesn`t make any unusual noise						PM				
4	General check	Visual check of the panel outside & inside for damage & missing components						PM				
5	General check	Are there any alarms indicated					PM	PM				
6	General check	Are any circuit breakers tripped					PM	PM				
7	General check	Are disconnecting devices lockable in the open position (LOTO)						PM				
8	General check	Are the circuit diagrams and relevant technical documentation available and complete						PM				
9	General check	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
10	Thermographic scan	Perform thermographic scans & create a WO for over-temperature to determine the root cause					PM	PM				
11	Thermographic scan value	Add a detailed note for all over-temperature measurements -> list the location and temperature -> Upload the thermographic scan					PM	PM				
12	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
13	Electrical components	Visual check for the protection against direct contact with live parts						PM				
14	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
15	Electrical components	Are all cables properly routed						PM				
16	Electrical components	Are all cables, terminal blocks & devices properly labeled or marked						PM				
17	Electrical components	Test all safety relevant switches						PM				
18	Electrical components	Test and maintain surge protection device according to manufacturer recommendation						PM				
19	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
20	Electrical components	Are all metal parts correctly connected to the protection earth (ground)						PM				
21	Electrical components	Is the ground connection to the building ground as per design						PM				
22	Functional cleaning	Damp clean the cabinet & fan if dusty						PM				
23	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.Removed task regarding CE certification.