amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, FIRE ALARM PANELS - 10
APM Object	FIRE.DET.ALRMPNL
APM EC	AMZ.FIRE.ALRMPNL.GRP
BBM Handbook Title	Fire Alarm Panels
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS			**Assets included in this PM:**	FIRE ALARM PANEL - REMOTE POWER SUPPLY - DIALER	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

A component of the fire alarm system that receives signals from initiating devices or other fire alarm control units and processes these signals to determine part or all of the required fire alarm system output function(s). Fire alarm panel is also known as a Fire Alarm Control Unit (FACU)

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency. Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	System Health	System health check - Check if there are any alarms, warnings etc indicated on the fire alrm panels. -> If yes identify & eliminate the root cause	SC									
2	System Health	Compare alarm list with the entries in the logbook and if necessary, determine the alarm cause						PM				
3	System Health	Background memory/event memory for deviations or examine and assess special events						PM				
4	General check	Visual check of the equipment for damage, loose- & missing components						PM				
5	Documentation	Is the documentation available and complete						PM				
6	Documentation	Are the circuit diagrams and relevant technical documentation available, complete & correct						PM				
7	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
8	Documentation	Are all required codes, passwords, etc. to activate & deactivate the system available						PM				
9	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
10	Battery & Charger	Check the EOL recommended by manufacturer and schedule an exchange						PM				
11	Battery & Charger	Check the batteries for leakage or damage						PM				
12	Battery & Charger	Load test of the batteries according to the manufacturer's specifications						PM				
13	Functional test battery	Simulate a power outage & check the system for correct function						PM				
14	Electrical components	Is the air filter & grid of the cooling inlets clean -> vacuum or change filter if necessary						PM				
15	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
16	Electrical components	Visual check for the protection against direct contact with live parts						PM				
17	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
18	Electrical components	Are all cables properly routed						PM				
19	Electrical components	Are all components properly labeled or marked						PM				
20	Electrical components	Are all components properly attached						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
24	Cause and effect	Check for correct output signal according to fire matrix						PM				
25	Obscuration	Check the obscuration rate of detectors and schedule replacement if it exceeds manufacturer specifications or as required						PM				
26	Dialer	Confirm correct function of the dialer and the backup battery						PM				
27	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM Object fromFIRE.DET.FIREALRM to FIRE.DET.ALRMPNL according to the last OCB updates. Removed 3M, 6M, 24M frequencies.
January 2025- Changing component to Obscuration in task 25.