amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, PUBLIC ADDRESS SYSTEM - 10
APM Object	FIRE.DET.COMM
APM EC	AMZ.FIRE.EVAC
BBM Handbook Title	Public Address System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.EVACUATION			**Assets included in this PM:**	PUBLIC ADDRESS	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Public Address System - These devices are designed for broadcasting crystal clear audio messages/live announcements during day-to-day operations or any emergency situations, helping towards safe evacuation.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	General check	Is the room properly ventilated			SC			PM				
2	General check	Are the components clean - free from debris						PM				
3	General check	Visual check of the equipment for alarms & damage & missing components			SC			PM				
4	Safety	Are disconnecting devices lockable in the safe position (LOTO)						PM				
5	Safety	Test all safety relevant switches for correct function						PM				
6	Documentation	Are the circuit diagrams and relevant technical documentation available and complete						PM				
7	Documentation	Are there manual entries in the drawings or technical documentation that indicate changes to the installation						PM				
9	Functional test	Perform a functional test of the equipment						PM				
10	Functional test	Simulate a power outage & check the system for correct function						PM				
11	Panel	Is the air filter & grid of the cooling inlets clean -> Please clean or change filter if necessary			SC			PM				
12	Panel	Are the cooling fans operating appropriately and doesn`t make any unusual noise						PM				
13	Panel	Are there any alarms indicated			SC			PM				
14	Panel	Are any breakers tripped - if yes identify the root cause			SC			PM				
15	Electrical components	Visual check of cable connections such as pinched insulation in the contact area						PM				
16	Electrical components	Visual check for the protection against direct contact with live parts						PM				
17	Electrical components	Were any obvious changes made (e.g. rewiring, hanging cables)						PM				
18	Electrical components	Are all cables properly routed						PM				
19	Electrical components	Are all components properly labeled or marked						PM				
20	Electrical components	Are all components properly attached						PM				
21	Electrical components	Are all metal parts connected to the protection earth (ground)						PM				
22	Electrical components	Is the ground connection to the building ground as designed?						PM				
23	Electrical components	Ensure all cable connections are correctly torqued according to manufacturers specification						PM				
24	Battery & Charger	Measure the voltage of each battery (disconnected) and plan for replacement if necessary						PM				
25	Battery & Charger	Measure the charging voltage and current before & after functional test						PM				
26	Battery & Charger	Compare to design specification & plan component exchange in case of an issue						PM				
27	Battery & Charger	Check the internal uninterruptable voltage supply of the unit						PM				
28	Battery & Charger	Check the batteries for leakage or damage						PM				
29	Battery & Charger	Check the fluid level of the batteries and recharge if required						PM				
30	Functional cleaning	Carry out a functional cleaning if required						PM				
31	Final Check	Check the O&M manual and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Changed the APM Object from FIRE.DET.BOSS to FIRE.DET.RADIO according to the last OCB updates. Removed thermal scan task because it's part of the LV inspection. Removed task regarding CE certification.Removed task regarding CE certification.