amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, MANUAL CALL POINTS - 10
APM Object	FIRE.DET.MCP
APM EC	AMZ.FIRE.MCP.GRP
BBM Handbook Title	Manual Call Points (MCP)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS			**Assets included in this PM:**	MANUAL CALL POINT	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

It is a device for the manual initiation of a fire alarm.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Manual Call Point	Verify that reset keys are available for all relevant stakeholders						PM	PM			
2	Manual Call Point	Visual check of the MCPs & covers for damage, loose- & missing components						PM	PM			
3	Manual Call Point	Change battery of the MCP cover							PM			
4	Manual Call Point	Carry out a functional test of the cover alarm						PM	PM			
5	Manual Call Point	Ensure that the seal is present after task completion						PM	PM			
6	Manual Call Point	Test of all Manual Call Points						PM	PM			
7	Manual Call Point	Are all Manual Call Points free from damage						PM	PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - New PM according to the OCB structure.