amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE DETECTION SYSTEM, SMOKE - 10
APM Object	FIRE.DET.SMOKE
APM EC	AMZ.FIRE.SMOKE.GRP
BBM Handbook Title	Smoke Detector
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certificates	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.FAS CT.FIRE.SMOKEDETECT	**Assets included in this PM:**	SMOKE DETECTOR	**Schedule With:**	FIRE.DET.HEAT FIRE.DET.SMOKEHEAT FIRE.DET.SMOKEHEATCO FIRE.DET.BEAM FIRE.DET.DUCT FIRE.DET.LINEAR FIRE.DET.FLAME FIRE.DET.ASD				

Description of System / Technology (According to BBM Handbook)

Smoke detector is a fire-protection device that automatically detect and gives a warning of the presence of smoke.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

IMPORTANT
Ensure that a different group of devices are tested each quarter so that all devices will be tested within one year

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Detection	Test all detectors, including the associated display of the origin of the message						PM	PM			
2	Detection	Is there any debris around detector that could create a False Activation						PM	PM			
3	Detection	Check all accustic and illumintaed signals for correct function						PM	PM			
4	Detection	Check for change in room or use of room. Are the detectors maps updated?						PM	PM			
5	Battery	Ensure battery is properly charged and replace if applicable						PM	PM			
6	Battery	Replace battery if applicable							PM			

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Removed 3M,6M, 24M frequencies because 12M frequency can be forecasted by groups along the year.