amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, FIRE DOORS HOLD OPEN SYSTEM - 10
APM Object	FIRE.FLS.HOLDDOOR
APM EC	AMZ.FIRE.HOLDDOOR.GRP
BBM Handbook Title	Fire Door Hold Open Device
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jun-24	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician with relevant certification	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.DOORS			**Assets included in this PM:**	HOLD OPEN FIRE DOOR	**Schedule With:**	FIRE.FLS.FIREDOOR BLDG.EMERDOOR		

Description of System / Technology (According to BBM Handbook)

The hold-open device is a system for keeping fire doors open. This means that a hold-open device (also known as a hold-open system, or FSA for short) keeps the fire door open and closes it automatically in the event of a fire.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of installed equipment available & complete						PM				
2	Open hold system	Test the system smoke detector and check system for correct function						PM				
3	Electrical components	Check the control elements for damage and correct function						PM				
4	Electrical components	Check if cables are properly routed and free from damage						PM				
5	Electrical components	Ensure all cable terminations are secure						PM				
6	Functional cleaning	Carry out a functional cleaning of all relevant components						PM				
7	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, aligmment with CT.
June 2024 - New PM for FIRE.FLS.HOLDDOOR.