amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE LIFE SAFETY SYSTEM, WAREHOUSE SMOKE EXTRACTION - 10
APM Object	FIRE.FLS.SMOKEEXT
APM EC	AMZ.FIRE.SMOKEEXT
BBM Handbook Title	Smoke Extraction Fans (Warehouse)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician certified in the electrical field	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.SMOKEVENTS			**Assets included in this PM:**	SMOKE EXTRACTION FAN	**Schedule With:**	-		

Description of System / Technology (According to BBM Handbook)

Smoke extract fans extract smoke and heat created from a fire for long enough for occupants to escape from danger

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly								
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the system available & complete						PM				
2	General check	Check air inlets for obstacles blocking the airflow						PM				
3	Functional test	Test the fire case matrix						PM				
4	Functional test	Confirm that equipment operates in accordance with the fire case matrix, incl. the activation of smoke extraction fans and the proper functioning of associated automatic dampers and doors, etc.						PM				
5	Measurement	Measure the power consumption of all smoke extraction fans & compare to design						PM				
6	Measurement	Measure the exhaust air volume flow of all smoke extraction fans & compare to design						PM				
7	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.