amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SPECIAL HAZARDS SYSTEM, KITCHEN HOOD - 10
APM Object	FIRE.SPHZRD.KITCHEN
APM EC	AMZ.FIRE.KHOOD
BBM Handbook Title	Kitchen Hood Suppression System
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Sep-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	TBC	**Pricing template Position:**	10	**Related CT Areas:**	CT.HVAC.GASDET CT.SAFE.FLAMGASDETECT			**Assets included in this PM:**	KITCHEN HOOD	**Schedule With:**	NO INFO		

Description of System / Technology (According to BBM Handbook)

Automatic fire extinguishing systems pro vided for the protection of grease removal devices, hoods, duct systems, and cooking equipment.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Piping	Ensure the piping system is free from damage, corrosion, and leaks						PM				
2	Piping	Ensure nozzles are clean and adequate for suppression purposes						PM				
3	System	Verify that system pressure meets code and design specifications						PM				
4	System	Confirm that all valves are in the correct position						PM				
5	Electrical components	Are there any alarms indicated						PM				
6	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

Aug 2024 - New PM after OCB update