amazon rme

AMAZON BASE BUILDING MAINTENANCE STANDARD

GLOBAL CENTRAL RME STANDARDS & COMPLIANCE

Task Title	FIRE SUPPRESSION SYSTEM, HYDRANT - 10
APM Object	FIRE.SUP.HDRNT
APM EC	AMZ.FIRE.HDRNT
BBM Handbook Title	Hydrant (Hose Cabinets,Fire Hydrants or Wall Hydrants)
General tasks always required	Follow safety procedures - e.g. 1MRA, LOTO, PPE, etc. Ensure that all WOs are carried out by qualified, certified staff with appropriate familiarisation and supervision as required Add notes for each observation and create a FWO if necessary to eliminate defects Use appropriate tools, chemicals and industry standard practices (RME policy permitting) Ensure relevant logs, readings and certification is uploaded to APM prior to WO closure These tasks are based on industry guidance, SME knowledge and HIE learning. Please ensure vendor specific requirements are followed. To suggest improvements please raise a SIM SIM - Link to SIM template

Last Update: (Version)	Jul-23	**Geo Applied:**	Intl APM Instance	**F-Gas**	Not Identified	**Activies may be covered by No-Go restrictions:**	TBC	**Special Certificaion Required:**	TBC	**Delivered By:**	Carried out by trained on site technician	**OCB:**	BBM
Evidence for CT:	YES	**Pricing template Position:**	10	**Related CT Areas:**	CT.FIRE.HYDRANTS			**Assets included in this PM:**	PRESSURIZED HYDRANT - FIRE HYDRANT	**Schedule With:**	FIRE.SUP.SPRK FIRE.SUP.WTRTNK FIRE.SUP.VALV FIRE.SUP.WETRISERS		

Description of System / Technology (According to BBM Handbook)

A fire hydrant is a connection point by which firefighters can tap into a water supply. It is a component of active fire protection.

Additional Information

All sites with the above listed Base Building Asset should conduct routine maintenance and inspections according to this standard PM package. The Amazon maintenance standard supports compliance, reduces safety risks,improves asset reliability & efficiency.
Some maintenances captures several assets within one PM package -> Ensure that corrective/reactive maintenance for assets where proactive maintenance is contained under another asset is created against the original asset.

Task Index	Component	Tasks	Tasks Nested for frequencies > weekly									
			Daily	Weekly	Monthly	3 Monthly	6 Monthly	12 Monthly	24 Monthly	36 Monthly	48 Monthly	60 Monthly
1	Documentation	Is the documentation of the equipment including location info available & complete						PM				
2	Equipment check	Check the wall hydrant & cabinet is free from damage, fixed properly & no leakage visible				SC						
3	Equipment check	Check for the correct maintenance labels & overdues				SC						
4	Equipment check	Check if the cabinets are closed and sealed				SC						
5	Equipment check	If the sealing is damaged - check if the hose connection is correct, all components (inc. extinguisher - if located in same box) are available, free from damage or manipulations and appl a new seal				SC						
6	Equipment check	Check if the hose connection is correct, all components (inc. extinguisher - if located in same box) are available, free from damage or manipulations and stick a new seal						PM				
7	Equipment check	Check hose connection devices according to local reuqirements (e.g. DIN EN 671-3)						PM				
8	Equipment check	Measure water flow, flow and static pressure at all hose connection valves						PM				
9	Equipment check	Check extinguishing water lines for stability (2 min at 1.5 times nominal pressure).						PM				
10	Equipment check	Check limit switches (if available) electrically and mechanically						PM				
11	Equipment check	Check the shut-off body for mobility and ease of movement						PM				
12	Equipment check	Check the spindle seal for leaks after test						PM				
13	Equipment check	Check the function of the claw, square and dirt deflector						PM				
14	Equipment check	Check that the claw cover is correctly seated on underground hydrants						PM				
15	Equipment check	Check the function and condition of the drop jacket (if present)						PM				
16	Equipment check	Check the filling and emptying station and the free spout						PM				
17	Equipment check	Extinguishing water lines for leaks (10 min at nominal pressure) check						PM				
18	Equipment check	Check & adjust the pressure reducer (if necessary)						PM				
19	Equipment check	Clean the stone trap						PM				
20	Equipment check	Check for easy findability, free reachability/accessibility						PM				
21	Equipment check	Dirt on the claw and protective cover of underground hydrants to free						PM				
22	Equipment check	Check that the jacket pipe is completely empty						PM				
23	Equipment check	Check the integrity of the claws for the upper tube insert						PM				
24	Equipment check	Check mudguard condition						PM				
25	Equipment check	Condition and correct fit of the sealing cap of underground hydrants						PM				
26	Equipment check	Check the function and condition of the cover cap(s) for pillar hydrants						PM				
27	Equipment check	Check waterquality through short-term water flow (sand, stone, etc.)						PM				
28	Equipment check	Secure the hydrant fasteners						PM				
29	Final Check	Check the O&M manual & local requirements (e.g. fire protection concept & building permit) and carry out additional required tasks						PM				

Change Log

July 2023 - First issue in new format. Simplification of task scope, alignment with CT.
June 2024 - Adding new category according to the last OCB version.